

(A) ITEM - ADDITIONAL QUANTITIES FOR LEVELING

An additional _ tons of asphaltic concrete (\$) shall be included with the overlay for leveling purposes. This quantity shall be reflected in the general notes on the project plans.

(B) ITEM - ADDITIONAL QUANTITIES FOR LEVELING

An additional _ tons of asphaltic concrete (\$) shall be estimated for leveling purposes. At areas designated by the Engineer, a total of _ tons of this material shall be used for wire guided or laser leveling prior to the overlay. The placement and compaction of this material shall be as directed by the Engineer. The remaining _ tons shall be included with the overlay for leveling purposes. These quantities shall be reflected in the general notes on the project plans.

DESIGNER:

Item (A) is to be used on overlay projects where the existing roadway has a fairly rough ride or is out of section. On overlay projects that have isolated areas that are extremely out of section an additional AC tonnage should be estimated for blade laid or wired guided leveling of these areas prior to the overlay. When blade laid or wired guided leveling is included Item (B) is to be used.

\$ List AC type (3/4, 1/2, Misc. Str., etc.) whichever is applicable.