

ITEM - ANCHOR SLABS

The work under this Item shall consist of constructing Anchor Slabs at the approaches and departures to overpass structures as per details shown in the plans. Anchor slabs shall be constructed at the following locations:

Location	Description	No. of Slabs

A total of _ anchor slabs will be required.

DESIGNER:

The following additional requirements shall apply when constructing Anchor Slabs on existing concrete pavements:

Anchor Slabs shall be constructed to the full width of the existing concrete pavement. The Anchor Slabs will need to be built by stage construction to facilitate traffic control. Each stage shall be built such that reinforcing steel is continuous through the longitudinal joint locations.

All Concrete shall be accelerated strength concrete as specified in Section 402-3.02 of the Standard Specifications. Texturing shall be as specified in Section 401-3.04(F) of the Standard Specifications.

The construction of the Anchor Slabs will require removal of the existing approach slabs and a sufficient number of existing PCCP slabs to accommodate the new Anchor Slabs. No measurements or payment will be made for removal or disposal of the existing approach slab or existing PCCP slabs; the cost being considered as included in the cost of the contract item.