

** USE THIS SPECIFICATION ON PROJECTS INVOLVING BORROW, **
SUBBASE, BASE, MATERIALS FOR CONCRETE
STRUCTURES, AND SURFACING MATERIALS.

** USE IN CONJUNCTION WITH STORED SPECIFICATION 104ENVIR **

(1001MATL, 12/14/09)

SECTION 1001 MATERIAL SOURCES: of the Standard Specifications is revised to read:

1001-1 Description:

The work under this section shall consist of the procuring of borrow, topsoil, subbase and base materials, mineral aggregates for concrete structures, surfacing, and landscape plating, from sources either designated on the project plans or in the Special Provisions or from other sources.

1001-2 General:

The contractor shall determine for itself the type of equipment and work required to produce a material meeting the specifications.

Sites from which material has been removed shall, upon completion of the work, be left in a neat and presentable condition. Where practicable, borrow pits, gravel pits, and quarry sites shall be located so that they will not be visible from the highway.

The contractor shall provide an Environmental Analysis, as specified in Subsection 104.12, for any source proposed for use regardless of whether an approved Environmental Analysis exists for the site.

In accordance with Subsection 104.12, the contractor may incorporate an existing Environmental Analysis approved after January 1, 1999, provided that the analysis is updated as necessary to be in compliance with current regulations and with the contractor's planned activities.

It shall be the responsibility of the contractor to conduct any necessary investigations, explorations, and research, on-site and otherwise, before and after submitting the bid proposal, to satisfy itself that the specified quantity and/or quality of material exists in any proposed material source.

The Department makes no representation regarding quality or quantity of materials in any source.

1001-2.01 Material Sources in Flood Plains:

Any material source located in a flood plain and proposed for use on the project shall be reviewed by the appropriate agency having flood plain management jurisdiction for the area

in which the proposed source is located. The contractor shall obtain a letter from the governing flood plain agency addressed to the Engineer, certifying that the location of the proposed source conforms to the requirements of the floodplain management agency.

Contractors seeking a flood plain material source are cautioned that Section 404 of the Clean Water Act may prevent use of the source unless an appropriate permit is first obtained from the U.S. Army Corps of Engineers.

Except for surplus material from agency-administered flood control management projects, borrow material shall not be obtained from any area situated in the 100-year flood plain of any stream or watercourse, and located within one mile upstream and two miles downstream of any highway structure or surfaced roadway crossing. Surplus material from agency-administered flood control management projects may be used as borrow material only if the contractor submits written evidence to the Engineer that the flood control agency project was fully designed and funded prior to the date of advertisement for bids on the Department project.

Material sources in flood plains located on Native American Indian Reservations will be considered for use based on an individual analysis. The analysis shall include a review of applicable land use plans, flood plain management plans, environmental plans, applicable laws and regulations pertaining to Indian Reservations, and an engineering analysis of the effects on any highway facility or structure. The contractor shall obtain from the Native American Tribal Council all permits, licenses, and approvals and present to the Department for review. The Department will review each request on a case by case basis.

1001-2.02 Information Available:

The Department's Materials Group maintains a listing of materials sources for which a completed Environmental Analysis is available and the landowner has allowed the source to be placed on the list. In addition, Materials Group maintains files for those sites for which the Department holds an easement, license, permit, lease, or other right, as well as a General Plan of Operation and Restoration. The contractor may contact the Materials Group at (602) 712-7231 for information and may review the files located at 1221 N. 21st Avenue, Phoenix, Arizona 85009-3740.

Contractors are advised that an agency having jurisdiction over the source, such as the Forest Service, Bureau of Land Management, Bureau of Reclamation, the State Land Department, etc., or the owner, as a condition to the use of the source, may have imposed certain obligations. The contractor who uses such a source shall assume full contractual responsibility for any and all of these obligations imposed either by the agency having jurisdiction or by the owner. Contractors considering such a source shall make themselves fully aware of any and all requirements imposed by the Department and the landowners.

The contractor may propose the use of these or other sources, provided that all requirements of the specifications have been met.

It shall be the responsibility of the contractor to comply with the provisions of the Environmental Analysis and with current laws, rules, and regulations.

The Department makes no representation regarding quality or quantity of materials in any source.

It shall be the responsibility of the contractor to conduct any necessary investigations, explorations and research, on-site and otherwise, to satisfy itself that the specified quantity and/or quality of material exists in any material source.

1001-2.03 Usage of Materials:

Approval of the use of any source shall be limited to the specific contract and purpose for which the use of the source was obtained.

1001-2.04 Royalty Charges:

If the Engineer approves a source for which the Department holds an easement, license, permit, lease, or other right with the landowner or controlling agency that includes requirements for the payment of royalties, the amount of the royalty charges and the name and address of the party to whom royalties are to be paid will be available from the Materials Group, 1221 N. 21st Avenue, Phoenix, Arizona 85009-3740.

Prior to the time of final payment, the contractor shall furnish the Engineer with evidence that all royalty charges have been paid. Such evidence shall consist of a waiver, release, or other written acknowledgement from the owner that all of the contractor's obligations to the owner have been met. In the event that royalty charges have not been paid, the Department reserves the right to make such payment and to deduct the amount of such payment from monies due the contractor.

The final billing and payment for material extracted from sources under the jurisdiction of the State Land Department will include a small administrative charge based on the total amount of royalties due for materials removed.

Upon receipt of the final billing from the Department of Transportation, the contractor shall mail a check, payable to the State Land Department, addressed as follows:

Arizona Department of Transportation
Field Reports Section
206 South 17th Avenue
Phoenix, Arizona 85007

1001-2.05 Performance Bonds:

If sources are under the jurisdiction of either the State Land Department or the Bureau of Land Management, the contractor shall secure a performance bond. A fully executed copy of the bond shall be furnished to the Engineer along with evidence that a fully executed copy has been sent to the State Land Department or the Bureau of Land Management.

The form of the Performance Bond will be available from the Materials Group, 1221 N. 21st Avenue, Phoenix, Arizona 85009-3740. For pits under the jurisdiction of the Bureau of Land Management, the surety shall be a company listed under "Surety Companies Acceptable on Federal Bonds." This list is published annually as of July 1 in the Federal Register.

Performance bonds shall be conditioned upon the compliance with the requirements of the State Land Department and the Bureau of Land Management and the requirements of the specifications for the clearing of pit sites, the removal of material and the cleaning up of pit sites.

Copies of fully executed performance bonds shall be mailed as follows:

State Land Commission	Bureau of Land Management
State Land Department	Manager, Land Office
1624 West Adams Street	222 North Central Avenue
Phoenix, Arizona 85007	Phoenix, Arizona 85004

1001-2.06 Sampling and Testing:

The results of any sampling and testing accomplished by the Department will be available from the Materials Group, 1221 N. 21st Avenue, Phoenix, Arizona 85009-3740.

1001- 2.07 Plan of Operation and Restoration:

The contractor shall determine whether the Department holds an easement, license, permit, lease or other right, for any proposed material source. For such sites, a project-specific Plan of Operation and Restoration will be required. The contractor shall obtain a copy of the related document and the Department's General Plan of Operation and Restoration for the proposed site from the Materials Group. The contractor shall prepare and submit to the Engineer a project-specific Plan of Operation and Restoration which shall follow the format of the Department's General Plan of Operation and Restoration, and shall take into account the requirements of the Environmental Analysis, as well as any restrictions placed on the use of the source by the landowner or agency.

The proposed source will not be approved without an approved project-specific Plan of Operation and Restoration. Approval of the contractor's project-specific plan does not constitute approval of the use of the source.

The contractor shall identify and provide a person in charge of the operation. That person shall maintain copies onsite of the Department's General Plan of Operation and Restoration, the contractor's approved project-specific Plan of Operation and Restoration, the current Environmental Analysis, and the license and permits issued to the Department by the landowner or agency.

1001-3 Proposed Source:

1001-3.01 Approval Requirements:

(A) General:

The contractor shall promptly advise the Engineer as to the source that it proposes to use.

The contractor acknowledges that all the conditions set forth in this subsection shall be met prior to the source being approved for use.

Other than sampling and testing, the requirements of this subsection shall be completed prior to initiation of any activities that disturb the existing conditions at the proposed source.

The contractor further acknowledges that no additional compensation will be made on account of any delays in preparing or modifying the Environmental Analysis, obtaining approval for the use of a source, or the failure to obtain approval of a source. An extension of contract time may be granted only in accordance with Subsections 104.12 or 1001-3.01(B)(4).

Regulatory changes, specification changes, or other reasons may preclude the approval of a materials source. The contractor acknowledges that the Department may refuse to approve a material source even if the Department had approved the source for other projects.

If all of the requirements for approval of a materials source have been accomplished for the project, and the Engineer has approved the source for use on the project and, subsequent to that approval, the Environmental Analysis is rescinded, the contractor may request a revision to the contract in accordance with Subsection 104.02 and 108.08. In reviewing the contractor's request, the Department will take into account the following factors. Additional factors may be considered.

- (1) Whether the contractor was in compliance with the requirements of the Environmental Analysis and, if applicable, the site-specific Plan of Operations and Restoration.
- (2) Whether the reasons for rescinding the approval were reasonably foreseeable.
- (3) Whether the action taken was the result of regulatory changes.
- (4) Whether deficiencies unrelated to the Environmental Analysis may have rendered the source unacceptable.
- (5) Whether rescinding the approval was the sole cause of any impact to controlling activities on the project.

(B) Specific Conditions For Approval:

The use of a source will require written approval by the Engineer. No approval will be given until the contractor has complied with the following conditions:

- (1) The contractor has submitted an Environmental Analysis, as specified in Subsection 104.12, of the source proposed for use and the Department has reviewed the analysis and satisfied itself that the use of such source will not have an adverse social, economic or environmental impact. The requirements of Subsection 1001-3.01 shall be completed prior to initiation of any activities that disturb the existing conditions at the proposed source, except for exploring test areas as specified in Subsection 1001-3.02.
- (2) The contractor has furnished the Engineer with evidence that he has secured the rights to the source, including ingress and egress.
- (3) The Department has determined that the material from the proposed source not only meets the requirements, but is also compatible with the established project design criteria developed by the ADOT Materials Group and based on the soil support value of the embankment; and the sampling and testing as herein specified has been satisfactorily completed.
- (4) The contractor has furnished a fully executed copy of the Performance Bond as specified in Subsection 1001-2.05.
- (5) When required, the contractor has submitted, and the Department has approved, the site-specific plan of operations and restoration as specified in Subsection 1001-2.07.

The contractor shall also notify the Arizona Department of Agriculture, in accordance with the Arizona Native Plant Law, at least 30 days prior to any clearing operations of less than 40 acres on private land, 60 days prior to clearing operations of 40 or more acres on private land, and 60 days prior to any clearing of state land, regardless of size. If the Engineer is convinced that the contractor has made every effort to comply with the provisions of the Arizona Native Plant Law in contacting the Department of Agriculture, the Engineer will increase the number of contract days by the amount of time required for action by the Department of Agriculture. The increase will not exceed 45 calendar days and will be concurrent with any increase allowed for the preparation of the Environmental Analysis.

(C) Historical and Cultural Resources:

If the Department determines that the proposed use will have major adverse impact on cultural or historic resources, the Department will not allow the use the source.

(D) Permit from Navajo Nation:

For projects located on the Navajo Reservation, the Navajo Nation has adopted a permitting system for any sources, regardless of whether on or off the Navajo reservation, which are to supply material for projects located within its boundaries. No material source will be approved until the contractor submits a copy of the permit from the Navajo Nation allowing materials from the proposed source to be used on the project. For information concerning the permit, the contractor shall contact the Navajo Nation Historic Preservation Office.

1001-3.02 Testing Requirements:

The contractor shall furnish equipment and personnel and shall obtain representative samples of the material under the supervision of the Engineer. At the option of the contractor, the material shall be tested by either the Department or by a testing laboratory approved by the Department. The cost of all sampling and testing done for the purpose of attaining approval of any source, including the cost of supervision by the Engineer, shall be borne by the contractor.

If testing is performed by a testing laboratory, the contractor shall arrange for the samples to be delivered to the testing laboratory. Tests shall be performed using appropriate test procedures referred to in the sections of the specifications in which the specific material requirements are described.

The contractor shall make the arrangements necessary to see that the testing laboratory submits the results of the tests to ADOT Materials Group. The contractor shall submit to ADOT Materials Group sufficient quantity of material from the samples taken so that ADOT Materials Group may test the materials, at the Department's expense, and verify the results.

Exploratory sampling and testing activities conducted prior to the Department's approval shall be limited so as to cause the minimum amount of vegetation removal and surface disturbance required to obtain representative samples. The contractor shall not produce material, mobilize crushing equipment or clear a worksite prior to approval of the Environmental Analysis.

The contractor may request an exemption from the testing requirements specified in this subsection upon presentation of evidence to the satisfaction of the Engineer that the material that will be produced on the project is sufficiently similar to material that has been previously acceptable to the Department on projects with similar materials specifications.

No approval of the source shall be assumed, nor will it be made, until the Department has determined that the material meets the specified requirements.

The contract time will not be adjusted because of any time required by either the contractor or the Department to sample and test the material and to determine the quality of the material.

1001-4 Special Access:

The contractor may make a request to the Engineer to approve special access to a controlled access highway if special access is not shown on the project plans.

The request by the contractor shall be accompanied by an Environmental Analysis and by documents which specify the point(s) of access, the acquisition of right-of-way, the manner in which access will be attained, the traffic control plan, and crossovers, along with all other appropriate data which will allow the Engineer to evaluate its request. If the request is approved, a supplemental agreement shall be entered into.

All costs associated with the special access requested by the contractor shall be borne by the contractor, including, but not limited to, cattle guards, fences, gates and restoration work.

When access is not being utilized, gates shall be closed and locked. Upon completion of all operations, the area within the right-of-way that has been disturbed shall be restored to the condition existing prior to the contractor's operations.

The decision by the Engineer to deny a request by the contractor will be considered to be final.

1001-5 Operations at Source:

1001-5.01 General Requirements:

The contractor shall conduct its operations in such a manner as to preserve available materials in excess of project requirements.

The contractor shall notify the Engineer in advance of operations at the source. Notice shall be given before and after clearing and grubbing, and before and after cleaning up.

1001-5.02 Clearing and Grubbing:

Before beginning stripping, the contractor shall clear and grub the source as necessary to prevent the contamination of materials to be used in the work. Clearing and grubbing shall be in accordance with the requirements of Section 201, except that the resulting surface need not be leveled and vegetable matter need not be separated from any overburden which the Engineer determines to be unsuitable for any future use and which is to be wasted. Clearing and grubbing shall be limited to the area expected to be excavated and areas used for processing and stockpiling.

In the disposal of all tree trunks, stumps, brush, limbs, roots, vegetation and other debris removed, the contractor shall comply with the requirements of the Arizona Revised Statutes Title 49 Chapter 3 – Air Quality; and with the Arizona Administrative Code Title 18 Chapter 2 – Department of Environmental Quality – Air Pollution Control.

Burning will be permitted only after the contractor has obtained a permit from the Arizona Department of Environmental Quality, and from any other Federal, State, County or City Agency that may be involved.

When stripping is required, overburden shall be removed to the extent necessary to remove all undesirable materials and shall, at all times, be kept stripped at least five feet beyond the working face of the area being excavated.

The contractor shall comply with the requirements of the landowner or agency having jurisdiction over the land.

1001-5.03 Extraction of Materials:

Materials shall be removed from the source in a workmanlike manner and, when required, in accordance with the contractor's project-specific Plan of Operation and Restoration. In order to produce acceptable material in the amount and gradation required, it may be necessary for the contractor to do any or all of the following, along with any other similar operations usually associated with the extraction, processing and production of the particular material being produced:

- Move materials from one area to another.
- Perform additional screening.
- Remove, wash and waste material.
- Blend materials.
- Revise crushing methods.
- Remove deleterious materials such as clay balls, roots and sticks.

If the Engineer determines that the material in a source is stratified, all material except borrow shall be removed for the full depth in such a manner as to produce a uniform blend of the material. Placing the material from different areas and depths into a surge pile and removing material from the surge pile by cutting through the pile will be acceptable provided that a uniformly blended material is obtained.

Material sources located in drainage channels such as washes, riverbeds, etc., may experience seasonal variations in the depth of ground water. In order to produce the quantity of material estimated to be available, the contractor may be required to work below the water table.

1001-6 Fences and Cattle Guards:

Where the haul roads to material sources cross existing fence lines in areas where there is livestock of any kind, temporary cattle guards shall be installed by the contractor at each crossing.

The livestock operator or owner shall be contacted prior to the beginning of any operations and effective measures shall be taken and means provided by the contractor to prevent livestock from straying.

In operations where conditions will exist that are dangerous to livestock of any kind, temporary cattle guards and fence shall be installed around the pit area by the contractor to protect livestock.

Temporary cattle guards and fence installed by the contractor shall be removed and existing fence disturbed shall be replaced or reconstructed and all fence shall be left in as good condition as it was prior to the beginning of work.

1001-7 Cleaning Up:

All overburden and other undesirable materials removed and all piles of waste materials resulting from operations in the source shall be handled in accordance with the

requirements of the landowner or agency having jurisdiction over the land, the Environmental Analysis, the project-specific Plan of Operation and Restoration, if applicable, and all laws, rules and regulations. All debris shall be removed and disposed of and, if directed, all open test holes shall be filled. Unless otherwise required, the sides of sources shall be sloped and smoothed so that livestock can enter and leave the excavated area safely. Unless otherwise required, all haul roads shall be obliterated and, as far as practicable, the ground left in as good condition as it was prior to hauling.

1001-8 Method of Measurement and Basis of Payment:

Except as may be otherwise specifically provided for in this section or elsewhere, no measurement or direct payment will be made for any costs involved in the procuring of materials. Such costs shall be considered as included in the cost of contract items.