# 2011 Annual Report November, 2011



Arizona Department of Transportation Office of Environmental Services 206 South 17th Avenue, MD 102A Phoenix, Arizona 85007

Stormwater Management Plan 2011 Annual Report MS4 Permit No. AZS000018-2008



APPENDICES       iii         ACRONYMNS and DEFINITIONS       iv         EXECUTIVE SUMMARY       vi         1       GENERAL INFORMATION       1         2       ANNUAL REPORT CERTIFICATION       1         3       NARRATIVE SUMMARY OF SSWMP ACTIVITIES       2         3.1       ADOT Technical Documents       2         2.0       Outfall Inspection and Tracking       3         3.1       Public Access to Stormwater Documents       3         3.4       Illicit Discharges Eliminated       5         3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Eliminated       5         3.4.3       Illicit Discharges Eliminated       5         3.4.1       Illicit Discharges Reported to Other Jurisdictions       5         3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Site Tracking System       7         3.9.1       SWPPP Update       8         3.10.2       Inactive Sites - Group A       8         3.10.1       Active Sites - Group A       10	TAB	LES	iii
EXECUTIVE SUMMARY       vi         1       GENERAL INFORMATION       1         2       ANNUAL REPORT CERTIFICATION       1         3       NARRATIVE SUMMARY OF SSWMP ACTIVITIES       2         3.1       ADOT Technical Documents       2         3.2       Outfall Inspection and Tracking       3         3.3       Public Access to Stornwater Documents       3         3.4       Illicit Discharges Eliminated       5         3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Eliminated       5         3.5       Forsion Abatement Projects       6         3.6       Sonstruction Site Issues       7         3.8.1       Construction Site Issues       7         3.8.2       Construction Site Issues       7         3.8.1       Construction Site Issues       7         3.9.2       No Exposure Certification       8         3.10.1       Active Sites - Group A       8         3.10.2       Inactive Sites - Group A       8         3.10.3       Reclaimed Sites - Group C       10         3.10.4       Non-Mining Sites - Group C       10         3.10.5.1       Sites Removed from Inspection List	APP	ENDICES	iii
1       GENERAL INFORMATION	ACR	ONYMNS and DEFINITIONS	.iv
2       ANNUAL REPORT CERTIFICATION       1         3       NARRATIVE SUMMARY OF SSWMP ACTIVITIES       2         3.1       ADOT Technical Documents       2         3.2       Outfall Inspection and Tracking       3         3.3       Public Access to Stormwater Documents       3         3.4       Illicit Discharges       4         3.4.1       Illicit Discharges Reported to Other Jurisdictions       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions       5         3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPs       6         3.8       Construction Site Tracking System       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.9       Industrial Facilities       7         3.9.1       Notexposure Certification       8         3.9.2       No Exposure Certification       8         3.9.2       No Exposure Certification       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group C       10	EXE	CUTIVE SUMMARY	. vi
3       NARRATIVE SUMMARY OF SSWMP ACTIVITIES.       2         3.1       ADOT Technical Documents.       2         3.2       Outfall Inspection and Tracking.       3         3.3       Public Access to Stormwater Documents.       3         3.4       Ilicit Discharges       4         3.4.1       Ilicit Discharges Reported to Other Jurisdictions.       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions.       5         3.5       Erosion Abatement Projects.       6         3.6       Spills and Other Releases.       6         3.7       Maintenance Facility SWPPPs.       6         3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.1       Construction Violations.       7         3.9.1       SWPPP Update.       8         3.9.2       No Exposure Certification       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group A       8         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Numerice Sites – Group I       10         3.10.5.1       Sites Removed from Inspection List       13	1 (	GENERAL INFORMATION	1
3.1       ADOT Technical Documents       2         3.2       Outfall Inspection and Tracking       3         3.3       Public Access to Stormwater Documents       3         3.4       Illicit Discharges Eliminated       5         3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions       5         3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPPs       6         3.8.1       Construction Site Issues       7         3.8.2       Construction Violations       7         3.9.1       SWPPP Update       8         3.02       No Exposure Certification       8         3.10       Active Sites – Group A       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group C       10         3.10.4       Non-Mining Sites – Group C       10         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3.10.5.2       Site Plans and Training       13         3.10.5.2	<b>2</b> A	ANNUAL REPORT CERTIFICATION	1
3.2       Outfall Inspection and Tracking       3         3.3       Public Access to Stormwater Documents       3         3.4       Illicit Discharges       4         3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions       5         3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPPs       6         3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.9       Industrial Facilities       7         3.9.2       No Exposure Certification       8         3.0.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group C       10         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3.10.5.2       Site Plans and Training       13         3.10.5.2	3 N	NARRATIVE SUMMARY OF SSWMP ACTIVITIES	2
3.3       Public Access to Stormwater Documents.       3         3.4       Illicit Discharges.       4         3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions.       5         3.5.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPs.       6         3.8       Construction Site Tracking System       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations.       7         3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group I       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3.10.5.2       Site Plans and Training       13         3.1	3.1	ADOT Technical Documents	2
3.4       Illicit Discharges       4         3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions       5         3.5.       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPs       6         3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       No Exposure Certification       8         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group D       9         3.10.3       Reclaimed Sites – Group D       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Istes Removed from Inspection List       13         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2	3.2	Outfall Inspection and Tracking	3
3.4.1       Illicit Discharges Eliminated       5         3.4.2       Illicit Discharges Reported to Other Jurisdictions       5         3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPPs       6         3.8       Construction Site Issues       7         3.8.1       Construction Violations       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       No Exposure Certification       8         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group I       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Ispection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3.10.5.2       Site Plans an	3.3		
3.4.2       Illicit Discharges Reported to Other Jurisdictions       5         3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPPs       6         3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.8.2       Construction Violations       7         3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Ispection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3       J.0.5.2       Site Plans and Training       13         5.1	3.4	Illicit Discharges	4
3.5       Erosion Abatement Projects       6         3.6       Spills and Other Releases       6         3.7       Maintenance Facility SWPPPs       6         3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       Construction Violations       7         3.8.1       Swyper Update       8         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Inspection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3.10.5.2       Site Plans and Training       13         5.1       Assessment of Program Operations	3.4.1	-	
3.6Spills and Other Releases63.7Maintenance Facility SWPPPs63.8Construction Site Issues73.8.1Construction Site Tracking System73.8.2Construction Violations73.8.2Construction Violations73.9Industrial Facilities73.9.1SWPPP Update83.9.2No Exposure Certification83.10Material Sources83.10.1Active Sites - Group A83.10.2Inactive Sites - Group B93.10.3Reclaimed Sites - Group B93.10.4Non-Mining Sites - Group I103.10.5.1Sites Removed from Inspection List133.10.5.2Site Plans and Training133NUMERIC SUMMARY OF SSWMP ACTIVITIES135.1Assessment of Program Operations135.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16	3.4.2		
3.7       Maintenance Facility SWPPPs       6         3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.9       Industrial Facilities       7         3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3       10.5.2       Site Plans and Training       13 </td <td>3.5</td> <td>Erosion Abatement Projects</td> <td>6</td>	3.5	Erosion Abatement Projects	6
3.8       Construction Site Issues       7         3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       Construction Violations       7         3.8.1       Construction Violations       7         3.8.2       Construction Violations       7         3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Inspection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         5       EVALUATION OF THE SSWMP       13         5.1       Assessment of Program Operations       13		•	
3.8.1       Construction Site Tracking System       7         3.8.2       Construction Violations       7         3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Inspection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3       A       NUMERIC SUMMARY OF SSWMP ACTIVITIES       13         5.1       Assessment of Program Operations       13         5.2       Assessment of Social Indicators       15         5.3       Monitoring Water Quality       16		•	
3.8.2       Construction Violations       7         3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10       Active Sites – Group A       8         3.10.1       Active Sites – Group B       9         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Inspection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         3       A       NUMERIC SUMMARY OF SSWMP ACTIVITIES       13         5       EVALUATION OF THE SSWMP       13         5.1       Assessment of Program Operations       13         5.2       Assessment of Social Indicators       15         5.3       Monitoring Water Quality       16         6       SSWMP MODIFICATIONS       16	3.8		
3.9       Industrial Facilities       7         3.9.1       SWPPP Update       8         3.9.2       No Exposure Certification       8         3.10       Material Sources       8         3.10.1       Active Sites – Group A       8         3.10.2       Inactive Sites – Group B       9         3.10.3       Reclaimed Sites – Group C       10         3.10.4       Non-Mining Sites – Group I       10         3.10.5       Inspection of Material Sources       11         3.10.5.1       Sites Removed from Inspection List       13         3.10.5.2       Site Plans and Training       13         5       EVALUATION OF THE SSWMP       13         5.1       Assessment of Program Operations       15         5.3       Monitoring Water Quality       16         6       SSWMP MODIFICATIONS       16	3.8.1		
3.9.1       SWPPP Update	3.8.2	Construction Violations	7
3.9.2 No Exposure Certification       8         3.10 Material Sources       8         3.10.1 Active Sites – Group A       8         3.10.2 Inactive Sites – Group B       9         3.10.3 Reclaimed Sites – Group C       10         3.10.4 Non-Mining Sites – Group I       10         3.10.5 Inspection of Material Sources       11         3.10.5.1 Sites Removed from Inspection List       13         3.10.5.2 Site Plans and Training       13         4 NUMERIC SUMMARY OF SSWMP ACTIVITIES       13         5.1 Assessment of Program Operations       13         5.2 Assessment of Social Indicators       15         5.3 Monitoring Water Quality       16         6 SSWMP MODIFICATIONS       16	3.9	Industrial Facilities	7
3.10Material Sources83.10.1Active Sites – Group A83.10.2Inactive Sites – Group B93.10.3Reclaimed Sites – Group C103.10.4Non-Mining Sites – Group I103.10.5Inspection of Material Sources113.10.5.1Sites Removed from Inspection List133.10.5.2Site Plans and Training134NUMERIC SUMMARY OF SSWMP ACTIVITIES135EVALUATION OF THE SSWMP135.1Assessment of Program Operations135.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16	3.9.1	SWPPP Update	8
3.10.1 Active Sites – Group A83.10.2 Inactive Sites – Group B93.10.3 Reclaimed Sites – Group C103.10.4 Non-Mining Sites – Group I103.10.5 Inspection of Material Sources113.10.5.1 Sites Removed from Inspection List133.10.5.2 Site Plans and Training134 NUMERIC SUMMARY OF SSWMP ACTIVITIES135 EVALUATION OF THE SSWMP135.1 Assessment of Program Operations135.2 Assessment of Social Indicators155.3 Monitoring Water Quality166 SSWMP MODIFICATIONS16	3.9.2	No Exposure Certification	8
3.10.2 Inactive Sites – Group B93.10.3 Reclaimed Sites – Group C103.10.4 Non-Mining Sites – Group I103.10.5 Inspection of Material Sources113.10.5.1 Sites Removed from Inspection List133.10.5.2 Site Plans and Training134 NUMERIC SUMMARY OF SSWMP ACTIVITIES135 EVALUATION OF THE SSWMP135.1 Assessment of Program Operations135.2 Assessment of Social Indicators155.3 Monitoring Water Quality166 SSWMP MODIFICATIONS16	3.10	Material Sources	8
3.10.3 Reclaimed Sites – Group C       10         3.10.4 Non-Mining Sites – Group I       10         3.10.5 Inspection of Material Sources       11         3.10.5.1 Sites Removed from Inspection List       13         3.10.5.2 Site Plans and Training       13         4 NUMERIC SUMMARY OF SSWMP ACTIVITIES       13         5 EVALUATION OF THE SSWMP       13         5.1 Assessment of Program Operations       13         5.2 Assessment of Social Indicators       15         5.3 Monitoring Water Quality       16         6 SSWMP MODIFICATIONS       16	3.10.	1 Active Sites – Group A	8
3.10.4 Non-Mining Sites – Group I       10         3.10.5 Inspection of Material Sources       11         3.10.5.1 Sites Removed from Inspection List       13         3.10.5.2 Site Plans and Training       13         4 NUMERIC SUMMARY OF SSWMP ACTIVITIES       13         5 EVALUATION OF THE SSWMP       13         5.1 Assessment of Program Operations       13         5.2 Assessment of Social Indicators       15         5.3 Monitoring Water Quality       16         6 SSWMP MODIFICATIONS       16	3.10.	2 Inactive Sites – Group B	9
3.10.5 Inspection of Material Sources113.10.5.1 Sites Removed from Inspection List133.10.5.2 Site Plans and Training134 NUMERIC SUMMARY OF SSWMP ACTIVITIES135 EVALUATION OF THE SSWMP135.1 Assessment of Program Operations135.2 Assessment of Social Indicators155.3 Monitoring Water Quality166 SSWMP MODIFICATIONS16	3.10.	3 Reclaimed Sites – Group C	10
3.10.5.1Sites Removed from Inspection List133.10.5.2Site Plans and Training134NUMERIC SUMMARY OF SSWMP ACTIVITIES135EVALUATION OF THE SSWMP135.1Assessment of Program Operations135.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16	3.10.	4 Non-Mining Sites – Group I	10
3.10.5.2Site Plans and Training134NUMERIC SUMMARY OF SSWMP ACTIVITIES135EVALUATION OF THE SSWMP135.1Assessment of Program Operations135.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16	3.10.	5 Inspection of Material Sources	11
4       NUMERIC SUMMARY OF SSWMP ACTIVITIES.       13         5       EVALUATION OF THE SSWMP       13         5.1       Assessment of Program Operations.       13         5.2       Assessment of Social Indicators       15         5.3       Monitoring Water Quality       16         6       SSWMP MODIFICATIONS       16		3.10.5.1 Sites Removed from Inspection List	13
5EVALUATION OF THE SSWMP135.1Assessment of Program Operations135.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16		3.10.5.2 Site Plans and Training	13
5.1Assessment of Program Operations	4 N	NUMERIC SUMMARY OF SSWMP ACTIVITIES	13
5.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16	5 H	EVALUATION OF THE SSWMP	13
5.2Assessment of Social Indicators155.3Monitoring Water Quality166SSWMP MODIFICATIONS16	5.1	Assessment of Program Operations	13
5.3    Monitoring Water Quality    16      6    SSWMP MODIFICATIONS    16			
6 SSWMP MODIFICATIONS			

6.2	Temporary or Experimental BMPs	
6.3	Increase of Existing BMPs	
6.4	Replacement of Existing BMPs	
7 N	IONITORING LOCATION INFORMATION	
8 S	TORM EVENT RECORDS	
9 S	UMMARY OF MONITORING DATA	
10 A	ASSESSMENT OF MONITORING RESULTS	
10.1	MS4 Results	
10.2	Total Maximum Daily Loads	
10.3	Industrial Results	
10.4	Construction Results	
10.4.1	1 Marsh Station I-10 Construction Project	
10.4.2	2 Doubtful Canyon SR260 Construction Project	
10.5	Maintenance Facilities	
10.5.1	1 Nogales Maintenance Yard	
10.5.2	2 Superior Maintenance Yard	
10.5.3	3 Superior Fuel Yard	
11 E	CSTIMATE OF POLLUTANT LOADING	
12 A	NNUAL EXPENDITURES	
12.1	Five-Year Construction Program	
12.2	Highway Maintenance Program	
12.3	Administrative Budget	
12.4	Office of Environmental Services Budget	
13 A	ADOT MS4 AUDIT	
13.1	Overview of Audit	
13.2	Positive Elements of MS4 Program	
13.3	Deficiencies of MS4 Program	
13.4	Proposed ADOT Actions	

### TABLES

Table 1 – Group A1 Sites	8
Table 2 – Group A2 Sites	
Table 3 – Reclamation or Utilization Schedule for Group B Sites	
Table 4 – Non-mining Sites	10
Table 5 – Summary of Inspection Findings, Deficiencies, and Corrective Actions	11
Table 6 – ADOT Stormwater Monitoring Locations	17
Table 7 – Estimated Stormwater Program Comprehensive Annual Budget	21

### APPENDICES

APPENDIX A:	Narrative Summary of SSWMP Activities
APPENDIX B:	Outfall Inspection and Tracking
APPENDIX C:	Notice of Illegal Discharge Letter
APPENDIX D:	Map of ADOT Licensed Materials Sources and Stockpile Sites
APPENDIX E:	Material Sources Inventory (Group A, B, C, and I)
APPENDIX F:	Numeric Summary of BMPs
APPENDIX G:	Approved MS4 Monitoring Locations
APPENDIX H:	ISCO Stormwater Sampling Equipment
APPENDIX I:	Summary of MS4 Monitoring Data
APPENDIX J:	Industrial Discharge Monitoring Reports
APPENDIX K:	Construction Discharge Monitoring Reports
APPENDIX L:	Maintenance Facility Discharge Monitoring Reports
APPENDIX M:	Maintenance Facility Laboratory Reports
APPENDIX N:	Summary of EPA Audit Results

#### **ACRONYMNS and DEFINITIONS**

**A&Wedw** – Aquatic and Wildlife (effluent-dependent water)

A&Wc – Aquatic and Wildlife (cold water)

**A&Ww** – Aquatic and Wildlife (warm water)

AASHTO - American Association of State Highway and Transportation Officials

ADEQ - Arizona Department of Environmental Quality

**ADOT** – Arizona Department of Transportation

AgL – Agricultural Livestock Watering

AHLI – Adopt-a-Highway Litter Initiative

A.R.S. - Arizona Revised Statute

**AZPDES** – **Arizona Pollutant Discharge Elimination System** – The State program for issuing, modifying, revoking and reissuing, terminating, monitoring and enforcing permits, and imposing and enforcing pretreatment requirements, under Sections 307, 318, 402, and 405 of CWA.

#### **BLM – Bureau of Land Management**

**BMP** – **Best Management Practice -** Permit condition used in place of or in conjunction with effluent limitations to prevent or control the discharge of pollutants. BMPs may include, but are not limited to, treatment requirements, operating procedures, or practices to control plant/facility site runoff, spillage, leaks, sludge or waste disposal, or drainage from raw material storage. BMPs may also include schedule of activities, prohibition of practices, maintenance procedure, or other management practice.

BOD - Biological Oxygen Demand

COD - Chemical Oxygen Demand

**COP** – City of Phoenix

**CWA – Clean Water Act -** The Clean Water Act is an act passed by the U.S. Congress to control water pollution. It was formerly referred to as the Federal Water Pollution Control Act of 1972 or Federal Water Pollution Control Act Amendments of 1972 (Public Law 92-500), 33 U.S.C. 1251 et. seq., as amended by: Public Law 96-483; Public Law 97-117; Public Laws 95-217, 97-117, 97-440, and 100-04.

DEC – District Environmental Coordinator

**DMR** – **Discharge Monitoring Report** - The form used (including any subsequent additions, revisions, or modifications) to report self-monitoring results by AZPDES permittees. DMRs must be used by approved states as well as by EPA.

**EPA** – U.S. Environmental Protection Agency

**EPCP** – Erosion Pollution Control Plan

**ERP** – Enforcement Response Plan

**FBC** – Full Body Contact

**FC** – Fish Consumption

FIS – Features Inventory System

**FPPP** – Facility Pollution Prevention Plan

**IDDE** – Illicit Discharge Detection and Elimination

**MS4** – **Municipal Separate Storm Sewer System -** A conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains) owned by a state, city, town or other public body, that is designed or used for collecting or conveying stormwater, which is not a combined sewer, and which is not part of a publicly owned treatment works. Commonly referred to as an "MS4" [40 CFR 122.26(b)(8)].

NASPA - Northern Arizona Stormwater Pollution Alliance

NEPA -- National Environmental Policy Act

NOV – Notice of Violation

NTU – Nephelometric Turbidity Units

**OES** – Office of Environmental Services

PAG – Pima Association of Governments

**PBC** – Partial Body Contact

Permittee – means the Arizona Department of Transportation.

QAM – Quality Assurance Manual

SCOE - Standing Committee on the Environment

SMP – Slope Management Program

**SR** – State Route

**SSC** – Suspended Sediment Characteristics

**SSWMP – Statewide Stormwater Management Plan** – A comprehensive plan for implementation of AZPDES permit requirements.

**STORM** – STormwater Outreach for Regional Municipalities

**Stormwater** – Stormwater runoff, snowmelt runoff, and surface runoff and drainage [40 CFR 122.26(b)(13)].

**SWAT** – Stormwater Advisory Team

TMDL - Total Maximum Daily Load

TSS – Total Suspended Solids

**TDS** – Total Dissolved Solids

TKN – Total Kjeldahl Nitrogen

**SWPPP** – Stormwater Pollution Prevention Plan

SWQS - Surface Water Quality Standard

**Waters of the United States** – All waters that are currently used, were used in the past, or may be susceptible to use in interstate or foreign commerce, including all waters subject to the ebb and flow of the tide. Waters of the United States include but are not limited to all interstate waters and intrastate lakes, rivers, streams (including intermittent streams), mudflats, sand flats, wetlands, sloughs, prairie potholes, wet meadows, playa lakes, or natural ponds. [See 40 CFR 122.2 for the complete definition.]

### **EXECUTIVE SUMMARY**

The Arizona Department of Transportation (ADOT) is submitting this 2011 Statewide Stormwater Management Program (SSWMP) Annual Report describing activities and programs implemented from July 1, 2010 through June 30, 2011. During this time period ADOT operated under the Arizona Pollutant Discharge Elimination System (AZPDES) Permit No. AZS000018-2008 (Permit). This is the third Annual Report under ADOT's stormwater permit which expires September 18, 2013. The Statewide Permit authorizes ADOT to discharge stormwater, and other discharges as specified, Statewide (except for Indian Country) to Waters of the United States in Arizona in accordance with its terms and conditions. Specifically, the Permit covers:

- Activities associated with the Municipal Separate Storm Sewer System (MS4) operated by ADOT
- Activities associated with construction initiated and controlled by ADOT from the commencement of construction until final stabilization
- Activities associated with industrial and maintenance facilities owned and operated by ADOT

The Annual Report is divided into the following twelve categories: (1) General Information, (2) Annual Report Certification, (3) Narrative Summary of the SSWMP activities, (4) Numeric Summary of SSWMP Activities, (5) Evaluation of the SSWMP, (6) SSWMP Modifications, (7) MS4 Monitoring Location Information, (8) Storm Event Records, (9) Summary of Monitoring Data, (10) Assessment of Monitoring Data, (11) Estimate of Pollutant Loading, and (12) Annual Expenditures. This Annual Report is used by ADOT to assess the performance of its stormwater management program and establish long-term assessment strategies.

#### **GENERAL INFORMATION** 1

Permittee Name: Arizona Department of Transportation

Permit Number: AZS000018-2008	Reporting Period: July 1, 2010 - June 30, 2011
Stormwater Management Program Contact:	Name of Certifying Official:
<u>Wendy Terlizzi</u>	<u>Todd G. Williams, M.Sc.</u>
Title: <u>Water Quality Manager</u>	Title: <u>Director, Office of Environmental Services</u>
Mailing Address:	Mailing Address:
<u>Arizona Department of Transportation</u>	<u>Arizona Department of Transportation</u>
<u>1611 West Jackson Street, MD EM04</u>	<u>1611 W Jackson Street, MD EM04</u>
City: <u>Phoenix, Arizona</u> Zip Code: <u>85007</u>	City: <u>Phoenix, Arizona</u> Zip Code: <u>85007</u>
Telephone Number: <u>(602) 712 – 8353</u>	Telephone Number: <u>(602) 712 – 8272</u>
Fax Number: <u>(602) 712 – 3492</u>	Fax Number: <u>(602) 712 – 3492</u>
Email Address: <u>WTerlizzi@azdot.gov</u>	Email Address: <u>TGWilliams@azdot.gov</u>

#### 2 **ANNUAL REPORT CERTIFICATION**

I certify under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Jodd G. Williams, M.Sc., Director, OES Date

# **3 NARRATIVE SUMMARY OF SSWMP ACTIVITIES**

Permit Section 9.1.2(c): Provide a summary of the status of the SSWMP each year, including a brief description of the implementation and progress of every individual best management practice (BMP). Also, provide an explanation of any significant developments or changes to the number or type of activities, the frequency or schedule of activities, or the priorities or procedures for implementation of specific management practices.

ADOT updated its SSWMP in March, 2010 and submitted it to the Arizona Department of Environmental Quality (ADEQ). The SSWMP outlines how ADOT will manage its stormwater discharges throughout the State. The SSWMP includes the following components:

- Description of the best management practices (BMPs) selected, implemented, maintained, and updated to minimize the discharges of pollutants that may contribute to an exceedence of any surface water quality standard
- List of narrative and/or numeric measurable goals for each BMP
- Timeframe by which ADOT will achieve each measurable goal
- Title(s) of the person(s) responsible for implementing and coordinating each measure

As required by Section 9.1.2(c) of the Permit, ADOT has provided a narrative summary of SSWMP activities in this Annual Report. This summary is provided in Appendix A and includes a brief description of the implementation and progress of individual BMPs. The summary indentifies each BMP, its location within the updated SSWMP, and Permit reference if applicable.

## 3.1 ADOT Technical Documents

Permit Requirement (Appendix B, Part 3): Include a short statement for each of the following documents indicating if a review was completed. Describe any major updates to each document.

ADOT reviews and updates its technical stormwater documents as needed. A status summary of each technical document is provided:

- *Erosion and Pollution Control Manual* Update of this manual is on-going and in accordance with Permit Section 3.2.2.1(c). Updates included revision of BMP detail drawings, SWPPP index sheets, associated training module, and a template for ADOT licensed material sources.
- *Maintenance and Facilities Best Management Practices Manual* This manual was updated in September 2010 by ADOT in accordance with Permit Section 3.2.3.1(c).
- *Stormwater Monitoring Guidance Manual for MS4 Activities* This manual had no updates in the last reporting year.
- *Stormwater Monitoring Guidance Manual for Construction Activities* This manual had no updates in the last reporting year.
- *Stormwater Monitoring Guidance Manual for Industrial Activities* This manual had no updates in the last reporting year.
- *Post-Construction Stormwater Control BMP Manual* This manual had no updates in the last reporting year.

- *Quality Assurance Manual (QAM)* This manual had no updates in the last reporting year.
- *Enforcement Response Plan (ERP)* This manual had no updates in the last reporting year.

### 3.2 Outfall Inspection and Tracking

Permit Section 3.2.3.2(e): ADOT shall document that a system to track and record the findings of outfall inspections, including the conditions of outfalls, potential sources of pollutants, and maintenance needs has been implemented and is being maintained.

ADOT has developed a system to track and record the condition of major outfalls. The tracking system consists of an excel spreadsheet maintained by ADOT's Office of Environmental Services (OES) that includes major outfalls as identified in ADOT's *Phase I and Phase II Stormwater System Maps* completed September, 2005 (Appendix B). Categories tracked and recorded for the major outfall inspections include:

- Outfall name
- Date of inspection
- Inspector name
- Receiving water
- Outfall type (pipe, channel, tunnel, culvert)
- Condition of outfall
- Maintenance needs
- Dry weather flows
- Potential sources of pollutants
- Follow up actions required (if any)

ADOT has initiated a pilot program within the Kingman District to track and record the condition of its stormwater drainage features in the Lake Havasu area. This pilot program uses ADOT's Features Inventory System (FIS). The FIS is a geographic information system capable of tracking and maintaining highway attributes, such as guardrail and signs, but also includes drainage features. The FIS pilot program remains ongoing within the Lake Havasu area.

ADOT has begun populating the FIS, which is capable of storing information regarding highway attributes, such as guardrail, signs, and drainage features. The FIS allows for attribute data, e.g., photos, global positioning system datum, and condition of features, to be documented. ADOT Districts started using the FIS drainage mapping component in October 2010 as a pilot to assist in tracking dry weather screenings. It is anticipated that the FIS will be fully populated with all drainage features by the end of this Permit term (2013). ADOT will continue to identify which assets are outfalls and priority outfalls as defined by the Permit and will complete the mapping effort three years later (i.e., 2016). In the meantime, outfall tracking will be conducted manually for Districts that do not have the FIS fully implemented.

#### **3.3** Public Access to Stormwater Documents

*Permit Section 3.2.2.3(a): ADOT shall summarize the status of public access to stormwater documents.* 

ADOT has maintained its online Stormwater Library for the general public and internal use. The Stormwater Library is a virtual library that can be accessed via the internet at the following location:

http://www.azdot.gov/Inside\_ADOT/OES/Water\_Quality/Stormwater/Index.asp.

This library houses documents required by the Permit. Anyone without internet access can also view available documents by contacting OES at (602) 712-8353. ADOT is currently unable to track the number of visits annually to the virtual library. Beginning July 1, 2011 ADOT will be able to track the number of page views for the Stormwater Library. Documents maintained in the Stormwater Library include:

- Stormwater Permit and Related Documents
  - ADOT Statewide Stormwater Discharge Permit
  - o Statewide Stormwater Management Plan
  - Permit Annual Reports (2005 2010)
  - ADOT Statewide Stormwater Permit Application
- Manuals
  - Quality Assurance Manual
  - o Erosion and Pollution Control Manual/BMP Detail Drawings
  - o Post-Construction Best Management Practices Manual
  - Maintenance and Facilities Best Management Practices Manual
  - o Stormwater Monitoring Guidance Manual for Construction Activities
  - Stormwater Monitoring Guidance Manual for MS4 Activities
  - o Stormwater Monitoring Guidance Manual for Industrial Activities
  - o Stormwater Enforcement Response Plan
- Maps
  - o Outstanding, Impaired, and Not Attaining Waters Maps by County
  - Phase I & Phase II Stormwater System Maps
  - o Projects in the Five Year Program Located Near Unique and Impaired Waters
- Other Resources
  - Construction Stormwater Pollution Prevention Plan (SWPPP) Template
  - Encroachment documents
  - ADOT-Licensed Material Sources Documents
  - Contact list
  - o Useful links

#### 3.4 Illicit Discharges

Permit Section 3.2.3.4(d): ADOT shall summarize the status of implementation procedures to track actions taken on illicit discharges and illegal dumping. Develop and implement a procedure to track the action taken on identified illicit discharges and illegal dumping.

ADOT has developed the following enforcement provisions for tracking illicit discharges:

- Written Warning If an inspection of the drainage system identifies an illegal connection/discharge to the ADOT system, ADOT will issue a "Notice of Illegal Discharge and Demand for Corrective Action" letter to the property owner where an illegal connection/discharge is discovered. The letter will request that the connection/discharge be ceased or removed within 30 days. A follow up inspection will be performed to ensure compliance. A Notice of Illegal Discharge or Connection letter is included in Appendix C.
- 2. *Removal of Connection/Discharge* ADOT may remove the illegal connection/discharge if it has not been corrected within 30 days. If ADOT removes the illegal connection/discharge, the responsible party is subject to an action for damages by the state brought by the attorney general, or the county attorney of the county in which the act is committed on direction of the attorney general, pursuant to Arizona Revised Statute (A.R.S.) §28-7053 Misuse of Public Highway.
- 3. *Civil Action* If the illegal connection/discharge is not corrected within 30 days, ADOT may forward this matter to the Arizona Office of the Attorney General so that a lawsuit may be filed.
- 4. Other Enforcement Actions ADOT is not a typical MS4, such as a city or county, with its own enforcement branch such as police department or sheriff. Without its own enforcement branch, ADOT relies on other jurisdictions for enforcement assistance. ADOT may request the assistance of other government entities to assist with enforcement to include other MS4s, ADEQ and/or the U.S. Environmental Protection Agency (EPA).

Enforcement actions are tracked initially by the inspector/District Environmental Coordinator (DEC) that identifies an illicit discharge. The discharge is documented and includes the source, date/time, photo points, contact person (if any), description of the nature of the non-compliance or illicit discharge, and actions taken. This information is then forwarded to the OES and the action tracked. The OES coordinates/tracks enforcement action or requests the assistance of the Attorney General's office.

### 3.4.1 Illicit Discharges Eliminated

Permit Section 3.2.3.4(b)(ii): ADOT shall report the number of illicit discharges eliminated each year in the Annual Report

ADOT has identified and eliminated the following number of illicit discharges for the identified District:

- Phoenix District 4 illicit discharges reported and 4 eliminated
- Prescott District 1 illicit discharge reported and 1 eliminated
- Yuma District 1 illicit discharge reported and 1 eliminated
- Holbrook District 1 illicit discharge reported and 1 eliminated

### 3.4.2 Illicit Discharges Reported to Other Jurisdictions

Permit Section 3.2.3.4(c)(iii): ADOT shall present the number of illicit discharges reported to other jurisdictions for follow-up in the Annual Report

There has been one illicit discharge identified within the past reporting year that required reporting to other jurisdictions for follow-up. In November 2010, an illicit discharge was

reported as originating from an ADOT outfall. It was determined that no discharge was entering ADOT's drainageway from the surface and that it was likely coming from a City of Phoenix (COP) interconnect. ADOT notified COP personnel and worked closely with them in an attempt to identify the source. The source of the discharge was not identified and dissipated within several hours.

### 3.5 Erosion Abatement Projects

Permit Section 3.2.6.2(d): ADOT shall describe the tracking system used to identify, track and prioritize erosion abatement projects. Summarize erosion abatement projects conducted during each year.

ADOT has identified the existing Slope Management Program (SMP) database as a possible tool to identify, track and prioritize erosion abatement projects. The SMP is a Microsoft ACCESS database that allows ADOT to track and prioritize the severity of rock slopes, soil cuts and embankments throughout the state. In Permit Year 4, ADOT will investigate expansion of this database as a viable tool to track erosion abatement projects.

### 3.6 Spills and Other Releases

Permit Section 4.1.5.2(d): ADOT shall document that a system to track and record spills and other releases by ADOT staff and at ADOT maintenance facilities has been established.

ADOT has developed and implemented a system to track and record spills. The system requires ADOT personnel to report non-emergency spills to their respective DEC. Spills requiring an emergency response are reported to the ADOT Safety and Health Section and to the DEC. The DEC documents the following information when spills occur:

- Number of spills
- Location
- Date/time
- Extent of the spill
- Media impacted (if any)
- Circumstances of the release
- Names of parties involved
- Corrective actions taken
- Follow up required (if any)

Spill information is forwarded to the OES and assistance provided to the DEC if required. Records are maintained at the facility where a spill or release occurred and at the OES.

## 3.7 Maintenance Facility SWPPPs

*Permit Section 4.2.1.1: ADOT shall document individually that the SWPPP required for each maintenance facility has been updated.* 

ADOT has been updating existing facility Stormwater Pollution Prevention Plans (SWPPPs) for the following maintenance facilities within the past reporting year:

- Avondale Maintenance Yard
- Broadway Maintenance Yard
- Douglas Maintenance Yard
- Durango Maintenance Yard
- Phoenix Equipment Services

- Flagstaff Maintenance Yard
- Grand Avenue Landscape Maintenance Yard
- Little Antelope Yard
- Mesa Country Club Maintenance Yard
- Mesa Recker Road Maintenance Yard
- Nogales Maintenance Yard
- North Phoenix Maintenance Yard
- Prescott Valley Maintenance Yard
- Statewide Striping Facility
- Superior Maintenance Yard
- Superior Storage and Fuel Yard
- Tucson Grant Road Maintenance Yard
- Yuma Maintenance Yard

In addition, it was discovered that the Camp Verde Maintenance Yard required a SWPPP due to its location within an MS4. The SWPPP was completed in December 2010.

In light of anticipated changes in federal regulations regarding Spill Prevention, Control, and Countermeasure, ADOT has embarked on an effort to expand the SWPPPs by incorporating SPCC regulations into a comprehensive Facility Pollution Prevention Plan (FPPP). FPPP preparation began at the end of the reporting year for 52 maintenance yards that house fueling stations.

### **3.8** Construction Site Issues

Permit Section 5.3.4: A list and description of all violations ADOT has determined at construction sites and their resolution, including any enforcement actions taken against ADOT contractors.

### 3.8.1 Construction Site Tracking System

ADOT is currently developing a system to adequately identify, track, and resolve violations at construction sites. Current State budget issues are restricting ADOT from fully developing and implementing this program. Once funded, the tracking will include the following elements:

- Track construction sites to include inspections and enforcement
- Prioritize sites for inspection based on risk to waterway, resources, and operator history
- Resolve violations as needed

### 3.8.2 Construction Violations

ADOT has received no Notice of Violations (NOVs) for construction sites from the ADEQ within the past reporting year.

## **3.9 Industrial Facilities**

Permit Section 6.6.2 & 6.7.2: Provide a brief statement documenting that the SWPPPs for Grand Canyon National Park Airport and Durango Sign Factor were updated and on-site within 90 days of the effective date of the permit.

ADOT industrial facilities include the Grand Canyon Airport, Durango Sign Factory and the former Print Shop (closed 2010). These facilities are discussed below.

### 3.9.1 SWPPP Update

SWPPPs for the Grand Canyon National Park Airport and the Durango Sign Factory have been maintained and updated (if required) within the past reporting year for each facility. Additionally, personnel at each facility have been trained on SWPPP requirements and quarterly and annual inspections have been completed.

### 3.9.2 No Exposure Certification

Permit Requirement Section 6.9.2: Confirm the Print Shop has "no exposure" to stormwater

Printing activities at the ADOT Print Shop (1655 W. Jackson Street, Phoenix, AZ) have been discontinued and the facility is no longer in operation. This requirement has been removed from ADOT's Permit.

#### 3.10 Material Sources

Permit Section 6.8.3: Provide a map of material sources and provide a status summary of each site.

ADOT's Materials Group maintains an inventory of regulated material sources and stockpile sites in accordance with Permit Section 6.8.3. These sites are classified into the following four categories:

- Group A Active Sites
- Group B Inactive Sites
- Group C Reclaimed Sites
- Group I Non-mining Sites

A site map illustrating the locations of material sources identified within these four groups is provided in Appendix D and a status summary is in Appendix E. The following section summarizes the status of sites in each group.

### 3.10.1 Active Sites – Group A

Permit Section 6.8.3: Provide a status summary of each site.

ADOT has 17 sites within Group A, which is defined as active sites where work or other activities related to the extraction, processing, removal or recovery of minerals is being conducted. Group A is further defined by ADOT into the following two categories:

- Group A1 sources used frequently for maintenance activities
- Group A2 sources used infrequently for major construction projects

There are 12 sites within Group A1 as identified in Table-1. These sites are used frequently by ADOT Maintenance and are inspected on a quarterly basis.

Material Sources Used Frequently and Inspected Quarterly							
Site No.	Source Name	District	County				
1563	Pole Knoll	Globe	Apache				
3512	Burnt Corral	Globe	Maricopa				
5154	JMP Ranches Inc.	Globe	Apache				
8763	Fish Creek	Globe	Maricopa				
8109	BVD	Holbrook	Coconino				
7810	Crabtree	Safford	Greenlee				
5058	Picacho	Tucson	Pinal				
6662	Val Vista	Tucson	Pinal				
1662	Tanner	Yuma	Yuma				
2979	Vicksburg	Yuma	La Paz				
3547	Gila Bend North	Yuma	Maricopa				
5474 Castle Dome		Yuma	Yuma				

 Table 1 - Group A1 Sites

There are 5 sites within Group A2 as identified in Table-2. These sites are used infrequently by contractors (every three to five years) for major construction projects and are inspected annually. When Group A2 sites are utilized for a project, the contractor includes the material source in the project SWPPP or develops a site-specific SWPPP. The contractor submits a Notice of Intent under the Construction General Permit, implements and maintains BMPs, conducts routine inspections, and provides interim stabilization before filing a Notice of Termination.

	Material Sources Used Infrequently and Inspected Annually						
Site No. Source Name District County							
8706	Yucca	Kingman	Mohave				
8569	Dugas	Prescott	Yavapai				
6022	Bowie	Safford	Cochise				
5643	Gila Bend South	Yuma	Maricopa				
8268 Tiger Wash West		Yuma	Maricopa				

 Table 2 - Group A2 Sites

Group A sites identified in previous Annual Reports not covered by an active mining license have been moved to Group B.

### 3.10.2 Inactive Sites – Group B

Group B includes sites or portions of sites where mining occurred in the past but is currently not an active facility.

ADOT has 7 sites in Group B, which is defined as inactive material sites being evaluated for mining license renewal, reclamation or disposal. ADOT may not hold a current mining license to some Group B sites and therefore ground disturbing activities at those facilities is not authorized. Sites will be maintained in Group B until funds are allocated and a reclamation plan approved. Table 3 below provides the goals to use or reclaim Group B sites during the permit term.

			Reclamation Schedule			
Site No.	District	County	Year 2	Year 3	Year 4	Year 5
3043	Globe	Gila		Permit Renewal		
3044	Globe	Gila		Permit Renewal		
7225	Globe	Gila		Permit Renewal		
8135	Globe	Apache		Permit Renewal		
6451	Safford	Graham			Further Evaluation	
1318	Tucson	Pima			Reclamation Plan	Initiate/Achieve Stabilization
478	Yuma	Yuma			Further Evaluation	

Table 3 - Reclamation or Utilization Schedule for Group B Sit	tes
---	-----

Other sites on the inventory that may be reclaimed and released to the land manager are listed in Group I. These sites were not used for mining and as a result do not fit into the definition of Group B. However, similar to sites in Group B, renewal or reclamation and disposal should be completed during the permit term (see Section 3.10.4 below for details regarding the specific sites).

### 3.10.3 Reclaimed Sites – Group C

Group C includes sites where activities are being conducted to return the land to its pre-mining state.

ADOT currently has no sites in Group C, which is defined as sites where activities are being conducted to return the land to its pre-mining condition. An update of sites previously identified in Group C is provided:

- MS 8223 Reclamation of this site located in the Safford District was completed in 2009. Minor paperwork to officially document closure of the land use permit will be pursued in Permit Year 4.
- MS 769 Reclamation and release from site in the Flagstaff District was documented in August 2010 and the site will be removed from future reporting.
- MS 8318 Operations at this site in the Holbrook District concluded and the land owner released ADOT from reclamation in October 2010. This site will be removed from future reporting.

### 3.10.4 Non-Mining Sites – Group I

#### Group I includes non-mining sites (regulated stockpile sites).

ADOT has 16 sites in Group I, which is defined as sites used to store aggregate, dirt, and other supplies. ADOT Maintenance has access to import or export material 365 days a year; therefore, these sites are inspected quarterly. These sites currently fall under the administrative responsibility of the State Materials Engineer while roadside stockpiles are managed by individual Districts and are not part of this section.

Group I includes three inactive, unlicensed stockpile sites: MS 1546, MS 3562 and MS 8629. Because these sites are not prior mining sites, they do not conveniently fit into Group B. ADOT has addressed this issue by assigning appropriate site use code. Group I sites scheduled for reclamation or permit renewal are identified in Table 4.

			Reclamation Schedule			
Site No.	District	County	Year 2	Year 3	Year 4	Year 5
3562	Flagstaff	Coconino			Reclamation Plan	Initiate/Achieve Stabilization
1546	Globe	Gila			Permit Renewal	
8629	Globe	Gila		NEPA Analysis	Reclamation Plan	Initiate/Achieve Stabilization

#### **Table 4 - Non-mining Sites**

#### 3.10.5 Inspection of Material Sources

Permit Section 6.8.4.2(d): ADOT shall create a summary for each Annual Report of all inspections conducted. The summary shall include the inspection findings, deficiencies, and corrections made to each site.

Group A, B, C and I sites were inspected as per Permit requirements throughout the reporting year (either quarterly, annually, or every 14 days). Reports are available from ADOT Materials Group or the appropriate ADOT District. In accordance with the Permit Section 6.8.4.2.d., the inspection findings, deficiencies, and corrective actions for non-compliant sites are provided in Table 5. Material sources not listed below and that appear in Appendix E have no deficiencies and require no corrective action.

Site No. & Name	Findings	Deficiencies	Corrective Action
MS 1245 – Sunset Pass	Perimeter berm has no freeboard.	Berm not adequately maintained.	Remove cinders from interior of berm on northwest corner (Permit Year 4).
MS 1662 – Tanner	Sediment discharge to wash in southwest corner of site.	No BMPs in place.	Relocated material stockpiles (March 2011) to another portion of the site (northwest corner) to eliminate sediment transport.
MS 3043 – Squaw Peak	Sediment discharge along eastern boundary.	Retention basin inadequately sized; no velocity control devices; blown out berm and ditch.	Increase storage capacity of retention basin. Install velocity reduction measures, such as slope roughening. Maintain drainage channels to convey flows to the retention basin. Mining permit authorization anticipated October 2011.
MS 3562 – Beaver Creek	Sediment discharge at haul road and southern boundary.	Berm along west side needs maintenance; implement check dams along haul road.	Will negotiate reclamation and closure of this site with the Forest Service.
MS 3591 – Carol Spring Mountain	Salt shed sump full of water; Berm along south breached.	Sump has inadequate storage volume; Need to install flow-velocity dissipaters.	Multiple corrections to the site have been made this year. Due to paving the haul road, runoff has increased. Installed retention area as primary defense with berm acting as final point of compliance. Requested facility modification for salt shed apron; need to obtain capital improvement funds to reconstruct apron or find alternate solution (e.g., add a tank to store pumped water).
MS 5002 – Fortuna Wash	Aggregate and reclaimed asphalt pavement mobilizing to floodplain; good housekeeping.	While some of the area is vegetated and provides a buffer to the wash, the north bank is sloughing.	ADOT is determining whether continued use of this ADOT-owned property is necessary. A prior excavated area (pit) is located between the upland area where material is stored and the ordinary high water mark of Fortuna Wash. Remedial action will be determined in Permit Year 4.
MS 5058 – Picacho	Non-compliance issues identified during use of this site by an ADOT contractor.	Secondary containment for fuel and used oil canisters not installed; rills along east side as a result of prior mining activities not maintained.	ADOT Contractor has corrected the items related to its operation and continues inspections as required by the AZPDES CGP. ADOT will address the slope erosion, as necessary, after the construction project is completed.

 Table 5 - Summary of Inspection Findings, Deficiencies, and Corrective Actions

Site No. & Name	Findings	Deficiencies	Corrective Action
MS 5643 – Gila Bend South	Non-compliance was identified during use of this site by an ADOT contractor.	Secondary containment for fuel and used oil canisters not installed; check dams for haul roads not maintained; aggregate wash pond not properly lined.	Generally, these deficiencies were corrected by the Contractor prior to the next regular inspection. ADOT and the Contractor met onsite in May 2011 to ensure interim stabilization was performed satisfactorily.
MS 5781 – Blue Grade	Sediment and aggregate discharge along southwestern boundary.	Ditch and berm that convey sheet flow to a retention basin have not been maintained.	ADOT initiated partial reclamation of the site; scarified and hydroseeded in June 2011. ADOT will be moving stored materials to the confines of the pit by 2013.
MS 6022 – Bowie	Non-compliance issues identified during use of this site by an ADOT contractor.	Track out pad not maintained; fuel containment devices inadequate or not installed; good housekeeping not implemented.	Generally, these deficiencies were corrected by the Contractor before the next regular inspection. ADOT and the Contractor met onsite in June 2011 to ensure interim stabilization was performed satisfactorily.
MS 6451 – Slick Rock Wash	Inadequate reclamation.	Stockpiles of material remain onsite; two areas along the wash bank contain asphalt waste.	There is no evidence of asphalt transport into the wash. The site was utilized nearly 2 decades ago. Vegetated buffers provide interim stabilization until ADOT can fund site remediation.
MS 6662 – Val Vista	Run-on and disturbance by off road vehicles eroding slopes; heavy trash; accepting flows from county road.	Infrequent maintenance of slopes; lack of signage to preclude trespass.	ADOT is coordinating with an onsite Contractor to effect maintenance of rills. A 100-foot-wide buffer along the county road should be re-established to eliminate co-mingling of stormwater. Appropriate signage could curb illegal dumping and further slope erosion due to off road vehicles.
MS 7287 – Centennial Wash	Run-on causing headcutting.	Infrequent maintenance of slopes.	Erosion should be periodically backfilled. ADOT currently does not have a dedicated access to the site and is working with FHWA to obtain ingress/egress. Repairs will occur thereafter.
MS 7525 – Defiance	Sediment and aggregate discharge along western boundary.	Berm not maintained; no velocity control devices; good housekeeping.	ADOT performed partial reclamation of an adjacent mining area to preclude run-on and installed rock check dams on interior roads; need to reestablish the west-side berm and replace wattles at discharge points to an unnamed drainage that intersects the haul road. Scheduled August 2011.
MS 7885 – Sahuarita	Run-on is eroding slopes on the north and northwest boundaries.	Infrequent maintenance of slopes.	ADOT backfilled slopes in June 2011; ADOT is coordinating with adjacent private land owners and will investigate potential illicit discharges from private land.
MS 8109 – BVD	Sediment discharge at northwest and southeast boundaries.	Retention basins and velocity reduction are inadequate for the site.	ADOT reconstructed both retention basins, added check dams, repaired prior check dams; ADOT is evaluating the site activities for revegetation of unused, previously cleared/grubbed areas.
MS 8268 – Tiger Wash West	Sediment discharge southwest of processing area.	Berm breached.	Reconstruct and maintain berm; roughen processing area and direct sheet flows to pit via ditch and check dams.
MS 8541 – Red Bluff	Erosion of southern boundary and haul road intersection.	No BMPs installed.	ADOT has abandoned the plan to obtain a license for use of this site. The land manager notified ADOT that ground disturbing activities shall not occur.
MS 8569 – Dugas	Sediment and aggregate discharge to vegetated buffer from retention basin outfall.	Retention basin is adequately sized; erosion is attributed to lack of maintenance of the contributing ditch/swale.	While discharges of sediment and aggregate were not observed outside the ADOT permit area, maintenance of the ditch/swale and repair of the basin outfall should be prioritized.
MS 8763 – Fish Creek	Retention basin at 2/3 capacity; haul road eroded.	Inadequately sized retention basin; overflowing and eroding haul road.	In February 2011 ADOT commenced mining in an adjacent area and reconfigured the retention basin.

• To the extent practicable, any off-site discharges will be collected and placed within the permitted boundary

#### 3.10.5.1 Sites Removed from Inspection List

Sites removed from inspection requirements within the reporting year include:

- MS 6125, MS 2330 and MS 3486 Removed because no activities associated with mining or material storage are occurring onsite.
- MS 8595, MS 2507 and MS 3543 Removed because no mining activities have commenced onsite and therefore no BMPs have been implemented that require inspection.
- MS 8541 Removed because land reclamation will be part of a larger regional project to be administered by the U.S. Forest Service.
- MS 7021 Removed because the U.S. Army Corps of Engineers (USCOE) has determined that runoff from the area does not discharge into Waters of the U.S.

#### 3.10.5.2 Site Plans and Training

ADOT has implemented a program to develop Erosion and Pollution Control Plans (EPCPs) for sites on the inspection list and provide appropriate training to ADOT personnel regarding inspection requirements. Approximately 15 EPCPs were developed within the reporting year and 33 ADOT personnel received training. The training was conducted in the field and included District Environmental Coordinators, natural resources, maintenance, and construction staff that operate these sources.

# **4 NUMERIC SUMMARY OF SSWMP ACTIVITIES**

Permit Appendix B, Part 4: Provide a numeric summary of BMPs and activities performed each year.

A numeric summary of BMPs and activities performed by ADOT during the reporting year is provided in Appendix F. The progress of BMPs without a numerical goal is described in Section 3, Narrative Summary of SSWMP Activities.

# **5** EVALUATION OF THE SSWMP

Permit Section 3.1.5: Provide an evaluation of the progress and success of the SSWMP each year, including an assessment of the effectiveness of stormwater management practices in reducing the discharge of pollutants to and from the municipal storm sewer system.

An evaluation of ADOT's SSWMP has been conducted utilizing EPA's January 2008 guidance entitled *Evaluating the Effectiveness of Municipal Stormwater Programs*. This guidance provides a set of methods to assess the success of a stormwater management program. The three EPA recommended approaches to evaluate program effectiveness were used:

- Assessing of program operations
- Evaluating social indicators
- Monitoring water quality

#### 5.1 Assessment of Program Operations

The purpose of assessing ADOT's program operation and activities is to verify basic compliance with its Permit and document that tangible efforts have been made to reduce impacts to stormwater. The following progress has been made to its program within the past reporting year:

#### Update of the SSWMP

As reported in the previous Annual Report, ADOT completed an update to its SSWMP in March, 2010. The update consisted of re-structuring the previous SSWMP and documenting current ADOT practices to comply with Permit requirements.

#### Guidance Manuals/Technical Documents

ADOT updated the guidance manuals and technical documents during the reporting year:

- Erosion and Pollution Control Plan Template for ADOT-Licensed Material Sources
- Erosion and Pollution Control Manual (on-going), associated training module
- SWPPP Index Sheets and Stormwater Quality Protection BMPs to include:
  - Arizona Pollutant Discharge Elimination System (AZPDES) Stormwater Pollution Prevention Plan (SWPPP) Index Sheet
  - o National Pollutant Discharge Elimination System (NPDES) SWPPP Index Sheet
  - Sediment Log
  - o Rock Riprap/Rock Mulch
  - o Sediment Wattle
  - o Sediment Control Berm
  - o Silt Fence
  - o Mini Benching
  - o Gravelbag
  - o Rock Check Dams
  - o Stabilized Construction Entrance / Exit Gravel Pad (New BMP Details)
  - o Rock Protection for Cut/Fill Transition
  - o Guardrail End Treatment Slope Protection (New BMP Details)
  - Erosion Control Blanket (New BMP Details)
  - o Storm Drain Inlet Protection Combined BMPs (New BMP Details)
  - Median Storm Drain Inlet Protection (New BMP Details)
  - o Class II Seeding specification updated from July 1, 2010 through June 30, 2011

#### BMP Tracking

ADOT tracked the following BMPs:

- 13 trainings were offered to ADOT employees specifically on stormwater issues (increase from 7 in 2009)
- 53 contractors were trained and certified in erosion control
- 119 miles of drainage canals, and approximately 5,500 roadway miles and associated storm drains, catch basin, outfall structures, and basins were inspected within the Phoenix metropolitan area

- 7 illicit discharges were identified and removed
- 11 FPPPs for ADOT facilities were in process

#### New or Revised Permits or Policies

ADOT has developed new and/or revised the following permits or policies associated with stormwater management:

- Erosion and Pollution Control Plan Template for ADOT-Licensed Material Sources
- Development and implementation of 404/401/402 Awareness class (in conjunction with USACOE)
- Development and implementation of ADOT Seeding Practices for Sustainable Revegetation and Erosion Control class
- Development of policies (in progress):
  - o Environmental Ethic
  - o Environmental Communication
  - o Environmental Risk and Liability
  - Stormwater Management
  - o Facility Pollution Prevention Plans (FPPPs)

#### 5.2 Assessment of Social Indicators

The assessment of social indicators is an important element that tracks knowledge and awareness. It is also an important tool in documenting behavioral changes. The following social indicators were tracked:

- 1,569 volunteer groups participated in the Adopt-a-Highway (AAH) Litter Initiative and is a decrease from 1,609 in 2010 (2.5% drop in participation from 2010 reporting year)
- 3,935 miles of highway were cleaned by AAH volunteers (94% increase from 2010 reporting year; increase due to more groups signing up for 2 mile segments)
- 224 tons of trash were removed from ADOT highways by AAH volunteers (6% increase from 2010 reporting year)
- 2,776 calls were received through the Litter Hotline (3% decrease from 2010 reporting year)
- 119 public events were attended by ADOT where educational materials were displayed (45% increase from 2010 reporting year)
- 8,000 (approximately) stormwater educational materials were distributed (23% increase from 2010 reporting year)

ADOT is also actively involved in four separate stormwater groups as summarized below:

• <u>STormwater Outreach for Regional Municipalities (STORM)</u> – STORM is a regional organization promoting stormwater quality education within the greater Phoenix metropolitan area. STORM was founded in 2002, in response to federal regulations requiring certain municipalities to implement measures to educate the public on protecting the quality of stormwater runoff. STORM educates the public on methods to keep pollutants out of the storm drain system by advertising via radio, television, theater ads, website (<u>www.azstorm.org</u>), and public events.

- <u>Northern Arizona Stormwater Pollution Alliance (NASPA)</u> NASPA is a northern Arizona regional stormwater group consisting of nine regulated MS4s. NASPA was established in 2008 to open dialogue amongst the MS4s and address stormwater issues unique to the region.
- <u>Pima Association of Governments Stormwater Management Working Group</u> (<u>SWMWG</u>) - SWMWG is a southern Arizona regional group that conducts stormwater outreach activities on behalf of PAG members, which are represented on the Stormwater Management Working Group. Members of the Working Group also include representatives from the building and construction industry, state government, the University of Arizona and Davis Monthan Air Force Base.
- American Association of State Highway and Transportation Officials (AASHTO) -AASHTO is a national organization that advocates transportation-related policies and provides technical services to support states in their efforts to efficiently and safely move people and goods. ADOT is a member of AASHTO's Standing Committee on the Environment (SCOE). The SCOE monitors federal environmental laws, regulations, procedures and guidance related to air quality, cultural resources, environmental process, and natural systems and ecological communities. As a member of SCOE, ADOT has participated in the National Stormwater Peer Exchange and Practitioners Meeting. The meeting brought together state transportation departments, regulators (including EPA), and research and technology experts from across the country in a collaborative environment. The purpose of the meeting was to increase stormwater understanding nationwide by learning from each other through collaboration, gaining insight from regulators and officials, increasing knowledge as to current research and new technologies and sharing information at all levels. ADOT viewed this meeting as a unique opportunity to understand and collaborate with others on a national level to address water quality issues. ADOT plans to attend future meeting of this SCOE subgroup.

### 5.3 Monitoring Water Quality

ADOT began installation of dedicated sampling equipment for its MS4 locations and conducted stormwater quality monitoring during the reporting year to include:

- 5 MS4 sampling sites identified for installation of sampling equipment
- 3 maintenance yards monitored near impaired waterways (Nogales and 2 in Superior)
- 2 construction sites monitored at outstanding/impaired waterway (Tucson and Payson)
- 1 industrial facility monitored (Phoenix Durango Sign Factory)

ADOT has completed the installation of 3 MS4 sampling sites and is completing the remaining two. These 5 sites will provide ADOT with a statewide view of the stormwater quality from its roadways and assist with a more broad approach to BMP implementation.

The sampling from maintenance yards and its industrial facility have not identified an exceedance of any surface water quality standard (SWQS). No discharges were reported from construction sites located with <sup>1</sup>/<sub>4</sub> mile of a unique or impaired waterway.

# **6** SSWMP MODIFICATIONS

Permit Section 3.1.6: Provide a description of modifications to the SSWMP each year:

There have been no SSWMP modifications within the last reporting year. However, ADOT will be reviewing its SSWMP in the next reporting cycle to determine necessary program changes as a result of the EPA audit conducted in October 2010.

### 6.1 Addition of New BMPs

Permit Section 3.1.6: Summarize the development and implementation of any new stormwater management practices or pollution controls each year.

ADOT has not developed or implemented any new BMPs during the reporting period.

### 6.2 Temporary or Experimental BMPs

Permit Section 3.1.6: Describe the initiation and cessation of such BMPs and the perceived success of the temporary or experimental stormwater control.

ADOT has not instituted any temporary or experimental BMPs during the reporting period.

### 6.3 Increase of Existing BMPs

Permit Section 3.1.6: Summarize modifications to existing stormwater management practices that increase the number of activities, increase the frequency of activities, or other increases in the level of implementation.

ADOT reports that no current BMPs have been modified that would cause increases in the number of activities, increase the frequency of activities, or otherwise cause an increases in the level of implementation during the reporting period.

#### 6.4 Replacement of Existing BMPs

Permit Section 3.1.6: Describe modifications to replace an ineffective stormwater management practice with an alternate practice by demonstrating that the change will continue to achieve an equivalent reduction in pollutants and will not cause or contribute to a violation of any applicable water quality standard.

ADOT has not modified or replaced any of its current BMPs during the reporting period.

# 7 MONITORING LOCATION INFORMATION

Permit Appendix B, Part 4: Provide a brief description of each stormwater monitoring location (outfall), including the following information: 1. The outfall identification number or name; 2. Address or physical location of the site, including the latitude and longitude of the outfall; 3. Size of outfall's drainage area; 4. Land use(s) with an estimated percentage of each use; 5. Name and description of the receiving water; and 6. Type of monitoring equipment used.

ADOT received final approval from ADEQ in December 2010 for the five proposed monitoring locations. These five locations are identified in the table below:

Table 0. ADOT Stormwater Womtoring Locations					
Outfall Name	Physical Location	Approximate Drainage Area	Land Use	Receiving Water / Designated Use	Monitoring Equipment
B40-196.14	Flagstaff: South side of intersection at Business 40 and SR180	29.30 Acres	Rural Highway (80%) & Commercial Streets (20%)	Rio de Flag / A&Wedw PBC	ISCO Avalanche Full-Size
	Latitude: 35°11'53.39"N Longitude: 111°39'05.48"W				Portable Sampler
101-13.68	Peoria: Loop 101	17.5 Acres	Urban	Skunk Creek /	ISCO 6712

#### Table 6: ADOT Stormwater Monitoring Locations

Outfall Name	Physical Location	Approximate Drainage Area	Land Use	Receiving Water / Designated Use	Monitoring Equipment
	Latitude: 33°37'19.84"N Longitude: 112°14'21.61"W		Highway (90%) & Commercial Streets (10%)	None	Full-Size Portable Sampler
82.0.57	Nogales: Intersection of I19 and SR82 in NE quadrant	59.5 Acres	Urban Highway (80%)	Nogales Wash (Impaired waterway) /	ISCO 6712 Full-Size
00.01	Latitude: 31°21'02.10"N Longitude: 110°55'24.48"W		& Residential Streets (20%)	A&Ww PBC	Portable Sampler
179-313.3	Sedona: At SR179 bridge over Oak Creek	7.35 Acres	State Rout/Business Route (90%) &	Oak Creek (Outstanding waterway) /	ISCO Avalanche Full-Size
Latitude: 34°51'43.93"N Longitude: 111°45'42.68"W			Commercial (10%)	A&Wc FBC, FC, AgL	Portable Sampler
10-255.8	Tucson: I-10 & Grant Rd, within Grant Rd. Maintenance Yard	4.8 Acres	Urban Highway (90%)	Santa Cruz / A&Wedw	ISCO 6712 Full-Size
	Latitude: 32°15'17.19"N Longitude: 110°59'49.39"W		& ADOT Facility (10%)	PBC	Portable Sampler

A&Wedw – Aquatic and Wildlife (effluent-dependent water) A&Ww – Aquatic and Wildlife warmwater

A&Wc – Aquatic and Wildlife coldwater AgL – Agricultural Livestock Watering FBC – Full Body Contact FC – Fish consumption

PBC – Partial Body Contact

Site maps for each MS4 monitoring location are provided in Appendix G and information concerning the ISCO stormwater monitoring equipment is included in Appendix H.

# 8 STORM EVENT RECORDS

Permit Requirement: For each MS4 outfall monitoring location, provide a summary of all subsequent representative storm events necessary to collect at least one representative stormwater sample (greater than 0.1 inch rainfall) occurring within the reporting period, including the date of each event, the amount of precipitation (inches) for each event, and whether a sample was collected, or if not collected, information on the conditions that prevented sampling.

ADEQ required review of the proposed monitoring locations prior to installation of equipment. ADEQ provided concurrence with the monitoring locations in December 2010; and ADOT purchased the appropriate sampling equipment in June 2011. By the end of Permit Year 3, ADOT had completed installation of 3 of the 5 monitoring locations. It is anticipated that the other two sites will be operational by the end of 2011.

# 9 SUMMARY OF MONITORING DATA

Permit Requirement (Appendix B, Part 9): Provide the outfall identification number, the receiving water, designated uses, and the lowest surface water quality standards applicable to the receiving water. Enter the analytical results for the stormwater samples collected for each season of the reporting period for each year. Include, as an attachment, the laboratory reports for stormwater samples.

ADEQ required review of the proposed monitoring locations prior to installation of equipment. ADEQ provided concurrence with the monitoring locations in December 2010; and ADOT purchased the appropriate sampling equipment in June 2011. By the end of Permit Year 3, ADOT had completed installation of 3 of the 5 monitoring locations. It is anticipated that the other two sites will be operational by the end of 2011. ADOT expects all five sampling stations to be fully operational by the end of 2011 and collecting the required samples in Permit Year 4. A summary of stormwater monitoring data previously collected is provided in tabular form in Appendix I.

## **10 ASSESSMENT OF MONITORING RESULTS**

#### 10.1 MS4 Results

As previously stated in Sections 8 and 9, ADOT was unable to conduct stormwater monitoring. ADOT expects all five sampling stations to be fully operational by the end of 2011 and collecting the required samples in Permit Year 4.

#### **10.2** Total Maximum Daily Loads

Permit Requirement (Appendix B, Part 11.D): Assess the effectiveness of BMPs meeting wasteload allocation associated with TMDL.

Total Maximum Daily Loads (TMDL) have not been established for receiving waters at the five approved MS4 stormwater sampling locations.

#### **10.3 Industrial Results**

Permit Requirement (Sections 8.3.3, 8.3.4.1, & 8.5.2.2): Provide a summary of monitoring performed at industrial and construction sites as required in the permit. Describe any adverse conditions that prevented sampling stormwater discharges. Where facility outfalls are essentially identical, justify the sampling of only one outfall.

An adequate volume of discharge was not received at the Durango Sign Factory during the reporting year to allow for stormwater analyses. A Discharge Monitoring Report (DMR) for the industrial monitoring is provided in Appendix J.

#### **10.4 Construction Results**

ADOT and its contractors conducted in-stream monitoring at two construction projects during the reporting year. DMRs for these in-stream monitoring activities are provided in Appendix K.

#### 10.4.1 Marsh Station I-10 Construction Project

ADOT conducted in-stream monitoring from February to April, 2011 within Cienega Creek located approximately 18 miles south of Tucson along Interstate 10. This monitoring was associated with the realignment of the Union Pacific Railroad and the Marsh Station Road. No discharge occurred during the monitoring period.

#### 10.4.2 Doubtful Canyon SR260 Construction Project

ADOT conducted in-stream monitoring from February 15–May 31, 2011 within Doubtful Canyon located approximately 19 miles east of Payson along State Route (SR) 260. This monitoring was associated with a road widening of SR 260. No discharge occurred during the monitoring period.

#### **10.5** Maintenance Facilities

ADOT conducted monitoring at three maintenance yards during the reporting year. DMRs for the maintenance facilities are provided in Appendix L. The laboratory reports for maintenance facilities are included in Appendix M.

#### 10.5.1 Nogales Maintenance Yard

A stormwater sample was collected at the Nogales Maintenance Yard on July 20, 2010 (summer season). Sampling was conducted by installing a Nalgene® Stormwater Sampler prior to the storm event. The Nalgene® is a passive-sample bottle with a floating ball valve that seals off the sample collection port once the bottle is full. The stormwater analysis indicates no applicable SWQS was exceeded. An adequate volume of discharge was not received during the winter season to allow for stormwater collection and analyses.

#### 10.5.2 Superior Maintenance Yard

A stormwater sample was collected at the Superior Maintenance Yard on July 22, 2010 (summer season). Samples were collected manually from a retention basin located along the southwest portion of the yard. The retention basin discharges into Queen Creek Wash via an 18-inch corrugated metal pipe. Queen Creek is identified by the ADEQ as impaired for copper. The stormwater analysis indicates no applicable SWQS was exceeded for this sampling event. An adequate volume of discharge was not received during the winter season to allow for stormwater collection and analysis.

#### 10.5.3 Superior Fuel Yard

A stormwater sample was collected at the Superior Maintenance Yard on July 22, 2010 (summer season). Samples were collected manually from a bermed area along the southwest portion of the yard. This facility has the potential to discharge to Queen Creek, which is identified by the ADEQ as impaired for copper. The stormwater analysis indicates no applicable SWQS was exceeded at this facility. An adequate volume of discharge was not received during the winter season to allow for stormwater collection and analysis.

# **11 ESTIMATE OF POLLUTANT LOADING**

Permit Requirement (Section 8.7.7): Provide an estimate of the pollutant loadings each year from the storm sewer system to waters of the U.S. for each constituent detected by stormwater monitoring within the permit term.

ADOT was unable to estimate pollutant loading for the reporting year since stormwater monitoring could not be conducted. This is due to receiving final approval from ADEQ of the five sampling locations in late 2010, the time needed to order and receive the proper sampling equipment, completion of right-of-way permitting and the installation equipment. ADOT expects all five sampling stations to be fully operational by the end of 2011 and collecting the required stormwater samples in Permit Year 4.

# **12 ANNUAL EXPENDITURES**

Permit Requirement (Appendix B, Part 13): Provide a summary of the expenditures incurred each reporting period (July 1-June 30) to implement and maintain the stormwater management program, including associated monitoring and reporting activities. Provide the estimated budget for implementing and maintaining the stormwater program in the subsequent reporting period. Include a brief description of the funding sources used to support program expenditures.

ADOT does not maintain a specific fund dedicated solely for its stormwater program. However, there are several potential sources available for funding of this program, including the Arizona

Department of Transportation Five-Year Construction Program, the Highway Maintenance Program, and the Administrative Budget.

#### **12.1** Five-Year Construction Program

ADOT's Five-Year Construction Program is a source of funding utilized when a stormwater issue or concern is related to a construction project that is programmed. The Program is reviewed on an annual basis, and at that time, new projects are added and modifications to existing projects are made. There are several sources identified to fund this program. These include federal, state, local, and private sources. The approval process required for incorporation of stormwater issues into the program is the identification of the project and funding requirements and submittal to the Priority Planning Committee, and then in turn, to the Transportation Board for final approval. The program is adopted on July 1st of each year.

#### 12.2 Highway Maintenance Program

Stormwater issues related to maintenance will be covered under the Highway Maintenance Program, which is funded by the State. Issues and costs are identified and submitted for approval to the legislature in August of each year. Funds for new issues are received on July 1<sup>st</sup> of the following year. Currently, there is approximately \$107,000,000 allocated to this program.

#### 12.3 Administrative Budget

The Administrative Budget is an additional source of funding for ADOT stormwater programs and is state-funded and appropriated by the Arizona Legislature. The process is similar to the Highway Maintenance Program. As part of the Administrative Budget, ADOT receives approximately \$62,000,000 in state funds for administrative purposes.

#### 12.4 Office of Environmental Services Budget

The OES was formed in 2006 and its budget has not been established. Currently, the OES operates under several budget accounts. Table 18 provides actual and estimated expenditures implemented under ADOT's Statewide Permit Number AZS000018-2008 requirements.

PROGRAM/ACTIVITY	FY 2010/2011 Actual	FY 2011/2012 Estimated
Street Sweeping – Phoenix and Tucson Area	\$1,688,702	\$105,058
Litter Pick-up and Removal – Phoenix and Tucson Area	\$3,921,864	\$508,318
Implement FIS	\$375,000	\$550,000
Preparation and Implementation of Statewide Permit	\$11,341,329	\$8,434,801
Implement/ Update of SWPPPs for ADOT yards	\$616,790	\$341,200
Dry Weather Sampling – 20% of Outfalls (includes training)	\$5,778	\$15,000
Stormwater Monitoring - Maintenance Yards and MS4	\$33,639	\$48,127
Stormwater Monitoring – Construction Related	\$259,527	\$48,127
Adopt-a-Highway Administration	0	20,000
Preparation of Annual Report	\$29,500	\$29,000
ANNUAL TOTALS	\$18,272,129	\$10,099,631

 Table 7 - Estimated Stormwater Program Comprehensive Annual Budget

# 13 ADOT MS4 AUDIT

### 13.1 Overview of Audit

The EPA conducted an audit of ADOT's MS4 program between October 25 and 29, 2010. The purpose of the audit was to assess compliance with the Permit and to evaluate ADOT's current implementation of its SSWMP. The EPA evaluated four ADOT Districts: Phoenix, Flagstaff, Tucson and Prescott. The audit included document review, interviews, and field verification inspections at 57 ADOT construction sites and maintenance facilities. ADOT staff, including Headquarters and District program managers and construction and maintenance personnel, participated extensively throughout the entire audit process. An ADOT headquarters session was held to obtain information regarding overall program management, program evaluation and oversight, and the MS4-related monitoring program. In addition, the EPA Audit Team held a closing conference at ADOT Headquarters on October 29, 2010, with representatives from headquarters and several Districts. A summary of the audit findings is in Appendix N and the full audit report can be found on the EPA Region 9 website:

http://www.epa.gov/region9/water/npdes/ms4audits.html#azeval

#### 13.2 Positive Attributes of MS4 Program

The EPA Audit Team observed several positive elements of the ADOT MS4 program, including:

- ADOT Environmental Management personnel demonstrated a thorough knowledge of Permit requirements and ADOT's SSWMP.
- ADOT had implemented sound monitoring and sampling practices at construction projects within <sup>1</sup>/<sub>4</sub>-mile of unique and sensitive waters.
- The District Environmental Coordinators were knowledgeable of local stormwater features and maintenance issues and effectively communicated stormwater maintenance needs to ADOT staff.
- EPCP program implementation

### **13.3 Deficiencies of MS4 Program**

The EPA Audit Team also identified program deficiencies and potential Permit violations; however, the items noted are not a formal finding of violation. The following summarizes the most significant deficiencies:

- ADOT had not fully implemented its Employee Stormwater Training Program.
- ADOT had not conducted dry-weather outfall screening of its 71 major MS4 outfalls.
- ADOT had not implemented an adequate illicit connection and illicit discharge detection and elimination program.
- ADOT had not conducted inspections of post-construction BMPs and had not implemented a system to inspect and track conditions of its MS4 system.
- Inspections of ADOT facilities and construction sites revealed common housekeeping deficiencies, including improperly installed BMPs, inadequate containment of pollutant sources and uncertified or outdated SWPPPs.

### **13.4 Proposed ADOT Actions**

ADOT has taken a proactive response to identified deficiencies and is using the audit results to improve its overall MS4 program. An official response to EPA concerning the deficiencies is

forthcoming from ADOT (by November 1, 2011) and will outline actions to the correct issues identified. In general, the proposed actions will include:

- Fully implement the stormwater training program
- Initiate dry-weather screening of major outfalls
- Implement an adequate illicit connect and illicit discharge detection and elimination program
- Conduct internal audits of its stormwater program as needed
- Provide dedicated support staff to ADOT stormwater manager
- Update of existing facility SWPPPs and/or modifying the plans into all inclusive FPPPs
- Perform, as needed, inspection of post-construction BMP controls
- Develop a system to inspect and track conditions of its MS4

ADOT is dedicated to improving its stormwater program and has already made significant changes as a result of the EPA audit.

# APPENDIX A Narrative Summary of SSWMP Activities

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
BEST MANAGEMENT PRACTICES	3.2.1.1, 3.2.1.2, and 3.2.1.3	4.0	Section 4.0 of the 2010 SSWMP details the Best Management Practices (BMPs) to improve operations and reduce pollution at or within ADOT facilities, Statewide and District Maintenance, MS4s, industrial facilities, and material sources. This includes: Measures to control discharges through education Illicit discharge/illegal dumping detection and elimination measures Measures to control discharges from new construction and land disturbances Measures to control discharges from new development and re-development Measures to control discharges from roadways
A. MEASURES TO CONTROL DISCHARGES THROUGH EDUCATION	3.2.2	4.1	ADOT's stormwater education program includes training, public education and outreach, public participation and involvement, and intra- and intergovernmental coordination.
1. ADOT Employee Training	3.2.2.1(a)	4.1.1	ADOT has developed training curricula, as well as a system for administering, tracking, and providing training to all appropriate personnel. New employees receive training within the first year of hire or within the first year of the change in their responsibilities. Refresher training is required at least once every three years.

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
a. Stormwater Awareness Training	3.2.2.1(a) (i)	4.1.1.2	General Stormwater Training is required to educate personnel at all levels of responsibility who are involved in activities that may impact stormwater quality and those staff who may come into contact with or otherwise observe an illicit discharge or illicit connection to the storm sewer system.
			Five awareness classes have been conducted within the past reporting year and 60 personnel trained.
b. Specific Stormwater Training	3.2.2.1(a) (ii)	4.1.1.3	Specific stormwater training is required to educate personnel who are directly involved in activities that may impact stormwater quality or that may generate or manage non- stormwater discharges. Eight specific stormwater training sessions to be offered are: illicit discharges and illegal dumping, non-stormwater discharges, new construction and land disturbances, new development and significant redevelopment, storm sewer system and highway maintenance, and good housekeeping.
			ADOT has conducted 12 stormwater specific training classes within the past reporting year and 52 personnel trained.

Appendix A: Page 2 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
c. Stormwater Library	3.2.2.1(a) (iii)	3.3	This library is a virtual library available at: <u>http://www.azdot.gov/inside_adot/OES/Water_Quality/Stormwater/Manuals.asp</u> . The library contains the following documents: Quality Assurance Manual,
			Erosion and Pollution Control Manual, Maintenance and Facilities BMP Manual, Stormwater Monitoring Guidance Manual for MS4 Activities, Post-Construction Stormwater Control BMP Manual, Stormwater Enforcement Response Plan, Stormwater Monitoring Guidance Manual for Construction Activities, and Stormwater Guidance Manual for Industrial Activities. The SSWMP is available at <u>http://www.azdot.gov/inside_adot/OES/Water_Quality/Stormwater/</u> .
			Documents within the library have been updated as-needed throughout the past reporting year. Until recently, ADOT was not able to track specific hits to the stormwater library website. However, tracking will begin during the next permit term.
2. ADOT Construction Contractor Training and Certification	3.2.2.1(b)	4.1.2	ADOT requires all contractors' inspectors to participate in the Construction Contractor Training and Certification Course offered by the Arizona Association of General Contractors to become an Erosion Control Coordinator (ECC) on ADOT projects. The 16 hour ECC training course covers the erosion and sediment control BMP requirements in the AZPDES CGP and inspection and maintenance of these BMPs.
			Training includes the erosion and sediment control BMP requirements and inspection and maintenance of BMPs.

Appendix A: Page 3 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
3. Erosion and Pollution Control Manual	3.2.2.1(c)	4.1.3	The Erosion and Pollution Control Manual addresses the selection, design, installation and maintenance of effective erosion, sediment, and waste control BMPs that ADOT uses for stormwater and non-stormwater discharges. ADOT conducts annual updates to the Manual.
			A final update to this manual is estimated for completion in February 2011.
4. Public Education and Outreach	3.2.2.2	4.1.4	Public education and outreach are ongoing efforts by ADOT to inform members of the general public about actions individuals can take to reduce transportation-related pollutants and improve water quality.
a. Program Description	3.2.2.2(a)	4.1.4.1	The target audience is the construction industry and the public (highway users). Target pollutants include sedimentation from construction sites, litter, unsecured loads, and tire treads.
			There have been no changes to the program this reporting period.
b. Distribution of Materials through Public Places	3.2.2.2(b) (i)	4.1.4.2	ADOT distributes material through participation with Regional Stormwater Coalitions, Arizona Clean and Beautiful, and Don't Trash AZ.
			ADOT distributes educational material through pamphlets, posters, highway variable message boards, bus stop posters, TV advertisements, radio announcements, and booths at local events.
			ADOT has worked close with STORM and PAG to distribute educational materials.

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
c. Distribution of Materials through ADOT's Stormwater Web Page	3.2.2.2(b) (ii)	4.1.4.3	ADOT maintains a webpage for its stormwater program. The webpage includes a variety of stormwater related documents such as program manuals, maps, document templates, and MS4 contacts. Also included on the webpage are a number of links to other organizations who play a role in stormwater management (ADEQ, EPA, FHWA, etc).
			The following is ADOT's stormwater webpage:
			http://www.azdot.gov/Inside_ADOT/OES/Water_Quality/Stormwater/Index.asp
5. Public Involvement and Participation	3.2.2.3	4.1.5	Public outreach and participation are ongoing efforts by ADOT to educate members of the general public about becoming involved in the stormwater program and improving water quality.
a. Public Availability of Stormwater Documents	3.2.2.3(a)	4.1.5.1	Distribution of materials is accomplished via the Stormwater webpage, STORM, and PAG.
b. Public Comments	3.2.2.3(b)	4.1.5.2	ADOT gathers public comments on the SSWMP via phone or the "Contact Us" link from the ADOT stormwater webpage.
			http://www.azdot.gov/Inside_ADOT/OES/Water_Quality/Stormwater/Index.asp
c. Public Reporting System	3.2.2.3(c)	4.1.5.3	ADOT implemented a public reporting system for illicit discharges and illegal dumping. This system consists of the ADOT hotline and an e-mail address on the Water Quality webpage.
			There has been no change to this system within the past reporting year.

Appendix A: Page 5 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
d. Adopt-A-Highway	3.2.2.3(d)	4.1.5.4	The Adopt-A-Highway program allows individuals to adopt a highway as a volunteer or through a maintenance provider as a sponsor. The program was updated to include a stormwater component.
e. Litter Hotline	3.2.2.3(e)	4.1.5.5	The litter hotline includes a toll free number and an online reporting form for Arizona citizens to report litterers.
			This is an ADOT program that is administered by Arizona Clean and Beautiful (ACB) through a procurement contract.
6. Intra and Inter- Governmental Coordination	3.2.2.4	4.1.6	Intra- and Intergovernmental coordination is a program that includes coordination mechanisms and program enforcement procedures among divisions, groups, sections and districts within ADOT to ensure compliance with the terms of the Permit.
a. Internal Coordination	3.2.2.3(a)	4.1.6.1	Various departments throughout ADOT work together to achieve the goals of the Permit. The OES oversees the stormwater components from each department.
b. Intergovernmental Coordination	3.2.2.3(b)	4.1.6.2	ADOT coordinates with outside agencies such as the Federal Highway Administration, Bureau of Land Management, and the Department of Agricultural Forest Service. ADOT also works with Metropolitan Planning Organizations, Councils of Governments, and Regional Stormwater Coalitions throughout the state.
			ADOT has maintained a working relationship with other government entities via STORM, PAG, NASPA, and AASHTO.

Appendix A: Page 6 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
B. ILLICIT DISCHARGE/ ILLEGAL DUMPING DETECTION AND ELIMINATION MEASURES	3.2.3 3.2.3.1(a)		The IDDE program serves to minimize, detect, investigate, and eliminate illicit discharges, including unauthorized non-stormwater discharges and spills, into ADOT MS4.
1. Minimizing Illicit Discharges and illegal Dumping	3.2.3.1		ADOT's field personnel and DEC's routinely perform visual inspections for illicit discharges and perform monitoring for illegal dumping.
a. Encroachment Permit Enforcement	3.2.3.1(b)	4.2.1.1	ADOT implements and enforces encroachment permits and external party requirements for activities within ADOT's jurisdiction. There have been no changes to the encroachment permit process within the past reporting year.
b. Maintenance and Facilities Best Management Practices (BMPs) Manual	3.2.3.1(c)	4.2.1.2	The Manual describes the selection criteria, design, installation and maintenance of effective BMPs to minimize pollutants in ADOT's non-stormwater discharges. This manual was updated in September 2010.
c. Authorized Non-Stormwater Discharges	3.2.3.1(d)	4.2.1.3	ADOT implements BMPs to minimize the authorized discharge of non-stormwater discharges and pollutants that may result from these flows. BMPs for reducing erosion, sedimentation, and stormwater contamination are contained within the Erosion and Pollution Control Manual and the Maintenance and Facilities BMP Manual.
d. Training	3.2.3.1(e)	See 4.1.1.2 and 4.1.1.3	Training is discussed in 4.1.1.2 and 4.1.1.3 above.

Appendix A: Page 7 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
2. Detecting Potential Illicit Discharges and Illicit Connections	3.2.3.2		Implement BMPs to detect illicit discharges and illicit connections.
a. Outfall Inventory	3.2.3.2 (a)	4.2.2.1	ADOT has been in the process of developing an outfall inventory including the 71 major outfalls. ADOT has also developed a proposal and schedule to identify all outfalls in the Phase II municipalities and all Priority Outfalls statewide. The inventory should be complete in 2013.
			Additionally, ADOT has implemented a Facilities Inventory System (FIS) to identify and track highway features using a GIS database. A pilot program has been initiated within the Kingman District using FIS to track and monitor drainage features.
b. Storm Sewer System Map	3.2.3.2 (b)	4.2.2.2	ADOT is in the process of developing a storm sewer map identifying the location of all ADOT's major outfalls identified to date and their receiving waters. The inventory should be complete in 2013.
			The FIS is being updated to include storm sewer mapping.
c. Stormwater Monitoring Guidance Manual for MS4 Activities	3.2.3.2(c)	3.3.7	This guidance manual provides the procedures used by ADOT personnel to conduct Permit-required monitoring associated with MS4 activities. This monitoring includes dry weather screening for illicit connections and illicit discharges and seasonal wet weather monitoring.
			This manual had no updates in the last reporting year.

Appendix A: Page 8 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
d. Dry Weather Screening	3.2.3.2(d), (e)	4.2.2.4	ADOT implements a dry weather outfall screening and discharge characterization program and inspects major and priority outfalls during the Permit term.
			Dry weather screening has occurred throughout each District within the past reporting period. However, documentation of the screening has not been properly maintained. ADOT is attempting to maintain better records for this activity.
e. Training	3.2.3.2(f)	See 4.1.1.3	Training is discussed in 4.1.1.3 above and has been on-going during the past reporting period.
3. Investigating Potential Illicit Discharges	3.2.3.3		Implement practices and procedures to investigate potential illicit discharges.
a. Establish illicit discharge investigation procedures	3.2.3.3 (a)	4.2.3.1	ADOT's 'Dry Weather Field Screening Sites' portion of the Stormwater Monitoring Guidance Manual for MS4 Activities describes procedures to investigate potential illicit discharges to identify possible sources.
			This manual had no updates in the last reporting year.
b. Investigate Illicit Discharges	3.2.3.3 (b)	4.2.3.2	ADOT initiates investigations and responds to complaints within 15 days from the date
(Source Identification)	3.2.3.3 (c) and	4.2.3.3 and	of detection or report of an illicit discharge. ADOT also implements a system to receive and track reports of illicit discharges and illegal dumping as well as ADOT's response and follow-up actions.
	3.2.3.4(d)	4.2.3.4	Seven illicit discharges were reported and subsequently removed within the past reporting year.

Appendix A: Page 9 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
c. Incidental Dry Weather Discharge Reporting	3.2.3.3(d)	4.2.3.4	ADOT reports dry weather discharges from any ADOT outfall. Within 15 days of detection ADOT initiates appropriate follow-up action to eliminate the discharge, including reporting the discharge to ADEQ as appropriate.
			There have been no dry weather discharges that required follow-up action within the past reporting year.
4. Eliminating Illicit Discharges and Illegal Dumping	3.2.3.4		Eliminate Illicit Discharges and Illegal Dumping.
a. Eliminate Existing Dry Weather Flows	3.2.3.4 (a)	4.2.4.1	This temporary BMP required ADOT to investigate and eliminate (if possible) the sources of existing dry weather flows from the six major outfalls in the July 21, 2005 Summary Report – Dry Weather Screening within the first 90 days of the Permit.
			ADOT completed this requirement in the first reporting year of the Permit.
b. Eliminate Sources of Illicit Discharges	3.2.3.4 (b)	4.2.4.2	ADOT takes action to eliminate source(s) of illicit discharges within 90 days of detection using ADOT's legal authority (Enforcement Response Plan) to terminate illicit discharges and illegal dumping.
			Seven illicit discharges were reported and subsequently removed within the past reporting year.
c. Coordinate with Local Jurisdictions for Complaint Response and Investigation	3.2.3.4 (c)	4.2.4.3	ADOT coordinates with other jurisdictions, including ADEQ, for assistance in enforcement where ADOT lacks legal authority to establish enforceable rules or if an illicit discharger fails to comply with procedures or policies established by ADOT. ADOT coordinates with other jurisdictions as described in the Enforcement Response Plan.
d. Record Actions	3.2.3.4(d)	See 4.2.3.4	Record keeping is discussed in 4.2.3.4.

Appendix A: Page 10 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
5. Responding to Spills	3.2.3.5	4.2.5	ADOT responds to spills as a result of highway accidents and emergencies and implements guidance from the Arizona Department of Emergency Management Plan, ESF-10 Oil and Hazardous Materials Annex.
			ADOT has maintained an emergency response team and responded to 156 incidents throughout the State.
C. MEASURES TO CONTROL DISCHARGES FROM NEW CONSTRUCTION AND LAND DISTURBANCES	3.2.4		Description of a program to reduce the discharge of pollutants from construction sites.
1. Applicability of Construction Requirements	5.1	4.3.1	This BMP contains the requirement for all construction sites and activities that are owned, operated, or contracted by ADOT to comply with provisions of the Permit.
			There have been no changes to construction requirements during the last reporting year.
2. Construction Site SWPPPs	5.2	4.3.2	ADOT requires all construction sites over 1-acre of disturbance to develop a Construction SWPPP.
			There have been no changes to construction requirements during the last reporting year.

Appendix A: Page 11 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs	
a. General Requirements	5.2.1	4.3.2	ADOT or its contractor(s) develop and implement construction site SWPPPs for certain construction sites. SWPPPs are maintained on the site, in accordance with the Construction General Permit, as well as the appropriate ADOT Office.	
			There have been no changes to construction requirements during the last reporting year.	
b. Site and Activity Description	5.2.2	4.3.2	ADOT outlines the required components of the SWPPP including a site description, map, receiving waters, monitoring program, potential pollutants sources, and off-site material storage areas.	
			There have been no changes to construction requirements during the last reporting year.	
c. BMPs to Reduce Pollutants	5.2.3	4.3.2	ADOT outlines the criteria for selection, installation, and maintenance of BMPs for inclusion in Construction SWPPPs. BMPs are contained in the Erosion and Pollution Control Manual, Maintenance and Facilities BMP Manual, Post-Construction Stormwater Control BMP Manual, Stormwater Monitoring Guidance Manual for Construction Activities, and Stormwater Monitoring Guidance Manual for MS4 Activities.	
			There have been no changes to construction requirements during the last reporting year.	

Appendix A: Page 12 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
d. Construction Inspections	5.2.5	4.3.2	ADOT requires routine inspections of construction sites to ensure BMPs are functional and effective and that the SWPPP is being properly implemented. Routine inspections are conducted jointly by the Resident Engineer (RE) and the Erosion Control Coordinator (ECC) and are conducted every 7-14 days or after a rain event. Following an inspection, a Construction Compliance Evaluation Report is filed documenting the findings of the inspection and basic inspection details. A more in-depth inspection is conducted by the Construction Site Inspector. Findings are documented and delivered to the RE who then has 14 days to address all deficiencies. Once the deficiencies are addressed, or within 14 days, the Resident Engineer sends a response to the Construction Site Inspector detailing the status of deficiencies. Responses are reviewed and scored for completeness by the Construction Site Inspector and a final report is sent to the District Engineer. Routine inspections have occurred as required throughout the last reporting year.
e. Construction BMP	5.2.4	4.3.2	
Maintenance	0.2.4	4.3.2	ADOT requires a maintenance plan for all erosion and sediment control BMPs. The ECC and/or RE are responsible for oversight of the requirements of this section, including maintaining all BMPs in effective operating condition, performing maintenance of ineffective BMPs within seven days of discovery and before the next anticipated storm event, and removing sediment from sediment traps when the design capacity has been reduced by 50%.
			There have been no changes to this construction requirement during the last reporting year.

Appendix A: Page 13 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs	
f. SWPPP Updates	5.2.6	4.3.2	ADOT requires updates to the construction site SWPPP to be conducted within 15 calendar days following an inspection. There are two copies of the SWPPP that are updated by the ECC throughout the course of the construction project. One copy of the SWPPP is located at the construction site while the second copy is maintained at the applicable District office. Construction Site Inspectors verify both SWPPPs are being updated before beginning each site inspection.	
			one construction own in a nave been updated as-needed.	
3. Operators under Contract to ADOT for Performing Construction Activities	5.3		There have been no changes to this construction requirement during the last reporting year.	
a. Compliance with Construction General Permit	5.3.1	4.3.3.1	ADOT requires its contractors to comply with the AZPDES CGP for regulated construction projects. This requirement includes the requirement to file an NOI for each construction project or site.	
			For work on Tribal Land, NOIs are filed by both the contractor and ADOT to the EPA. For work on non-Tribal Land, an NOI is only filed by the contractor.	
			There have been no changes to these construction requirements during the last reporting year.	

Appendix A: Page 14 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
b. NOT - Transfer of Responsibility to ADOT	5.3.2	4.3.3.2	ADOT requires contractors to file a NOT to terminate their responsibility for site activities once a site and interim stabilization is in place. ADOT assumes responsibility for the site until final stabilization is achieved for the entire project. ADOT also removes all <u>temporary</u> sediment control BMPs that may impede stormwater flow as soon as practicable after final stabilization. If work is conducted on Tribal Land, ADOT files an NOT to the EPA as required.
			There have been no changes to this construction requirement during the last reporting year.
c. Completed Construction Site Inventory	5.3.3	4.3.3.3	Twice per year (by July 10 and January 10) ADOT provides ADEQ with an electronic list of all construction projects, including the name of the project and its associated AZCON number(s) that have achieved final stabilization and that ADOT considers to be complete. This list is compiled based on memos from the RLA who conducts the stabilization inspection.
			The inventory has been provided to the ADEQ as required during the last reporting year.
d. Enforcement Tracking and Reporting	5.3.4	4.3.3.4	ADOT maintains a list and description of all violations and their resolution, including any enforcement actions taken against its contractors. ADOT achieves enforcement actions through implementation of its stormwater Enforcement Response Plan. The list is generated from the inspection letters from Construction Site Inspectors. The RE is responsible for maintaining a file for all findings and reporting them to the Water Quality Group.
			ADOT has maintained a list and description of violations during the last reporting year.

Appendix A: Page 15 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
D. MEASURES TO CONTROL DISCHARGES FROM NEW DEVELOPMENT AND REDEVELOPMENT	3.2.5	4.4	Develop and implement a comprehensive planning procedure and BMPs to prevent or minimize water quality impacts from new highway development and re-development.
1. Post-Construction Stormwater Control BMP Manual	3.2.5.1	4.4.1	These guidance manual details the post-construction BMPs ADOT uses to comply with the Permit. The manual identifies factors for consideration during selection of BMPs and provides BMP design guidance.
			This manual had no updates in the last reporting year.
2. Install Post-construction Stormwater Control BMPs	3.2.5.2	4.4.2	ADOT requires post-construction stormwater control BMPs be installed for all newly developed or redeveloped roadways that discharge stormwater runoff to impaired or unique waters.
			This manual had no updates in the last reporting year.
3. Inventory, Inspect, and Maintain all Post-construction Stormwater Pollution Control BMPs	3.2.5.3 and 3.2.6.1(a)	4.4.2	The Maintenance Group inventories, inspects, and maintains all post-construction BMPs. ADOT has hired a consultant to inventory all stormwater assets for which ADOT is responsible throughout the State. This survey is not anticipated to be completed until 2013. The Maintenance/Facilities SWAT is in the process of developing a uniform system to implement for conducting regular maintenance in each district.
4. Training	3.2.5.4	See 4.1.1.3	Training is discussed in Permit reference 4.1.1.3 (Page 2 of this table).
E. MEASURES TO CONTROL DISCHARGES FROM ROADWAYS	3.2.6		Previously discussed in Permit reference 4.1.1.3 (Page 2 of this table).

Appendix A: Page 16 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
1. Maintenance and Facilities Best Management Practices Manual	3.2.6 (a) and (b)	See 4.2.1.2	The Maintenance and Facilities BMP Manual is discussed in 4.2.1.2 above.
2. Storm Sewer System and Highway Maintenance	3.2.6.1		ADOT shall implement BMPs for operating and maintaining roadways and drainage ways to minimize discharges to and from the storm sewer system in all MS4 Compliance Areas.
a. Inventory Post-Construction Stormwater Pollution Control BMPs	3.2.6.1(a)	4.5.2.1	ADOT is in the process of developing an inventory of post-construction stormwater pollution control BMPs. See 4.4.2 above.
b. Inspect Storm Sewer System	3.2.6.1 (b)	4.5.2.2	ADOT has implemented a system to inspect and record the condition of the storm sewer system. The District Engineer maintains a record of inspections and conditions found and forwards the list to the Water Quality Group annually.
			ADOT is in the process of populating the FIS, a geographic information system capable of tracking and maintaining an inventory of ADOT's highway features, including drainage features. The FIS allows for attribute data to be stored and tracked for each feature identified and will be a useful tool in assisting with outfall inspections. It is ADOT's intent to eventually use the FIS throughout the State.

Appendix A: Page 17 of 20

New Table of Contents	Permit Reference	2010 SSWMP Reference or Other Source	Description and Implementation of BMPs
c. Develop Maintenance Schedules and Priorities	3.2.6.1 (c)	4.5.2.3	Each year ADOT conducts routine maintenance of its storm sewer system. Maintenance schedules and priorities are evaluated annually by District. The MSLT has developed a standard method for developing a routine maintenance schedule that includes prioritization, implementation and recordkeeping. Each year the maintenance schedule is reviewed and revised as necessary.
			A maintenance schedule will be included with ADOT's implementation of the FIS as previously described.
d. Stormwater System Repair, Maintenance, and Cleaning	3.2.6.1(d), (e), and (f)	4.5.2.4	ADOT conducts repairs, maintains, and cleans its roadways and storm sewer system to minimize the discharge of pollutants from the storm sewer system. During maintenance activities, each storm drain inlet is assessed for evidence of illicit discharges or illegal dumping in accordance with the Maintenance and Facilities BMP Manual. If evidence is discovered, illicit discharges or illegal dumping are reported and followed up according to 4.2.4.2 above. While conducting maintenance and cleaning activities ADOT implements BMPs to reduce the discharge of pollutants from unpaved roads, shoulders, parking lots, unpaved roads, and unpaved parking lots. ADOT properly disposes of all waste removed from its storm sewer system and facilities.
			ADOT has conducted system repair, maintenance and cleaning of its stormwater conveyance system on an as-needed basis throughout Permit Year 3.
3. Training	3.2.6.1 (g)	See 4.1.1.3	Training is discussed in 4.1.1.3 above.
3. Roadside Maintenance Program	3.2.6.2		Training is discussed in Permit reference 4.1.1.3 (Page 2 of this table).

Appendix A: Page 18 of 20

New Table of Contents	Permit Reference	Reference Description and Implementation of BMPs						
a. Pesticide and Fertilizer Application	3.2.6.2(c)		BMPs have been maintained to manage vegetation along ADOT roadway throughout Permit Year 3.					
i. Optimize Chemical Applications	3.2.6.1 (c)(i)	4.5.3.1	ADOT requires its employees and commercial applicators to implement practices and procedures in accordance with the Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA) at ADOT facilities and within right-of-ways. ADOT BMPs address the timing of applications in relation to precipitation events and require applicators to use only pesticides approved for aquatic use in areas within or adjacent to a water of the U.S The Stormwater Monitoring Guidance Manual for Construction Activities and the Arizona Office of Pest Management licensing requirements contain the guidelines governing pesticide, herbicide, and fertilizer application.					
			Stormwater Monitoring Guidance Manual for Construction Activities and the Arizona Office of Pest Management licensing requirements contain the guidelines for FIFRA applications; however, the existing text in this box stated: Maintenance and Facilities Best Management Practices Manual and the Vegetation Management Plan regarding insecticide, fungicide, and rodenticide applications are what ADOT follows.					
ii. FIFRA Certification	3.2.6.1 (c)(ii)	4.5.3.2	ADOT personnel have maintained their FIFRA certification as required.					
iii. Training	3.2.6.2 (c)(iii)	See 4.1.1.3	Training is discussed in Permit reference 4.1.1.3 (Page 2 of this table).					

Appendix A: Page 19 of 20

New Table of Contents	Permit	2010 SSWMP Reference	Description and Implementation of BMPs
	Reference	or Other Source	
b. Erosion Abatement Projects	3.2.6.2(d)	4.5.3.4	ADOT has a system to identify, track, and prioritize erosion abatement projects in areas where slopes are 3:1 or greater and actively eroding with sediment leaving ADOT's right of way. The Erosion and Pollution Control Manual contains BMPs guiding site stabilization and erosion control.
			ADOT has identified the existing Slope Management Program (SMP) database as a potential tool to identify, track and prioritize erosion abatement projects. The SMP is a Microsoft ACCESS database that allows ADOT to track and prioritize the severity of rock slopes, soil cuts and embankments throughout the state. Additional potential mechanisms may be investigated in Permit Year 4.
4. Winter Storm Policies	3.2.6.3	4.5.4	ADOT implements BMPs to minimize stormwater impacts from application of salt, de- icing and anti-icing chemicals, abrasives for snow and ice removal, salt and sand storage, and snow disposal areas. These BMPs are described in the Winter Storm Management of Arizona State Highways Environmental Overview, Winter Storm Management of Arizona State Highways Operations Manual, and Maintenance and Facilities BMP Manual.
			These manuals have been updated as-needed throughout Permit Year 3.

Appendix A: Page 20 of 20

# APPENDIX B Outfall Inspection and Tracking

				Appendix B - Majo Inspection Dat						
Route No- Mile Post	Outfall Location	Outfall Description	Receiving Water	Potential Sources of Flow	Inspection Date	Inspector	Outfall Condition	Maintenance Need	Dry Weather Flow Present	Follow up actions (if any)
Phoenix Area										
101-6.05	Loop 101 Agua Fria Freeway	Trapezoidal Open Channel, Concrete	New River	None	8/28/2008	PM	Good	None	No	None
	300' W of 107th Ave.	TW=102' D=12'			0,20,2000					
101-7.76	Loop 101 Agua Fria Freeway	Trapezoidal Open Channel, Concrete	New River	Irrigation tail water	6/30/2005	JB	Good	Remove some	No	Remove some
	<sup>1</sup> ⁄ <sub>4</sub> mile S. of Northern Ave. and 1000' W. of 99th Ave.	TW=82' D=8'						vegatiaon		excess vegetation
101-10.84	Loop 101 Agua Fria Freeway ½ mile N. of Peoria Ave.	Trapezoidal Open Channel, Concrete & Soil Cement TW=65'	New River	None	8/16/2005	JB	Good	None	No	None
	along E. Bank of New River	D=12'								
101-11.85	Agua Fria Freeway ½ Mile S. of Thunderbird Rd. and 300'	Trapezoidal Open Channel, Concrete	New River	None	8/16/2005	JB	Good	None	No	None
	West	D=8'								
101-13.44	Loop 101 Agua Fria Freeway	Dual Circular Pipe, Concrete	Skunk Creek	None	8/28/2008	JB	Good	None	No	None
	200' S. of S.B. Bridge over Skunk Creek and 80' East	DIA=42"			0,20,2000					
101-13.68	Loop 101 Agua Fria Freeway 30 ' N of NB Bridge over Skunk Creek and	Trapezoidal Open Channel, Concrete TW=22'	Skunk Creek	None	8/16/2005	JB	Good	None	No	None
	80' E Loop 101	D=4'								
101-14.38	Agua Fria Freeway 1200' S. of Bell Road Traffic Interchange &	Open Channel, Concrete TW=28'	New River	None	8/23/2006	JB	Good	None	No	None
	300' West Loop 101	D=10'								
101-15.18	Agua Fria Freeway 4/10 Mile N of Bell Rd. & 500' West	Circular Pipe, Concrete	New River	None	8/23/2006	JB	Good	None	No	None
	Loop 101 Agua Fria Freeway	Circular Pipe, Concrete								
101-16.31	4/10 of a mile S. of Beardsley Rd. and 300' W.	DIA=48"	New River	None	8/30/2007	SL	Good	None	No	None
101-16.62	Loop 101 Agua Fria Freeway	Circular Pipe, Concrete	New River	None	8/30/2007	SL	Good	None	No	None
101-16.62	2/10 of a mile S. of Beardsley Rd. and 500' W	DIA=48"	New River	None	8/30/2007	SL	Good	none	INO	None
101-16.74	Loop 101 Agua Fria Freeway	Trapezoidal Open Channel, Concrete	New River	None	8/30/2007	SL	Good	None	No	None
	150' S of Beardsley Rd. & 2800' W. of 75 Ave	TW=56' D=11'			0,00,2001		0000			
101-20.19	Loop 101 Agua Fria Freeway	Circular Pipe, Concrete	Skunk Creek	None	8/30/2007	SL	Good	None	No	None
	<sup>1</sup> / <sub>2</sub> Mile S. of Beardsley Rd. at 51st Ave Loop 101	DIA=36"								
101-21.23 B	Agua Fria Freeway	Circular Pipe, Concrete	Skunk Creek	None	8/30/2007	SL	Good	None	No	None
	245' E of 43rd Ave & N. Side of Beardsley	DIA=42"								

				Appendix B - Majo Inspection Dat						
Route No- Mile Post	Outfall Location	Outfall Description	Receiving Water	Potential Sources of Flow	Inspection Date	Inspector	Outfall Condition	Maintenance Need	Dry Weather Flow Present	Follow up actions (if any)
	Loop 101 Agua Fria Freeway	Trapezoidal Open Channel, Concrete								
101-21.23 A	260' E of 43rd Ave & N side of N Frontage Rd.	TW=20' D=2'	Skunk Creek	None	8/30/2007	SL	Good	None	No	None
101-21.83	Loop 101 Agua Fria Freeway	Circular Pipe, Concrete	Scatter Wash	None	8/30/2007	SL	Good	None	No	None
	2000' W. of 35th Ave. & S. side of S. Frontage Rd.	DIA=96"								
101-21.87A	Loop 101 Agua Fria Freeway	Trapezoidal Open Channel, Concrete	Scatter Wash	None	8/30/2007	SL	Good	None	No	None
101-21.07A	1500' W of 35th Ave & N side of N Frontage Rd.	TW=32' D=8'		None	0/30/2007	52	0000	None	NO	None
404 04 070	Loop 101 Agua Fria Freeway	Circular Pipe, Concrete	Cootton Mach	Nama	0/00/0007	0	Oned	Neve	Nia	Naza
101-21.87B	1600' W. of 35th Ave & N side of N. Frontage Rd.	DIA=42"	Scatter Wash	None	8/30/2007	SL	Good	None	No	None
101 - 25.92	Loop 101 Pima Freeway	2 Barrel Box Culvert, Concrete	Cave Creek	None	8/28/2008	PM	Cood	None	No	None
101 - 25.92	S. of 101, 1/4 mile west of 7th St into east bank of Cave Creek	2 - 8' x 6'	Cave Creek	None	8/28/2008	РМ	Good	None	INO	None
404 50.07	Loop 101 Pima Freeway	2 Barrel Box Culvert, Concrete		News	0000		Quart	Nexe	N La	News
101 - 50.87	N bank of Salt River in NE quadrant of 101 / 202 interchange	2 - 10' x 10'	Salt River	None	2008	JB	Good	None	No	None
404 54 07	Loop 101 Pima Freeway	3 Barrel Box Culvert, Concrete	Calk Diver	Indention	C/00/0005	סו	Oned	Remove some	Maa	Remove excess
101-51.07	S bank of Salt River, E of 101 under 202 interchange	3 - 12' x 12'	Salt River	Irrigation	6/29/2005	JB	Good	vegetation	Yes	vegatation
10,100,0	I-10 Papago Freeway	Circular Pipe, Concrete			2222	10				
10-130.2	W. bank of Agua Fria River under Van Buren St.	DIA=48"	Salt River	None	2006	JB	Good	None	No	None
10-130.3	I-10 Papago Freeway	Trapezoidal Open Channel, Concrete							Yes - irrigation	
Papago Channel	<sup>1</sup> / <sub>2</sub> Mile W. of El Mirage Rd. & 100' N. of I- 10	TW=80' D=10'	Agua Fria River	Irrigation water	6/30/2005	SL	Good	None	water	None
10-145.17	I-10 Papago Freeway	Circular Tunnel, Concrete	Calk Diver		C/00/0005		Oned	Neve	Yes - irrigation	Nega
West Tunnel	Central Ave. W side @ N. Bank of Salt River	DIA=21"	Salt River	Irrigation water	6/29/2005	JB	Good	None	water	None
10-149.18 East Tunnel	I-10 Papago Freeway	Circular Tunnel, Concrete	Salt River	Irrigation water/Interconnects	6/29/2005	JB	Good	None	Yes - irrigation and intefconnects	None
	20th St. E. side@ N. Bank of Salt River I-10 Maricopa	DIA=21"		water/interconnects						
10-150.44	Freeway	Circular Pipe, Concrete	Salt River	None	2008	JB	Good	None	No	None
	N. Bank of Salt River @ W side of I-10	D=36"								
10-150.45	I-10 Maricopa Freeway	Dual Circular Pipe, Concrete	Salt River	None	2008	JB	Good	None	No	None
	N. Bank of Salt River @ E. side of I-10 I-10 Maricopa	D=72"								
10-151.06	Freeway NW Quadrant of I-10 & University Traffic Interchange	Circular Pipe, Concrete D=66"	Tempe Drain	None	8/30/2006	SL	Good	None	No	None

				Appendix B - Majo Inspection Dat						
Route No- Mile Post	Outfall Location	Outfall Description	Receiving Water	Potential Sources of Flow	Inspection Date	Inspector	Outfall Condition	Maintenance Need	Dry Weather Flow Present	Follow up actions (if any)
	I-10 Maricopa Freeway	Dual Box Culverts, Concrete								
10-162.44	NW quadrant of I-10 / Maricopa Road Interchange	2 - 10' x 8'	Gila Floodway	None	2008	JB	Good	None	No	None
	S.R. 143 Hohokam Expressway	Circular Pipe, Concrete								
143-2.90	600' N. of Van Buren & 350' E of S.R. 143 at west bank of Old Cross Cut Canal	D=66"	Old Cross Cut Canal	None	8/30/2006	SL	Good	None	No	None
153 - 1.64	S.R. 153 Sky Harbor Expressway	Circular Pipe, Concrete	Salt River	Irrigation	6/29/2005	JB	Good	Remove some	Yes	Remove excess
155 - 1.04	S. bank of Salt River west of expressway	D=72"	Sait River	water/Interconnects	0/29/2005	JD	Good	vegetation	165	vegatation
17 - 198.48	I-17 Black Canyon Freeway	Circular Pipe, Concrete	Colt Diver	Nene	2008	חו	Cood	Nene	No	Nega
17 - 198.48	2200' S. of Buckeye Rd. & 1700' E. of 27th Ave.	D=102"	Salt River	None	2008	JB	Good	None	No	None
17-208.2	I-17 Black Canyon Freeway	Circular Pipe, Concrete	Arizona Canal	None	2008	JB	Good	None	No	None
17-200.2	1/4 mile north of Dunlap, west of I-17 into Az Canal	D=36"	Diversion Channel	None	2008	JD	Good	None	NO	None
	Loop 202 East Papago Freeway	Dual Box Culverts, Concrete								
202-3.57	Directly under Loop 202/SR143 interchange at E. bank of Relocated Old Cross Cut Canal	2 - 3' x 4'	Old Cross Cut Canal	None	6/30/2005	JB	Good	None	No	None
000 5 4 4	Loop 202 East Papago Freeway	Open Channel, Earthen			0/00/0000			N		
202-5.14	N of north side levee on Salt River ¼ mile west of 202 and E of 143	TW=60' D=5'	Salt River	None	8/30/2006	SL	Good	None	No	None
202-5.90	Loop 202 East Papago Freeway	Circular Pipe, Concrete	Salt River	Nene	8/30/2006	SL	Cood	Nene	Ne	Nega
202-5.90	1000' E. of Priest Dr. and 2200' N. of 1st St.	DIA=36"	Sait River	None	8/30/2006	5L	Good	None	No	None
202-7.44	Loop 202 East Papago Freeway	Circular Pipe, Concrete	Salt River	None	9/6/2007	JB	Good	Note - outfall within Tempe	Unk	None
202-7.44	1100' W. of Rural Rd. @ N Bank of Salt River	DIA=48"	Sait River	None	9/6/2007	JD	Good	Town Lake	UTIK	none
202-7.98	Loop 202 East Papago Freeway	Dual Box Culvert, Concrete	Salt River	None	9/6/2007	JB	Good	Note - outfall within Tempe	Unk	None
202-7.90	1100' E. of Rural Rd. @ N. Bank of Salt River	2 - 8' x 8'	Sait River	None	9/0/2007	JD	Good	Town Lake	Ulik	None
202-8.28	Loop 202 East Papago Freeway	Circular Pipe, Concrete	Salt River	None	8/28/2008	PM	Good	None	Yes - Rainfall	None
202-0.20	2300' E. of Rural Rd. @ N. Bank of Salt River	D=48"	Gait River	None	0/20/2000		0000		<96 hrs	
202-8.65	Loop 202 East Papago Freeway	Circular Pipe, Concrete	Salt River	None	2008	JB	Good	None	No	None
202-0.00	4000' E. of Rural Rd. @ N. Bank of Salt River	D=36"	Sait River	NOTE	2000	JD	Guu		INU	NOTE

				Appendix B - Majo						
			T	Inspection Dat	abase					
Route No- Mile Post	Outfall Location	Outfall Description	Receiving Water	Potential Sources of Flow	Inspection Date	Inspector	Outfall Condition	Maintenance Need	Dry Weather Flow Present	Follow up actions (if any)
202 44.22	Loop 202 East Papago Freeway	Trapezoidal Open Channel, Concrete	Colt Diver	Nene	0/20/2000	PM	Cood	Naza	No	Nega
202 - 14.22	S bank of Salt River, 1000' W of Mesa Dr, 2200' N of 202	TW=43' D=11'	- Salt River	None	8/28/2008	PIVI	Good	None	No	None
51-5.45	S.R. 51 Squaw Peak Parkway	Circular Pipe, Concrete	Arizona Canal	None	2008	JB	Good	None	No	None
51-5.45	300' N & W of Intersection @ 18th St. and Ocotillo	D=48"	Diversion Channel	None	2008	JD	Good	none	NO	None
51 -7.04	S.R. 51 Squaw Peak Parkway	Circular Pipe, Concrete	- Dreamy Draw Wash	None	8/28/2008	PM	Good	Tree trimming	No	Remove vegation
51 -7.0 <del>4</del>	400' S and E of Intersection @ Northern and Squaw Peak Freeway	D=48"	Dicarny Diaw Wash	None	0/20/2000	1 101	0000			Remove vegation
51-8.22	S.R. 51 Squaw Peak Parkway	Concrete Box Culvert, Concrete	- Dreamy Draw Wash	None	2008	JB	Good	None	No	None
01 0.22	500' E of Northern, 400' S of 51 @ Dreamy Draw	10' x 6'	Broanly Braw Wach	T tono	2000	00	0000			- Tono
51 - 10.91	S.R. 51 Squaw Peak Parkway	Trap Channel, Concrete	Indian Bend Wash	None	2008	JB	Good	None	No	None
	1/4 mile east of 51, 250' S of Sweetwater into Indian Bend Wash	TW=86' D=8'			2000					
51 - 11.62	S.R. 51 Squaw Peak Parkway	Circular Pipe and Box Culvert, Concrete	Indian Bend Wash	None	8/28/2008	PM	Good	None	No	None
	400' N of Thunderbird into Indian Bend Wash	84" pipe, 10' x 6' CBC							NO	
87-178.55	S.R. 87 Mesa-Payson Hwy	Open Channel, Concrete	- Salt River	None	8/28/2006	JB	Good	None	No	None
	S. of S.R.87 east of McDowell Rd intersection									
60-187.43	S.R. 60 Superstition Freeway	Trapezoidal Open Channel, Concrete	East Maricopa		2008	JB	Good	None	No	None
	<sup>1</sup> / <sub>2</sub> mile E of Higley Rd. & S.R. 60 Traffic Interchange north side	TW=44' D=8'	Floodway							
60-189.65	S.R. 60 Superstition Freeway	Trapezoidal Open Channel, Concrete	- Sossoman Chanel	None	9/3/2008	PM	Good	None	No	None
-	1/4 mile E of Sossman & S.R. 60 Traffic Interchange	TW=48' D=9'								
Tucson Area	I-10	Circular Pipe, Concrete	1	I I		-		L	[	
10-260.7	N. Side of Julian Wash at 10th Ave, S. of I- 10	DIA = 72"	Julian Wash	None	8/22/2005	JB	Good	None	No	None
10 200.1	I-10	Circular Pipe, Concrete								
10-261.5	1400' W. of S. Park Ave., 1300' N. of Ajo Way- E. of SPRR	Dia = 78"	Julian Wash	None	8/22/2005	JB	Good	None	No	None
	I-10	Oval Pipe, CM								
10-264.6	1200' S. of I-10 & Palo Verde Rd. Interchange, W. side of Palo Verde & N. Bank Julian Wash	56" x 42"	Julian Wash	None	8/23/2005	JB	Good	None	No	None
	I-19 Nogales Freeway	Circular Pipe, CM								
19-59.0	1200' S. of I-19 & Valencia Interchange S. of Valencia & E. bank Santa Cruz River	Dia = 36"	Santa Cruz River	None	6/21/2006	JB	Good	None	No	None
	I-19 Nogales Freeway	Trapezoidal Open Channel	- Rodeo Wash	None	6/21/2006	JB	Good	None	No	None
19-61.7	900' S. of I-19 & Ajo Way Interchange E. side of I-19 & S. Bank of rodeo Wash	TW=10' D=2'		INOLIG	0/21/2000		5000	NONE		None

	Appendix B - Major Outfalls Inspection Database											
Route No- Mile Post	Outfall Location	Outfall Description	Receiving Water	Potential Sources of Flow	Inspection Date	Inspector	Outfall Condition	Maintenance Need	Dry Weather Flow Present	Follow up actions (if any)		
	S.R. 86 Ajo Highway	Circular Pipe, CM										
86-171.1	1600' S. of I-19 & Ajo Way Interchange @ W. bank of Santa Cruz River S. of Ajo Way	Dia = 36"	Santa Cruz River	None	6/21/2006	JB	Good	None	No	None		
	U.S. 77 Tucson Florence Highway	Circular Pipe, CM				_	_		Yes - irrigation			
77-71.74	S. Bank of Rillito River E. of Oracle Road	Dia = 72"	Rillito River	Irrigation	8/29/2008	GH	Good	None	water	None		
	U.S. 77 Tucson Florence Highway	Open Channel, Concrete										
77-71.8	N. Bank of Rillito River E. of Oracle Road	TW=40' D=7'	Rillito River	None	optional	JB	Good	None	No	None		
	U.S. 77 Tucson Florence Highway	Circular Pipe, Concrete	Tributary of Canada	None								
77-78.7	S.E. Quadrant of U.S. 77 & Greenock Dr	2 Dia = 36"	Del Oro		8/27/2008	GH	Good	None	No	None		
	U.S. 77 Tucson Florence Highway	Circular Pipe, Concrete	Tributary of Canada									
77-78.9	N.E. Quadrant of U.S. 77 & Greenock Dr	Dia = 42"	Del Oro	None	8/27/2008	GH	Good	None	No	None		
	U.S. 77 Tucson Florence Highway	Open Channel, Concrete	Tributary of Canada		- /							
77-79.9	S.E. Quadrant of U.S. 77 & Hanley Road	TW=25' D=8'	Del Oro	None	8/29/2007	SL	Good	None	No	None		
	U.S. 77 Tucson Florence Highway	Open Channel, Concrete										
77-80.8	N.W. Quadrant of U.S. 77 & Canada Del Oro	TW=30' D=10'	Canada Del Oro	None	2003	JB	Good	None	No	None		
	S.R. 210 Aviation Parkway	Circular Pipe, Concrete										
210-1.2	S.E. of Intersection of 10th Street & 3rd Ave.	Dia = 96"	Arroyo Chico	Irrigation	8/29/2007	JB	Good	None	Yes	None		
	S.R. 210 Aviation Parkway	Circular Pipe, Concrete										
210-2.7	N.W. Quadrant @ Intersection of Campbell Ave. & Aviation Parkway	Dia = 108"	Railroad Wash	Irrigation	8/29/2007	JB	Good	None	Yes	None		

APPENDIX C Notice of Illegal Discharge Letter



Arizona Department of Transportation

Intermodal Transportation Division

206 South Seventeenth Avenue Phoenix, Arizona 85007-3213

Janice K. Brewer

John S. Halikowski Director

DATE

Floyd Roehrich Jr. State Engineer

### NOTICE OF ILLEGAL DISCHARGE OR CONNECTION

Person or Business Name Address Phoenix, AZ

Dear Property Owner:

The Arizona Department of Transportation (ADOT) is responsible for maintaining not only roadways, but also the extensive storm drain network located within the State rights-of-way. The Arizona Pollutant Discharge Elimination System (AZPDES) Program, which is a component of the Clean Water Act of 1972, requires ADOT to control the amount of pollutants entering the drainage system. Part of this charge is the detection and elimination of illegal discharges or connections to the system that may contain pollutants or are otherwise not allowed. Left uncorrected, any pollutants entering the system will ultimately impact nearby streams, as storm drainage is not treated at any sort of treatment facility. In addition, neighboring property owners are not allowed to occupy, use or interfere with public right of way without permission. Any discharge/connection without permission is an illegal encroachment on ADOT right of way.

An inspection of the drainage system has occurred in the vicinity of your property and an illegal connection/discharge was discovered entering into the ADOT system. The discharge/connection was discovered on date at business name and address.

Indicators or Source include piping and staining.

Photographs of this discharge/connection are enclosed with this letter. In addition, I have enclosed an aerial photograph showing the location of this discharge/connection.

This discharge or connection must be ceased or removed within 30 days. A follow-up investigation will be conducted after that time to ensure compliance. If the situation is not corrected, ADOT will take corrective measures, including but not limited to sending this matter to the Arizona Office of the Attorney General so that a lawsuit may be filed. In the alternative, ADOT may remove the discharge/connection and bill you directly pursuant to A.R.S. § 28-7053.

If the illegal discharge/connection cannot be removed within 30 days, you do not understand this notice, or you disagree that an illegal discharge/connection exists at your property, please contact me with further details or explanation by calling 602.712.8353 or by email at wterlizzi@azdot.gov.

Sincerely,


Wendy Terlizzi ADOT Office of Environmental Services Water Quality Manager 1611 W Jackson Street, MD EM02 Phoenix, Arizona 85383

Enclosure (photographs)

cc: Todd G. Williams, M.Sc, ADOT Office of Environmental Services Director District Engineer District Environmental Coordinator

## APPENDIX D Map of ADOT Licensed Materials Sources and Stockpile Sites

# Arizona Department of Transportation Licensed Material Sources and Stockpile Sites




# **Permit Year 3**

- GROUP A
- GROUP B
- GROUP C
- GROUP I

## Legend

Cities
 State Highway System
 District Boundary
 County Boundary



# APPENDIX E Material Sources Inventory (Group A, B, C, and I)

#### Appendix E ADOT- Licensed Material Source Inventory

Material Source		ADOT		Owner	Town-					Latitude	Longitude	Total	SIC	Site	Non- Exclusive	Potential Non-SW	Stockpiled	Water of	Distance to Waters	U/I
(MS) No.	Source Name	District	County	Code	ship	Range	Sec	Hwy	MP	°-'-"N	°-'-"W	Acres	Code	Use	Use	Discharge	Material	US	(miles)	Waters
GROUP A	: A materials source in the	nis group will include a	a place where	work or othe	r activities	related to	the extra	action, pr	ocessin	g, removal or	recovery of mir	nerals is b	eing condu	cted. Group	A may also i	include a site or p	ortion of site wi	here mini	ng has occurre	ed in the
past, yet cu	irrently mining is not bein	g actively undertaken	and the facility	/ may or may	/ not be co	vered by a	an active	mining	permit is	sued by the la	andowner(s), a	pplicable S	State or Fee	leral gover	nment agency	/.			-	
A1. These	sources are expected to	be used at least annu	ally. Inspection	is are conduc	cted at lea	st quarterl	у.													
1563	Pole Knoll	Globe	Apache	3	08 N	27 E	30	260	381	34-03-24.83	109-31-55.04	5	1429	20,22	No	HH,LL	Yes	Yes	0.25	No
3512	Burnt Corral	Globe	Maricopa	3	03 N	11 E	1	88	237	33-38-04.52	111-11-18.65	11	1499	20	Yes	HH	Yes	Yes	0.25	No
5154	JMP Ranches Inc.	Globe	Apache	7	13 N	28 E	30	180	366	34-30-04.52	109-24-18.65	80	1499	22	No	HH	Yes	Yes	<0.25	No
8763	Fish Creek	Globe	Maricopa	3	02 N	11 E	5	88	227	33-32-39.06	111-15-15.76	4	1429	20	Yes	HH,JJ	Yes	Yes	0.25	No
8109	BVD	Holbrook	Coconino	1,5	19 N	15 E	21	I-40	250	35-01-54.56	110-45-32.79	80	1499	20,22,23	No	HH,MM,NN	Yes	Yes	>0.50	No
7810	Crabtree	Safford	Greenlee	3	02 N	29 E	14	191	216		109-18-59.02	10	1429	20,22	Yes	HH	Yes	Yes	0.25	No
5058	Picacho	Tucson	Pinal	1	08 S	08 E	15	87	195		111-30-43.93	52	1429	20	Yes	HH,MM	Yes	Yes	On-site	No
6662	Val Vista	Tucson	Pinal	4	05 S	06 E	23	I-10	187		111-43-04.41	120	1499	22,23	Yes	HH	Yes	Yes	On-site	No
1662	Tanner	Yuma	Yuma	4	08 S	21 W	9	95	38		114-25-33.55	25	1442	20,22,24	Yes	HH,II,JJ	Yes	Yes	On-site	No
2979	Vicksburg	Yuma	La Paz	4	05 N	15 W	23	72	44		113-47-39.44	60	1499	20	Yes	HH	Yes	Yes	<0.25	No
3547	Gila Bend North	Yuma	Maricopa	4	06 S	03 W	7	I-8	124		112-35-51.77	19	1499	20,22	Yes	HH	Yes	Yes	On-site	No
5474	Castle Dome	Yuma	Yuma	9	06 S	20 W	3	95	53	32-56-15.13	114-18-32.26	14	1442	20,22	No	HH	Yes	Yes	0.25	No
	sources are used less the											L	1						-	ļ
8706	Yucca	Kingman	Mohave	1,2,4,7	18 N	17 W	30	I-40	29		114-07-02.16		1442	20,23	Yes	HH,MM	Yes		On-site	No
8569	Dugas	Prescott	Yavapai	3	12 N	03 E	27	I-17	270		112-02-26.61	40	1429	20	Yes	HH	Yes	Yes	<0.25	No
6022	Bowie	Safford	Cochise	2,4	13 S	28 E	32	I-10	365		109-30-02.93	134	1442	20,23	Yes	HH,MM	Yes	Yes	On-site	No
5643	Gila Bend South	Yuma	Maricopa	4	06 S	03 W	19	I-8	123		112-36-42.77	256	1442	20,23	Yes	HH,MM	Yes	Yes	On-site	No
8268	Tiger Wash West	Yuma	Maricopa	4	04 N	10 W	16	I-10	73	33-41-29.35	113-18-02.48	74	1442	20,23	Yes	HH	Yes	Yes	On-site	No
		17																		
GROUP B	: A material source in the	is group will include a	a site or portion	of a site who	ere mining	occurred	in the pa	ast but is	not an a	active facility.	A site that is no	o longer be	eing used w	ill remain i	n this group u	ntil it can be recla	aimed, at which	time it wo	ould be moved	to Group C.
00.40	<b>a a</b> .	<u></u>	0.1										1100	4.00					0.05	
3043	Squaw Peak	Globe	Gila	3	08 N	14 E	30	288	299		110-57-23.93	4	1499	1,20	Yes	HH	Yes		0.25	No
3044	Board Tree Saddle	Globe	Gila	3	07 N	14 E	7	288	295		110-57-11.80		1499	1,20	Yes	HH	Yes	Yes	<0.25	No
7225	Connor Canyon	Globe	Gila	3	06 N	13 E	36	288	281		110-55-30.94	9	1499	1,20	Yes	HH	Yes	Yes	< 0.25	No
8135	Warm Springs	Globe	Apache	3	07 N	30 E	5	180	411		109-11-53.27	42	1429	1,20,24	Yes	HH	Yes	Yes	On-site	No
6451	Slick Rock Wash	Safford	Graham	4	08 S	29 E	10	70	361		109-21-28.43	25	1442	20,26	Yes	N/A	Yes	Yes	On-site	No
1318	Quijotoa	Tucson	Pima	5	14 S	02 W	19	86	68		112-31-03.30	10	1499	1,26	Yes	N/A	No	Yes	<0.25	No
478	Mohawk	Yuma	Yuma	4	08 S	14 W	17	I-8	55	32-43-57.44	113-43-41.55	20	1499	26	Yes	N/A	No	Yes	On-site	No
	: Includes activities inte	/	d to ito pro min	ing state (O	non o oito	ia realaim	مط أخيبينا	he reme	word from	m this Crown)										
GROUP C	. Includes activities inte	nded to return the lan	a to its pre-min	ing state. (O	nce a sile	is reciaim	ea, it will	be remu	veu no	n mis Group)										
769	Twin Arrows	Flagstaff	Coconino	3	20 N	10 E	2	I-40	217	25 00 04 61	111-18-45.07	32	1429	21	Yes	N/A	No	Yes	<0.25	No
8318	Aztec	Holbrook	Navajo	2,7	16 N	21 E	3	77	381		110-06-18.35		1429	21	No	N/A N/A	No	Yes	<0.25	No
8223	Upper Sheep Wash	Safford	Greenlee	3	02 S	28 E	2	191	190		109-26-54.60		Not 14XX	1	Yes	N/A	No		On-site	No
		3	Oreeniee	0	02.0	20 L	~	101	100	00 11 00.01	100 20 04.00				100	14/7	110	100	Oll bite	
	Non-Mining Sites. These	e regulated stockpile s	sites will be ins	nected at lea	ast quarter	lv														
	encor mining encor moo	o rogulatoù otoonplio t			lot quarton	. <b>y</b> .														
3562	Beaver Creek	Flagstaff	Yavapai	3	15 N	05 E	12	179	302	34-42-35.03	111-46-45.18	2	Not 14XX	1,19,20	Yes	HH.MM	Yes	Yes	<0.25	No
5781	Blue Grade	Flagstaff	Yavapai	3	16 N	06 E	35	I-17	302		111-40-58.62	17	Not 14XX	20,22	Yes	HH,LL,MM	Yes	Yes	0.25	No
7625	Fort Tuthill	Flagstaff	Coconino	1,3	21 N	07 E	31	89A	400		111-41-31.75		Not 14XX	20,22	No	HH.LL.MM	Yes	Yes	On-site	No
1061	Second Knoll	Globe	Navajo	3	10 N	23 E	18	60	347		109-56-19.91	16	Not 14XX	20,22	Yes	HH,LL	Yes	Yes	0.25	No
1546	Kinney Mountain	Globe	Navajo	5	08 N	23 E	24	260	360	34-04-53.85		22	Not 14XX	1,20	Yes	HH,LL,MM	Yes	Yes	<0.25	No
3591	Carol Spring Mountain	Globe	Gila	3	04 N	17 E	33	60	278		110-34-06.08	6	Not 14XX	20,22	No	HH,LL,MM	Yes	Yes	<0.25	No
7525	Defiance	Globe	Pinal	3	2 S	12 E	11	177	167		111-05-38.06	7	Not 14XX	20	Yes	HH,MM	Yes	Yes	< 0.25	No
8629	Seven Mile Wash	Globe	Gila	3	03 N	16 E	23	60	268		110-38-47.23	1	Not 14XX	1,20	Yes	HH,MM	Yes	Yes	On-site	No
1245	Sunset Pass	Holbrook	Coconino	2,7	17 N	13 E	13	87	327		110-54-29.34	10	Not 14XX	20,22	No	HH,LL,MM	Yes	Yes	On-site	No
7021	Gordon Drive	Kingman	Mohave	1	22 N	16 W	33	66	59		113-59-04.02	15	Not 14XX	20	No	HH,MM	Yes	No	N/A	No
8400	Sunflower	Phoenix	Maricopa	3	06 N	09 E	19	87	217		111-28-30.29	2	Not 14XX	20	Yes	HH	Yes	Yes	<0.25	No
999	Tubac	Tucson	Santa Cruz	1	20 S	13 E	31	I-19	24		111-03-19.16	14	Not 14XX	20,22	No	HH,MM	Yes	Yes	On-site	No
7885	Sahuarita	Tucson	Pima	1	17 S	13 E	27	I-19	44		111-00-01.88		Not 14XX	20,22	No	HH,MM	Yes	Yes	<0.25	No
5002	Fortuna/Blaisedell	Yuma	Yuma	1	08 S	21 W	33	95	33		114-25-19.78	40	Not 14XX	20,26	No	HH,MM	Yes	Yes	On-site	No
6183	Dateland	Yuma	Yuma	2	06 S	13 W	36	I-8	67		113-33-07.68	60	Not 14XX	20,22	Yes	HH,MM	Yes	Yes	On-site	No
7287	Centennial	Yuma	La Paz	1	03 N	11 W	27	I-10	68		113-22-48.65	40	Not 14XX	20	No	HH,MM	Yes	Yes	On-site	No
		16									2 == 10100								1	
<u> </u>																				

#### Appendix E ADOT - Licensed Material Source Inventory (continued)

Definitions:	may also include a site or porti		work or other activities related to the extraction, processing, removal or recovery of minerals is being conducted. Group A I in the past, yet currently mining is not being actively undertaken and the facility may or may not be covered by an active I government agency.							
		this group will include a site or portion of a site a site or portion of a site a site which time it would be moved to Group C.	portion of a site where mining occurred in the past but is not an active facility. A site that is no longer being used will remain in this d to Group C.							
	Group C : Includes activities in	ntended to return the land to its pre-mining state.	(Once a site is reclaimed, it will be rer	moved from this Group).						
	Group I: Non-mining sites.T	hese regulated stockpile sites will be inspected a	t least quarterly.							
	Waters of the US:	Based on review of topographic maps	and/or on-site review							
	Latitude/Longitude:	Latitude/Longitude are expressed in N	AD 83							
	N/A:	Not Applicable								
Site Use Codes:			Ownership Codes:							
1	Expired permit or license		1	ADOT						
2	Never used - will not be insp	ected until pit is developed	2	Arizona State Land Departm	lent					
18	Undergoing reclamation		3	USDA Forest Service						
19	Requires revegetation or con	ntouring	4 5	Bureau of Land Managemen	it					
20 21	Stockpiles present	warkmanagar	5	Tribal Private						
21	Released from site by land o Maintenance only	wner/manager	9	Department of the Army						
22	Construction only		5	Department of the Army						
23	Multiple permitees		Non-Stormwater Dis	scharge Codes:						
25	To be sold		HH	Water for dust control (not w	vastewater)					
26	Requires further evaluation		II	Uncontaminated groundwate	,					
Standard Industrial	Classification (SIC) Codes:		JJ	Diverted stream flow						
1429	Crushed and broken stone (	basalt and volcanic rock)	КК	Coring and drilling water - w	vithout additives					
1442	Sand and gravel		LL	Deicing chemicals or produce	cts					
1499	Borrow or fill dirt		MM	Petroleum-containing mater						
Not 14XX	Non-mining sites; material s	torage area only	NN	Fertilizers - herbicide applica	ation to invasives					
ADOT Districts:	Address:		District Engineers:	Phone:	E - Mail:					
Flagstaff District	1801 S. Milton Ro	ad, Flagstaff, AZ 86001	John Harper	928-774-1491	jharper@azdot.gov					
Globe District		obe, AZ 85502-2717	Roderick Lane	928-402-5600	rlane@azdot.gov					
Holbrook District		vd., Holbrook, AZ 86025	Lynn Johnson	928-524-5408	ljohnson@azdot.gov					
Kingman District		ine, Kingman, AZ 86401	Mike Kondelis	928-681-6010	mkondelis@azdot.gov					
Phoenix Construction	on 4550 N. Black Car	iyon Hwy., Phoenix, AZ 85017	Robert Samour	602-712-8965	rsamour@azdot.gov					
Phoenix Maintenand	e 2140 W. Hilton Av	e., Phoenix, AZ 85009-3740	Tim Wolfe	602-712-6550	twolfe@azdot.gov					
Prescott District	1109 Commerce E	Drive, Prescott, AZ 86305	Greg Gentsch	928-777-5862	ggentsch@azdot.gov					
Safford District		, Safford, AZ 85546	Bill Harmon	928-428-5470	bharmon@azdot.gov					
Tucson District	1221 South 2 <sup>nd</sup> Av	e., Tucson, AZ 85713-1602	Todd Emery	520-388-4210	temery@azdot.gov					
		lge Road, Yuma, AZ 85365-2101	Alvin Stump	928-317-2156	astump@azdot.gov					

# **APPENDIX F Numeric Summary of BMPs**

			Annual Reporti	ng Year (Ju	ly1 - June 3	0)
Section	Stormwater BMP or Activity	2008-	2009-	2010-	2011-	2012-
Number		2009	2010	2010-     201       2011     201       13     33       NA     -       13     -       33     NA       13     -       33     -       13     -       33     -       13     -       33     -       13     -       33     -       13     -       36     -	2012	2013
	MEASURES TO CONTROL DISCHARGES THR	OUGH EDU	CATION			
3.2.2.1(a)(ii)(1)	Train ADOT Employees - Illicit discharges and illegal dumping					
	Number of trainings offered	7	17	13		
	Number of employees trained	35	112	33		
	(Other numeric measurable goals(s))	NA	NA	NA		
3.2.2.1(a)(ii)(2)	Train ADOT Employees - Non-stormwater discharges					
	Number of trainings offered	7	17	13		
	Number of employees trained	35	112	33		
	(Other numeric measurable goals(s))	NA	NA	NA		
3.2.2.1(a)(ii)(3)	Train ADOT Employees - New Construction and land disturbances					
	Number of trainings offered	7	17	13		
	Number of employees trained	35	112	33		
	(Other numeric measurable goals(s))	NA	NA	NA		
	Train ADOT Employees - New development and significant					
3.2.2.1(a)(ii)(4)	redevelopment					
	Number of trainings offered	7	17	13		
	Number of employees trained	35	112	33		
	(Other numeric measurable goals(s))	NA	NA	NA		
	Train ADOT Employees - Storm sewer system and highway					
3.2.2.1(a)(ii)(5)	maintenance					
	Number of trainings offered	7	17	13		
	Number of employees trained	35	112	33		
	(Other numeric measurable goals(s))	NA	NA	NA		
3.2.2.1(a)(ii)(6)	Train ADOT Employees - Good housekeeping and material BMPs					
	Spill Prevention and Response - Number of trainings offered	7	17	1		
	Spill Prevention and Response - Number of employees trained	35	112	36		
	Pesticides, Herbicides, and Fertilizer Application - Number of trainings					
	offered	7	17	1		
	Pesticides, Herbicides, and Fertilizer Application - Number of employees					
	trained	35	112	36		
	Industrial Sites - Number of trainings offered	7	17	1		
	Industrial Sites - Number of employees trained	35	112	36		
	(Other numeric measurable goals(s))	NA	NA	NA		

		Annual Reporting Year (July1 - June 30)								
Section	Stormwater BMP or Activity	2008-	2009-	2010-	2011-	2012-				
Number		2009	2010	2011	2012	2013				
3.2.2.1(a)(iii)	Develop Stormwater Library									
	Number of times accessed or visited	NA	NA	NA						
	(Other numeric measurable goals(s))	NA	NA	NA						
3.2.2.1(b)	ADOT Construction Contractor Training and Certification									
	Number of trainings offered	7	6	8						
	Number of ADOT employees trained/certified	35	22	34						
	Number of ADOT employees recertified	5	28	5						
	Number of ADOT contractors trained	NA	129	53						
3.2.2.2(b)(i)	Distribution of Educational Materials Through Public Places		•							
	Number of materials (posters, brochures, signs, etc.) distributed	2600	4,577	5200						
	Number of public events ADOT attended with displays	5	65	119						
	Est'd Audience from tv, movie, radio, billboard, bus shelter PSAs	NA	13,534,800	4,268,300						
	Educational items (coloring books, wrist bands, magnets, etc). distributed	NA	6,129	8,000						
	Construction seminar provided	NA	NA	80						
	(Other numeric measurable goals(s))	NA	NA	NA						
	Distribution of Educational Materials Through ADOT's Stormwater		•							
3.2.2.2(b)(ii)	Webpage									
	Number of hits on webpage	NA	NA	NA						
	(Other numeric measurable goals(s))	NA	NA	NA						
3.2.2.3 (b)	Record and Consider Public Comments		•							
	Number of public comments received	0	0	0						
	(Other numeric measurable goals(s))	NA	NA	NA						
3.2.2.3(c)	Implement a Public Reporting System									
	Number of reports received from public	0	0	0						
	Number of reports investigated	0	0	0						
	(Other numeric measurable goals(s))	NA	NA	NA						
3.2.2.3(d)	Develop a Stormwater Component of the Adopt-a-Highway Litter Initiative									
	Number of volunteer groups participating	1,835	1,609	1,569						
	Number of miles cleaned	2,291	2,026	3935.4						
	Amount of trash collected (tons)	2,291	211	224						
	(Other numeric measurable goals(s))	NA	NA	NA						
3.2.2.3(e)	Continue Implementation of Litter Hotline	11/7	11/7							
0.2.2.0(0)	Number of calls received	3,389	2864	2776						
	(Other numeric measurable goals(s))	0,000 NA	NA	NA						


Section Number	Stormwater BMP or Activity	Annual Reporting Year (July1 - June 30)					
		2008-	2009-	2010-	2011-	2012-	
		2009	2010	2011	2012	2013	
	ILLICIT DISCHARGE/ILLEGAL DUMPING DETECTION A	ND ELIMINA	ATION MEASUR	RES			
3.2.3.1(a)	Maintain Illicit Discharge Authority						
	(Numeric Measurable goal(s))	0	0	0			
3.2.3.1(b)	Enforce Standard Encroachment Permit						
	Number of enforcement actions	0	0	0			
	(Other numeric measurable goal(s))	0	0	0			
3.2.3.1(c)	Implement Non-Stormwater BMPs						
	(Numeric Measurable goal(s))	NA	NA	NA			
3.2.3.1(d)	Inspect Outfalls for Dry Weather Discharges						
	Number of major outfalls inspected	35	35	0			
	Number of 71 identified major outfalls inspected	35	35	0			
	Number of priority outfalls inspected		0	0			
	Number of storm drain cross connection detected	0	0	0			
	Number of illicit discharges detected	1	1	0			
	Number of other dry weather flows detected	0	0	0			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.3.3(b)	Investigate Illicit Discharges (Source Identification)						
	Number of storm drain cross connection investigated	0	0	0			
	Number of illicit discharges investigated	0	0	7			
	Number of other dry weather flows investigated		0	0			
	(Other numeric measurable goal(s))	NA	NA	0			

Section	Stormwater BMP or Activity	Annual Reporting Year (July1 - June 30)					
		2008-	2009-	2010-	2011-	2012-	
Number		2009	2010	2011	2012	2013	
3.2.3.3(c)	Respond to Complaints						
	Number of complaints received	0	0	0			
	Number of complaints responded to	0	0	0			
	Average response time (in days)	0	0	0			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.3.3(d)	Report Incidental Dry Weather Discharges						
	Number of discharges reported to ADEQ	1	1	0			
	(Other numeric measurable goal(s))	NA	NA	0			
3.2.3.4(a)	Take Action to Eliminate Existing Dry Weather Flows						
	Number of existing dry weather discharges eliminated	0	0	0			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.3.4(b)	Take Action to Eliminate Sources of Illicit Discharges						
	Number of storm drain cross connection eliminated	0	0	0			
	Number of illicit discharges eliminated	1	1	7			
	Number of dry weather discharges eliminated	1	1	0			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.3.4(c)	Coordinate with Local Jurisdictions for Complaint Response and Investigation						
	Number of illicit discharges reported to other jurisdictions for follow-up	1	0	0			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.3.5	Responding to Spills		-	-	-	-	
	Number of highway accident spills responded to	0	156	180			
	Number of highway accident spills prioritized (potential for discharge)	0	156	10			
	Hazardous material released	NA	NA	50			

	Stormwater BMP or Activity	Annual Reporting Year (July1 - June 30)					
Section Number		2008- 2009	2009- 2010	2010- 2011	2011- 2012	2012- 2013	
3.2.5.2	Install Post-Construction Stormwater Control BMPs						
	Number of new post-construction stormwater control BMPs installed		0	0			
	(Other numeric measurable goal(s))		NA	NA			
	MEASURES TO CONTROL DISCHARGES F	ROM ROAD	WAYS				
3.2.6.1(b)	Inspect Storm Sewer System					-	
	Number of inspections performed		54	54			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.6.1(c)	Develop Maintenance Schedules and Priorities				-		
	(Numeric measurable goal(s))	NA	NA	NA			
3.2.6.1(d)	Perform Repair, Maintenance, and Cleaning				-		
	Number of miles of roadways repaired/maintained		0*	0*			
	Number of inlets cleaned		0*	0*			
	Number of drain inlets containing significant materials		0*	0*			
	(Other numeric measurable goal(s))	NA	NA	NA			
3.2.6.2(c)(ii)	Require Certification/License		1		•		
	Number of licensed ADOT applicators	41	41	40			
3.2.6.2(d)	Stabilize Roadway Slopes (attach summary of tracking & prioritization)						
	Acres of roadway slopes stabilized	0	0	0			
* In accordanc	e with 3.2.6.1(b), ADOT has 24 months to implement a system to inspect and r	ecord condi	tions of its storn	n sewer syst	em		
	MEASURES TO CONTROL DISCHARGES FROM ADOT						
4.1.5.3	Stencil Drain Inlets at ADOT Facilities						
	Number of new catch basins installed	0	0	0			
	Number of catch basins marked or stenciled	15	0	0			
	(Other numeric measurable goal(s))	NA	NA	NA			

APPENDIX G Approved MS4 Monitoring Locations





a

An

02

V:\308032




Stormwater Sample Location



Ν








Photograph: Outlet from Roadway looking North




**Figure 1** Approved MS4 Sampling Location Flagstaff, Arizona

ARIZONA DEPARTMENT OF TRANSPORTATION AZPDES STORM WATER MONITORING SITE









Photograph: Outlet looking Northeast




**Figure 2** Approved MS4 Sampling Location Nogales, Arizona

ARIZONA DEPARTMENT OF TRANSPORTATION AZPDES STORM WATER MONITORING SITE





Ν







ADOT


Engineering and Environmental Consultants, Inc. 7878 North 16<sup>th</sup> Street, Suite 140, Phoenix, AZ 85020

## Legend

• Stormwater Sample Location

# **Figure 3** Approved MS4 Sampling Location Phoenix, Arizona

ARIZONA DEPARTMENT OF TRANSPORTATION AZPDES STORM WATER MONITORING SITE





Yard







Maps\Figure 5\_ Ы ğ ing Sar ntial MS4 \$ Annual Report/Pote 2009 / ables\710 Deliv 2009\700 pling. Sar ual Report\_ .05 Anr /:\308032

Prop

S

Tuc

Photograph: Outfall from Roadway looking East



**Figure 5** Approved MS4 Sampling Location Tucson, Arizona

ARIZONA DEPARTMENT OF TRANSPORTATION AZPDES STORM WATER MONITORING SITE

APPENDIX H ISCO Stormwater Sampling Equipment

## Isco 6712 Full-size Portable Sampler

Isco's 6700 Series Portable Samplers have set the industry standard, providing the most comprehensive and durable performance available. With the introduction of our new 6712, Isco takes another step toward the ultimate by including SDI-12 interface capabilities.

The 6712 uses Isco's advanced 6700 Series Controller, a device that allows you to select from a variety of programming modes, assuring the most suitable routine for your application. Programming is fast and simple, with on-line help just a key stroke away.

The environmentally-sealed 6712 controller delivers maximum accuracy and easily handles all of your sampling applications, including:

- wastewater effluent
- stormwater monitoring
- CSO monitoring
- > permit compliance
- > pretreatment compliance

In the Standard Programming Mode, the controller walks you through the sampling sequence step-by-step, allowing you to choose all parameters specific to your application. Selecting the Extended Programming Mode lets you enter more detailed programs.

An optional telephone modem allows programming changes and data collection to be performed remotely, from a touchtone phone. It also has dial-out alarm features.

Bottle options are available for practically any sequential or composite application.



## Versatile and Convenient

With eleven bottle choices, Isco's 6712 Sampler lets you quickly adapt for simple or intricate sampling routines. Up to 30 pounds (13.5 kg) of ice fits in the insulated base, preserving samples for extended periods, even in extreme conditions. A convenient drain plug aids removal of water from melted ice.

## Tough and Reliable

The 6712 Portable Sampler features a vacuum-formed ABS plastic shell to withstand exposure and abuse. Its tapered design and trim 20-inch (50.8 cm) diameter result in easy manhole installation and removal. Large, comfortable handles make transporting safe and convenient—even when wearing gloves.

Isco's 6712 Portable Sampler carries a NEMA 4X, 6 (IP67) enclosure rating. It's submersible, watertight, dust-tight, and resistant to sleet and corrosion.

Superior capability, rugged construction, and unmatched reliability make the 6712 the ideal choice for portable sampling in just about any application.

## All 6712 Samplers share the following features:

## Advanced Delivery System

The 6712's peristaltic pump delivers samples at the EPA-recommended velocity of 2 ft/sec., even at head heights of 26 feet. At a head height of 3 feet, line velocity is 3 ft/sec. No other automatic sampler achieves this level of performance!

Our patented\* pump revolution counter tells you when tubing should be replaced. Changing tubing is a snap; there are no pump covers, collars or tools to slow you down. An exclusive safety interlock removes power from the pump when it's opened.

## Step-by-Step Programming

This feature walks you through the sampling sequence and allows you to choose all parameters specific to your application:

- ► When to start
- What volume to collect
- ► How to distribute samples
- ► If samples are to be time- or flow-paced.

You can easily enter complex programs to suit your unique needs. Available routines include:

- Pause and resume for intermittent discharge flow monitoring
- Sampler pacing by time, non-uniform time, flow or external event
- Random interval sample collection

## Convenient Data Retrieval

Every 6712 Sampler is also a powerful data logger. Sampling, flow, rainfall, and other water quality data can be stored in its 512 KB memory.

Data may be retrieved directly into a Flowlink<sup>®</sup> 4 equipped PC in three ways:

- ► Via cable connection
- Remotely, via Isco's 2102 Wireless Communication System
- By phone, using our optional built-in modem

## SDI-12 Interfacing

The 6712 functions as a SDI-12 logger and connects to any sensor that fully implements the protocol standard.



Display window showing SDI-12 connection status.

In addition, Isco has defined extended commands to enable "plug and play" communications and ease of programming. These commands are implemented by the sensor manufacturer. Data are identified and logged by their specific type.

## Expand your monitoring capabilities with these products and accessories.

Contact Isco or your Isco Representative to receive specific literature and prices on the following items.

## **Telephone Modem**

A factory-installed option that lets you set up and make programming changes, or collect data from your 6712 sampler from the comfort of your office.

## 581 RTD (Rapid Transfer Device)

Slim enough to fit in your shirt pocket, yet rugged enough to withstand submersion, the 581 RTD lets you quickly retrieve and transfer data without taking your laptop computer into the field.



## ProPak<sup>TM</sup> Disposable Sample Bags

Isco's patented ProPak bags eliminate the expense of washing and storing bottles, while taking away worries about contamination from previous samples. The bags are available with a 1000 ml capacity, or in a 2-gallon version for composite sampling.

## Flowlink Software

Isco's advanced Flowlink<sup>®</sup> 4 for Windows Data Management Software harnesses the power of Microsoft Windows<sup>®</sup> to retrieve, import, compare, and analyze data, generate advanced charts and graphs, create comprehensive reports, and more.

## 700 Series Modules

Our interchangeable 700 Series Modules let you adapt your 6712 sampler for a variety of jobs. These compact modules are environmentally sealed and may be added to your 6712 system at any time.



#### 701 - pH and Temperature Module

Combines accurate pH and temperature monitoring in one module. It will also activate your 6712 Sampler at a user-elected pH or temperature range.

#### 710 - Ultrasonic Flow Module

Uses our field-proven ultrasonic level sensor that doesn't require submersion in the flow stream.

#### 720 - Submerged Probe Flow Module

Provides accurate measurement at sites where wind, steam, foam, turbulence, or air temperature fluctuations exist. Suitable for small channels, it accurately senses pressure even when covered with silt and sand.

#### 730 – Bubbler Flow Module

Get the dependability and accuracy of Isco bubbler flow meters in a miniaturized package. The 730 is unaffected by changing stream conditions, and level measurement remains accurate despite temperature fluctuations or exposure to harsh chemicals.

#### 750 - Area Velocity Flow Module


Gives greater accuracy where weirs and flumes are not practical, and where submerged, full pipe, surcharged, and reverse flow conditions may occur. And, you don't have to estimate the slope and roughness of the channel.

#### 780 - Smart 4-20 Module

Add intelligence to a simple analog signal. Flow rates are displayed in actual volume units, not merely a percent of full scale. Any linear 4-20 mA input can be characterized by using the 780. The information can be stored and retrieved for later analysis.

## **Integrated Water Monitoring**

Isco 6712 Samplers feature "plug and play" connection with SDI-12 compatible measuring devices - including multi-parameter sondes from leading manufacturers. Combined with the 6712's standard 512 KB of memory, enough for more than 200,000 stored readings. SDI-12 networking gives you great flexibility for logging environmental data, and for "smart sampling" event notification, triggered on any combination of up to 16 inputs.



## Isco 6712 Full-size Portable Sampler Specifications

Sampler			Controller					
Height	27.0 in.	68.6 cm	Weight	13 lbs.	5.9 kg			
Diameter	20 in.	50.7 cm	Dimensions	10.3 x 12.5 x 10 in.	26 x 31.7 x 25.4 cm			
Weight (Dry/Less Battery)	32 lbs.	15 kg	Operational Temperature	32° to 120°F	0° to 49°C			
Material	High-strength ABS plast Stainless steel hardware		Enclosure Rating	NEMA 4X, 6	IP67			
Power Requirements	12 VDC	,	Program Memory	Non-volatile flash mem	<b>,</b>			
Pump	12 000		Flow Meter Signal Requirements	5 to 15 volt DC pulse or contact closure.	25 millisecond isolated			
Intake Purge	Adjustable air purge bef each sample.	ore and after	Number of Programmable Composite Samples	1 to 999 samples or co				
Tubing Life Indicator	Provides a warning to c	hange pump tubing.	- Real Time Clock Accuracy	1 minute per month, ty	pical			
Intake Suction Tubing			Software	1				
Length	3 to 99 ft.	1 to 30 m		1 minute to 99 hours 59 minutes, in 1 minute increments. Non-uniform times in minutes or				
Material	Vinyl or Teflon <sup>®</sup> lined		Sample Frequency					
Inside Dimension	3⁄8 in.	1 cm	Selection	clock times 1 to 9,999 f				
Pump Tubing Life	Typically 1,000,000 pun	np counts	- Sampling Modes	Uniform time, non-uniform time, flow.				
Maximum Suction Lift	28 ft.	8.5 m		(Flow mode is controlled by external flow				
Typical Repeatability	±5 ml or ±5% of the ave	rage volume in a set	-	meter pulses.)				
Typical Line Transport Velocity			Programmable Sample Volumes	10 to 9,990 ml in 1 ml i	ncrements			
at head heights of: 3 ft. (0.9 m)	3.0 ft./s	0.91 m/s	Sample Retries	If no sample is detected user selectable	I, up to 3 attempts;			
10 ft. (3.1 m)	2.9 ft./s	0.87 m/s	Rinse Cycles		ction line up to 3 rinses			
15 ft. (4.6 m)	2.7 ft./s	0.83 m/s	- 	for each sample collect	ion			
Liquid Presence Detector	Non-wetted, non-condu	ctive sensor detects	Program Storage	5 sampling programs				
· · · · · · · · · · · · · · · · · · ·	when liquid sample reaches the pump to automatically compensate for changes in		Sampling Stop/Resume	Up to 24 real time/date sample stop/resume commands				
	head heights.	č	Controller Diagnostics	Tests for RAM, ROM, pump display, and distributor				

## **Ordering Information**


Description	Part Number
<b>6712 Portable Sampler, Full-size</b> Includes controller with 512 KB RAM, top cover, center section, base, distributor arm, instruction manual, pocket guide.	68-6710-070
6712 Portable Sampler with Jumbo Base (as described above)	68-6710-082

Note: Power source, bottle configuration, suction line, and strainer must be ordered separately. Other options and accessories are also available. Contact Isco or your Isco Representative for complete information.



#### Isco, Inc.

4700 Superior St. Lincoln, NE 68504 USA Phone: (402) 464-0231 USA & Canada: (800) 228-4373 Fax: (402) 465-3022 E-Mail: info@isco.com





*The 6712 Controller is an SDI-12 logger. Manual pump operations are now located on the front panel keys.* 

## Isco Avalanche® Multi-bottle, Refrigerated Portable Sampler

## Multi-function sampling and data logging with dual-power cooling

Avalanche<sup>®</sup> is based on Isco's industry-leading 6712 controller. You get all the advanced control, data logging, and communication features of the 6712, with cooling from either AC or battery power.

Bottle options include 5- and 2.5 gallon composites as well as  $4 \times 1$ -gallon and  $14 \times 950$  ml sequentials.

A 12V deep-cycle battery delivers 48 hours or more- of refrigeration. The power-saving cooling system remains on standby until the first sample is drawn, and only then switches on to preserve the collected samples for pickup.

Available routines include: pause-and-resume for intermittent-discharge flow monitoring; sampler pacing by time, non-uniform time, flow or external event; and random interval sample collection.

## Standard Features


- Standard and extended programming keeps setup simple when you don't need advanced features.
- NEMA 4x, 6 (IP67) controller enclosure.
- SDI-12 interface provides "plug and play" connection with multi-parameter waterquality sondes and other compatible devices.
- 512kB memory gives you great flexibility for logging environmental data.
- Sample delivery at the EPA-recommended velocity of 2 ft/sec. at head heights up to 26 feet.
- Patented pump revolution counter ensures accurate sample volumes - and tells you when tubing should be replaced.



Optional mobility kit includes pneumatic tires for ease of transport over rough terrain, and a convenient battery platform.

## **Applications**

- Stormwater runoff compliance
- TMDL and watershed monitoring
- Enforcement monitoring
- Advanced sampling combined with data logging and communications for flow, rainfall, and water quality parameters.



Is control technology accurately preserves samples at  $3^{\circ}C$  – even under difficult conditions shown above ( $40^{\circ}C$  ambient,  $20^{\circ}C$  sample temperature).

## Specifications

Isco Avalanche	e Sampler
Size (H x W x D):	30.5 x 14 x 24 inches (78 x 36 x 60 cm)
Weight:	Dry, less battery - 76 lbs (35 kg)
Bottle configurations:	5-gallon poly bottle
	2.5-gallon glass bottle configuration
	2.5-gallon poly bottle configuration
	1-gallon poly bottle configuration (4 bottles
	950 ml poly bottle configuration (14 bottles)
Power Requirements:	12V DC (Supplied by battery or AC power converter.)
Pump	
Intake suction tubing:	
Length	3 to 99 feet (1 to 30 m)
Material	Vinyl or Teflon
Inside dimension	3/8 inch (1 cm)
Pump tubing life:	Typically 1,000,000 pump counts
Maximum lift:	28 feet (8.5 m)
Typical Repeatability	$\pm 5$ ml or $\pm 5\%$ of the average volume in a set
Typical line velocity at Head height: of	
3 ft. (0.9 m)	3.0 ft./s (0.91 m/s)
10 ft. (3.1 m)	2.9 ft./s (0.87 m/s)
15 ft. (4.6 m)	2.7 ft./s (0.83 m/s)
Liquid presence detector:	Non-wetted, non-conductive sensor detects when liquid sample reaches the pump to automatically compensate for changes in head heights.

Controller	
Weight:	13 lbs. (5.9 kg)
Size (HxWxD)	10.3 x 12.5 x 10 inches (26 x 31.7 x 25.4 cm)
Operational temperature:	32° to 120°F (0° to 49°C)
Enclosure rating:	NEMA 4X, 6 (IP67)
Program memory:	Non-volatile ROM
Flow meter signal input:	5 to 15 volt DC pulse or 25 millisecond isolated contact closure.
No. of composite samples:	Programmable from 1 to 999 samples.
Clock Accuracy:	1 minute per month, typical, for real time clock
Software	
Sample frequency:	1 minute to 99 hours 59 minutes, in 1 minute increments. Non-uniform times in minutes or clock times 1 to 9,999 flow pulses
Sampling modes:	Uniform time, non-uniform time, flow, event. (Flow mode is controlled by external flow meter pulses.)
Programmable sample volumes:	10 to 9,990 ml in 1 ml increments
Sample retries:	If no sample is detected, up to 3 attempts; user selectable
Rinse cycles:	Automatic rinsing of suction line up to 3 rinses for each sample collection
Program storage:	5 sampling programs
Sampling Stop/Resume:	Up to 24 real time/date sample stop/resume commands
Controller diagnostics:	Tests for RAM, ROM, pump, display, and distributor

## **Ordering Information**


**Note:** Bottle configuration, suction line, and strainer must be ordered separately. 12 VDC operation requires external battery. Contact Isco or your Isco Representative for complete information.

Description	Part Number
Isco Avalanche Sampler (115-230 VAC/12V DC) Includes controller, distributor arm, instruction manual, pocket guide. Standard power cord.*	68-2970-003
5-gallon poly bottle	68-2970-008
2.5-gallon glass bottle configuration	68-2970-006
2.5-gallon poly bottle configuration	68-2970-009
1-gallon poly bottle configuration (4 bottles	68-2970-002
950 ml poly bottle configuration (14 bottles)	68-2970-001
Mobility Kit	68-2960-004



#### **Teledyne Isco, Inc.**

4700 Superior Street Lincoln NE 68504 USA Phone: (402) 464-0231 USA and Canada: (800) 228-4373 Fax: (402) 465-3022 E-Mail: iscoinfo@teledyne.com Internet: www.isco.com



The Avalanche controller is a powerful SDI-12 data logger, designed to work directly with Isco's advanced Flowlink® Software.

Data for flow, rainfall, and water quality can be transferred from the Avalanche controller into a Flowlink-equipped PC in three ways: via cable connection, via Isco's 2102 Wireless Communication System, or by phone, using Avalanche's optional built-in modem

Flowlink Software lets you quickly retrieve, import, compare, and analyze data, generate charts and graphs, and create comprehensive reports.

## APPENDIX I Summary of MS4 Monitoring Data

OUTFALL ID: 202-2.36				МС	NITORING	SEASO	NS			
RECEIVING WATER: Retention Basin		Summer: June 1- October 31								
				Wint	er: Novem	ber 1- Ma	v 31			
DESIGNATED USES: Water Retention		Winter	Summer	Winter	Summer	Winter	Summer	Winter	0	
SAM	PLING DATE	2008-09	2009	2009-10	2010	2010-11	2011	2011-12	Summer 2012	
MONITORING PARAMETERS	WQS	12/17/08	7/21/09	2/28/10	NS	NS		I		
Flow	NNS	1.7gpm	1.4gpm	L .	NS	NS		1		
PH	5.0-9.0	7.75	7.21	8.52	NS	NS				
Temperature (F°)	0.0-9.0 NNS	54.4	96.9	56.5	NS	NS				
Hardness	NNS	180	-	60	NS	NS				
Specific conductance (mg/L)	NNS	550	900	1500	NS	NS				
Total Dissolved Solids (TDS) (mg/L)	500.00	290	720*	97	NS	NS				
Total Suspended Solids (TSS) (mg/L)	NNS	85	-	76	NS	NS				
Turbidity (NTU)	NNS	49	21	100	NS	NS				
Biochemical Oxygen Demand (BOD) (mg/L)	NNS	13	40	<5.0	NS	NS				
Chemical Oxygen Demand (COD) (mg/L)	NNS	110	350	70	NS	NS				
Inorganics										
Cyanide (mg/L)	0.20	<0.0050	<0.0050	<0.0050	NS	NS				
Sulfates (mg/L)	250.00	56	69	7.6	NS	NS				
Nutrients										
Nitrate (mg/L)	10.00	3.3	4	1.1	NS	NS				
Nitrite (mg/L)	1.00	0.19	0.77	<0.10	NS	NS				
Total Kjeldahl Nitrogen (TKN) (mg/L)	NNS	3	12	1.5	NS	NS				
Total Phosphorous (mg/L)	NNS	-	1.1	0.25	NS	NS				
Phosphate, Ortho (mg/L)	NNS	<0.12	0.46	0.48	NS	NS				
Total Nitrogen (mg/L)	NNS	-	-	1.2	NS	NS				
Total Amonia (mg/L)	NNS	0.66	2.6	0.48	NS	NS				
Sodium (mg/L)	NNS	49	85	1.3	NS	NS				
Calcium (mg/L)	NNS	46	64	150	NS	NS				
Chloride (mg/L)	NNS	69	130	6.9	NS	NS				

OUTFALL ID: 202-2.36		MONITORING SEASONS								
RECEIVING WATER: Retention Basin		Summer: June 1- October 31								
		Winter: November 1- May 31								
DESIGNATED USES: Water Retention		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012	
SAM	PLING DATE	12/17/08	7/21/09	2/28/10	NS	NS				
Microbiological										
Coliform, fecal (col/100 ml)	NNS	>1,200	-	>200	NS	NS				
E.Coli (cfu/100 ml)	100.00	>24,200	-	-	NS	NS				
Total Metals										
Antimony (mg/L)	0.006	<0.020	0.0037	<0.020	NS	NS				
Arsenic (mg/L)	0.050	<0.021	0.0064	<0.020	NS	NS				
Barium (mg/L)	2.000	0.098	0.14	0.074	NS	NS				
Beryllium (mg/L)	0.004	<0.0020	<0.0020	<0.0020	NS	NS				
Cadmium (mg/L)	0.005	<0.0050	<0.0050	<0.0050	NS	NS				
Chromium (mg/L)	0.100	<0.010	<0.010	<0.010	NS	NS				
Copper (mg/L)	1.300	0.023	0.073	<0.020	NS	NS				
Lead (mg/L)	0.015	0.0084	0.006	0.0064	NS	NS				
Mercury (mg/L)	0.002	<0.00020	<0.00020	<0.0002	NS	NS				
Nickel (mg/L)	0.140	<0.020	<0.020	<0.020	NS	NS				
Selenium (mg/L)	0.020	<0.020	<0.020	<0.020	NS	NS				
Silver (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
Zinc (mg/L)	2.10	0.053	0.14	4.7	NS	NS				
Organic Toxic Pollutants										
Total Petroleum Hydrocarbons (TPH) (mg/L)	NNS	0.73	2.7	0.32	NS	NS				
Oil & Greese (Hexane Extr) (mg/L)	NNS	<5.0	<5.9	<5.3	NS	NS				
Chlorine, residual (mg/L)	0.70000	0.2	<0.10	<0.10	NS	NS				

OUTFALL ID: 202-2.36		MONITORING SEASONS								
RECEIVING WATER: Retention Basin		Summer: June 1- October 31								
		Winter: November 1- May 31								
DESIGNATED USES: Water Retention			Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012	
	SAMPLING DATE	12/17/08	7/21/09	2/28/10	NS	NS				
VOCs, Semi-VOCs and Pesticides										
Benzene (mg/L)	0.0050	<0.00050	<0.00050	<0.0010	NS	NS				
Ethylbenzene (mg/L)	0.0050	0.00068	<0.00050	<0.0010	NS	NS				
Toluene (mg/L)	1.00	<0.0050	<0.0050	<0.0050	NS	NS				
Total Xylene (mg/L)	10.00	0.0039	<0.0015	<0.0030	NS	NS				
Chromium, Trivalent (mg/L)	NNS	<0.010	<0.010	-	NS	NS				
MBAS (mg/L)	NNS	0.3	1.1	<1.0	NS	NS				
Endrin ketone (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS				
Hexachlorobenzene (mg/L)	0.001	<0.00050	<0.000050	<0.000050	NS	NS				
Methoxychlor (mg/L)	0.004	<0.00050	<0.000050	<0.000050	NS	NS				
Benzidine (mg/L)	0.000	<0.050	<0.050	<0.010	NS	NS				
Bis(2-chlorethoxy)methane (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
Bis(2-chloroethyl)ether (mg/L)	0.030	<0.010	<0.010	<0.010	NS	NS				
Bis(2-chloroisopropyl)ether (mg/L)	0.280	<0.010	<0.010	<0.010	NS	NS				
4-Bromophenyl-phenylether (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
2-Chloronaphthalene (mg/L)	NNS	<0.010	<0.010	<0.0010	NS	NS				
4-Chlorophenyl-phenylether (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
3,3-Dichlorobenzidine (mg/L)	0.0031	<0.010	<0.010	<0.010	NS	NS				
2,4-Dinitrotoluene (mg/L)	0.0140	<0.010	<0.010	<0.010	NS	NS				
2,6-Dinitrotoluene (mg/L)	0.0001	<0.010	<0.010	<0.010	NS	NS				

OUTFALL ID: 202-2.36		MONITORING SEASONS								
RECEIVING WATER: Retention Basin		Summer: June 1- October 31								
				Wint	er: Novem	nber 1- Ma	y 31			
DESIGNATED USES: Water Retention		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012	
	SAMPLING DATE	12/17/08	7/21/09	2/28/10	NS	NS				
Hexachlorobenzene (mg/L)	0.0010	<0.010	<0.010	<0.010	NS	NS				
Hexachloro-1,3-butadiene (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
Hexachlorocyclopentadiene (mg/L)	0.0500	<0.010	<0.010	<0.010	NS	NS				
Hexachloroethane (mg/L)	0.0025	<0.010	<0.010	<0.010	NS	NS				
Indeno(1,2,3-cd)pyrene (mg/L)	0.0005	<0.0010	<0.010	<0.0010	NS	NS				
Isophorone (mg/L)	0.0370	<0.010	<0.010	<0.010	NS	NS				
Nitrobenzene (mg/L)	0.0035	<0.010	<0.010	<0.010	NS	NS				
n-Nitrosodimethylamine (mg/L)	0.0080	<0.050	<0.050	<0.010	NS	NS				
n-Nitrosodiphenylamine (mg/L)	0.0071	<0.010	<0.010	<0.010	NS	NS				
n-Nitrosodi-n-propylamine (mg/L)	0.0050	<0.010	<0.010	<0.010	NS	NS				
Benzylbutyl phthalate (mg/L)	NNS	<0.010	<0.010	<0.0010	NS	NS				
Bis(2-ethylhexyl)phthalate (mg/L)	NNS	<0.010	<0.010	<0.0010	NS	NS				
1,2,4-Trichlorobenzene (mg/L)	0.070	<0.010	<0.010	<0.010	NS	NS				
4-Chloro-3-methylphenol (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
4,6-Dinitro-2-methylphenol (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				

OUTFALL ID: 202-2.36				MONITORING SEASONS						
RECEIVING WATER: Retention Basin				Sumi	ner: June	1- Octobe	er 31			
				Wint	er: Novem	bor 1- Ma	v 31			
DECIONATED LICES, Mater Detertion		Winter	Summer	Winter	Summer	Winter	Summer	Winter		
DESIGNATED USES: Water Retention		2008-09	2009	2009-10	2010	2010-11	2011	2011-12	Summer 2012	
	SAMPLING DATE	12/17/08	7/21/09	2/28/10	NS	NS				
Acid Compounds										
2-Chlorophenol (mg/L)	0.035	<0.010	<0.010	<0.010	NS	NS				
2,4-Dichlorophenol (mg/L)	0.021	<0.010	<0.010	<0.010	NS	NS				
2,4-Dimethylphenol (mg/L)	0.140	<0.010	<0.010	<0.010	NS	NS				
2,4-Dinitrophenol (mg/L)	0.014	<0.010	<0.010	<0.010	NS	NS				
2-Nitrophenol (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
4-Nitrophenol (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS				
Pentachlorophenol (mg/L)	0.001	<0.010	<0.010	<0.010	NS	NS				
Phenol (mg/L)	4.20	<0.010	<0.010	<0.010	NS	NS				
2,4,6-Trichlorophenol (mg/L)	0.00320	<0.010	<0.010	<0.010	NS	NS				
Bases/Neutrals										
Acenaphthene (mg/L)	0.42	<0.0010	<0.010	<0.0010	NS	NS				
Acenaphthylene (mg/L)	NNS	<0.0010	<0.010	<0.0010	NS	NS				
Anthracene (mg/L)	2.10	<0.0010	<0.010	<0.0010	NS	NS				
Benzo(a)anthracene (mg/L)	0.00190	<0.0010	<0.010	<0.0010	NS	NS				
Benzo(a)pyrene (mg/L)	0.00020	<0.0010	<0.010	<0.0010	NS	NS				
Benzo(b)fluoranthene (mg/L)	NNS	<0.0010	<0.010	<0.0010	NS	NS				
Benzo(g,h,i)perylene (mg/L)	NNS	<0.0010	<0.010	<0.0010	NS	NS				
Benzo(k)fluoranthene (mg/L)	0.0480	<0.0010	<0.010	<0.0010	NS	NS				
Chrysene (mg/L)	0.00479	<0.0010	<0.010	<0.0010	NS	NS				
Dibenzo(a,h)anthracene (mg/L)	0.00190	<0.0010	<0.010	<0.0010	NS	NS				
Diethyl phthalate (mg/L)	5.60	<0.010	<0.010	<0.0010	NS	NS				
Dimethyl phthalate (mg/L)	NNS	<0.010	<0.010	<0.0010	NS	NS				
Di-n-butyl phthalate (mg/L)	NNS	<0.010	<0.010	<0.0010	NS	NS				
Di-n-octyl phthalate (mg/L)	2.80	<0.010	<0.010	<0.0010	NS	NS				
Fluoranthene (mg/L)	0.28	<0.0010	<0.010	<0.0010	NS	NS				
Fluorene (mg/L)	0.28	<0.0010	<0.010	<0.0010	NS	NS				
Naphthalene (mg/L)	0.14	<0.0010	<0.010	<0.0010	NS	NS				
Phenanthrene (mg/L)	NNS	<0.0010	<0.010	<0.0010	NS	NS				
Pyrene (mg/L)	0.21	<0.0010	<0.010	<0.0010	NS	NS				

OUTFALL ID: 202-2.36		MONITORING SEASONS									
RECEIVING WATER: Retention Basin		Summer: June 1- October 31									
				Wint	er: Novem	bor 1- Ma	v 21				
DESIGNATED USES: Water Retention			Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012		
SAM	IPLING DATE	12/17/08	7/21/09	2/28/10	NS	NS					
Pesticides											
Aldrin (mg/L)	0.0020	<0.00050	<0.00051	<0.000050	NS	NS					
Alpha BHC (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Beta BHC (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Delta BHC (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Gamma BHC (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Chlordane (mg/L)	0.0020	<0.0050	<0.00050	<0.00050	NS	NS					
4,4-DDD (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
4,4-DDE (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
4,4-DDT (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Dieldrin (mg/L)	0.0020	<0.00050	<0.000050	<0.000050	NS	NS					
Endosulfan I (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Endosulfan II (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Endosulfan sulfate (mg/L)	NNS	<0.00050	<0.000050	<0.000050	NS	NS					
Endrin (mg/L)	0.0020	<0.00050	<0.000050	<0.000050	NS	NS					
Endrin aldehyde (mg/L)	NNS	<0.00050	0.000088	<0.000050	NS	NS					
Heptachlor (mg/L)	0.00040	<0.00050	<0.000050	<0.000050	NS	NS					
Heptachlor epoxide (mg/L)	0.00020	<0.00050	<0.000050	<0.000050	NS	NS					
Toxaphene (mg/L)	NNS	<0.010	<0.00050	<0.00050	NS	NS					

NS - Not Sampled

OUTFALL ID: Tucson MS4 Grant Road		MONITORING SEASONS							
RECEIVING WATER: Santa Cruz		Summer: June 1 - October 31							
				Winter	: Novembe	er 1 - May 3	31		
DESIGNATED USES: ADOT Facility		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012
SAM	PLING DATE	12/1/08	6/30/09	4/23/10	NS	NS			
MONITORING PARAMETERS	WQS								
Flow	NNS	-	-	-	NS	NS			
рН	6.5-8.5	-	-	7.3	NS	NS			
Temperature (F°)	NNS	62.3	88.1	64.4	NS	NS			
Hardness	NNS	250		470	NS	NS			
Total Dissolved Solids (TDS) (mg/L)	500	680*	680*	910	NS	NS			
Total Suspended Solids (TSS) (mg/L)	NNS	110	160	130	NS	NS			
Turbidity (NTU)	NNS	94	-	58	NS	NS			
Biochemical Oxygen Demand (BOD) (mg/L)	NNS	65	44	90	NS	NS			
Chemical Oxygen Demand (COD) (mg/L)	NNS	560	640	490	NS	NS			
Inorganics									
Cyanide, total (mg/L)	0.2	0.0059	<0.0050	<0.10	NS	NS			
Sulfates (mg/L)	250	110	68	-	NS	NS			
Nutriants									
Nitrate (mg/L)	1	<0.10	0.21	9.9	NS	NS			
Nitrite (mg/L)	10	<0.10	<0.10	1.9	NS	NS			
Total Ammonia (mg/L)	NNS	6.2	6.7	<0.50	NS	NS			
Total Kjeldahl Nitrogen (TKN) (mg/L)	NNS	12	14	7.8	NS	NS			
Total Phosphorous (mg/L)	NNS	0.42	0.36	0.58	NS	NS			
Phosphate, Ortho (mg/L)	NNS	0.62	<0.12	310	NS	NS			
Sodium (mg/L)	NNS	-	18	18	NS	NS			
Calcium (mg/L)	NNS	-	100	150	NS	NS			
Chloride (mg/L)	10	26	19	14	NS	NS			

OUTFALL ID: Tucson MS4 Grant Road		MONITORING SEASONS									
RECEIVING WATER: Santa Cruz				Summe	er: June 1	- October	31				
				Winter	: Novembe	er 1 - May :	31				
DESIGNATED USES: ADOT Facility		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012		
SAM	PLING DATE	12/1/08	6/30/09	4/23/10	NS	NS					
Microbiological											
Coliform, fecal (col/100 ml)	NNS	-	-	2400*	NS	NS					
E.Coli (cfu/100 ml)	100.00	-	-	390	NS	NS					
Total Metals											
Antimony (mg/L)	0.00600	-	0.0046	<0.20	NS	NS					
Arsenic (mg/L)	0.05000	<0.020	0.003	<0.040	NS	NS					
Barium (mg/L)	2.0T	0.2	0.2	0.2	NS	NS					
Beryllium (mg/L)	0.00400	<0.0050	<0.0020	<0.0020	NS	NS					
Cadmium (mg/L)	0.00500	-	<0.0050	<0.0020	NS	NS					
Chromium (mg/L)	0.1T	<0.010	<0.010	<0.030	NS	NS					
Copper (mg/L)	1.3T	-	0.033	0.13	NS	NS					
Lead (mg/L)	0.015T	0.015	<0.0050	<0.040	NS	NS					
Mercury (mg/L)	0.00200	<0.00020	<0.00020	<0.0010	NS	NS					
Nickel (mg/L)	0.14000	-	<0.020	<0.050	NS	NS					
Selenium (mg/L)	0.02000	<0.020	0.02	<0.040	NS	NS					
Silver (mg/L)	NNS	<0.010	<0.010	<0.010	NS	NS					
Zinc (mg/L)	2.1T	-	0.18	0.41	NS	NS					
Organic Toxic Pollutnats											
Total Petroleum Hydrobarbons (TPH) (mg/L)	NNS	6.2	-	-	NS	NS					
Oil & Greese (Hexane Extr) (mg/L)	NNS	<5.6	<6.7	9.2	NS	NS					
Chlorine, residual (mg/L)	0.7	<0.10	-	<0.10	NS	NS					

OUTFALL ID: Tucson MS4 Grant Road		MONITORING SEASONS									
RECEIVING WATER: Santa Cruz				Summ	er: June 1	- October	31				
				Winter	: Novembe	er 1 - May	31				
DESIGNATED USES: ADOT Facility		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012		
	SAMPLING DATE	12/1/08	6/30/09	4/23/10	NS	NS					
VOCs, Semi-VOCs and Pesticides											
Benzene (mg/L)	0.005	<0.0010	<0.00050	<0.50	NS	NS					
Ethylbenzene (mg/L)	0.70000	<0.0010	<0.00050	<0.50	NS	NS					
Toluene (mg/L)	1.00000	<0.0050	<0.0050	<0.50	NS	NS					
Total Xylene (mg/L)	10.00000	<0.0030	<0.0015	<0.50	NS	NS					
Chromium, Hexavalent (mg/L)	NNS	-	<0.010	-	NS	NS					
Chromium, Trivalent (mg/L)	NNS	-	<0.010	-	NS	NS					
MBAS (mg/L)	NNS	-	11	-	NS	NS					
Specific conductance (mg/L)	NNS	720	690	1000	NS	NS					
Total Nitrogen (mg/L)	NNS	12	-	11.8	NS	NS					
Toluene - d8 (mg/L)	NNS	99	-	<0.50	NS	NS					
Dibromofluoromethane (mg/L)	TTHM	100	-	-	NS	NS					
Endrin ketone (mg/L)	NNS	-	<0.000050	<0.96	NS	NS					
Hexachlorobenzene (mg/L)	0.00100	-	<0.000050	<96	NS	NS					
Methoxychlor (mg/L)	0.00400	-	<0.000050	<96	NS	NS					
Benzidine (mg/L)	0.00020	-	<0.050	<96	NS	NS					
Bis(2-chlorethoxy)methane (mg/L)	NNS	-	<0.010	<96	NS	NS					
Bis(2-chloroethyl)ether (mg/L)	0.03000	-	<0.010	<96	NS	NS					
Bis(2-chloroisopropyl)ether (mg/L)	0.28000	-	<0.010	<96	NS	NS					
4-Bromophenyl-phenylether (mg/L)	NNS	-	<0.010	<96	NS	NS					
2-Chloronaphthalene (mg/L)	NNS	-	<0.010	<96	NS	NS					
4-Chlorophenyl-phenylether (mg/L)	NNS	-	<0.010	<96	NS	NS					
3,3-Dichlorobenzidine (mg/L)	0.00310	-	<0.010	<190	NS	NS					
2,4-Dinitrotoluene (mg/L)	0.01400	-	<0.010	<96	NS	NS					
2,6-Dinitrotoluene (mg/L)	0.00005	-	<0.010	<96	NS	NS					

OUTFALL ID: Tucson MS4 Grant Road		MONITORING SEASONS									
RECEIVING WATER: Santa Cruz				Summ	er: June 1	- October	31				
				Winter	: Novembe	er 1 - May	31				
DESIGNATED USES: ADOT Facility		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012		
	SAMPLING DATE	12/1/08	6/30/09	4/23/10	NS	NS					
Hexachlorobenzene (mg/L)	0.00100	-	<0.010	<96	NS	NS					
Hexachloro-1,3-butadiene (mg/L)	NNS	-	<0.010	<96	NS	NS					
Hexachlorocyclopentadiene (mg/L)	0.05000	-	<0.010	<96	NS	NS					
Hexachloroethane (mg/L)	0.00250	-	<0.010	<96	NS	NS					
Isophorone (mg/L)	0.03700	-	<0.010	<96	NS	NS					
Nitrobenzene (mg/L)	0.00350	-	<0.010	<96	NS	NS					
n-Nitrosodimethylamine (mg/L)	0.00800	-	<0.050	<96	NS	NS					
n-Nitrosodiphenylamine (mg/L)	0.00710	-	<0.010	<96	NS	NS					
n-Nitrosodi-n-propylamine (mg/L)	0.00500	-	<0.010	<96	NS	NS					
Benzylbutyl phthalate (mg/L)	NNS	-	<0.010	<96	NS	NS					
Bis(2-ethylhexyl)phthalate (mg/L)	NNS	-	<0.010	<96	NS	NS					
1,2,4-Trichlorobenzene (mg/L)	0.07000	-	<0.010	<96	NS	NS					
4-Chloro-3-methylphenol (mg/L)	NNS	-	<0.010	<96	NS	NS					
4,6-Dinitro-2-methylphenol (mg/L)	NNS	-	<0.010	<190	NS	NS					
Acid Compounds											
2-Chlorophenol (mg/L)	0.03500	-	<0.010	<96	NS	NS					
2,4-Dichlorophenol (mg/L)	0.02100	-	<0.010	<96	NS	NS					
2,4-Dimethylphenol (mg/L)	0.14000	-	<0.010	<96	NS	NS					
2,4-Dinitrophenol (mg/L)	0.01400	-	<0.010	<480	NS	NS					
2-Nitrophenol (mg/L)	NNS	-	<0.010	<96	NS	NS					
4-Nitrophenol (mg/L)	NNS	-	<0.010	<480	NS	NS					
Pentachlorophenol (mg/L)	0.00100	-	<0.010	<290	NS	NS					
Phenol (mg/L)	4.20000	-	<0.010	<96	NS	NS					
2,4,6-Trichlorophenol (mg/L)	0.00320	-	<0.010	<96	NS	NS					

OUTFALL ID: Tucson MS4 Grant Road		MONITORING SEASONS									
RECEIVING WATER: Santa Cruz				Summ	er: June 1	- October	31				
				Winter	: Novembe	er 1 - May :	31				
DESIGNATED USES: ADOT Facility		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012		
	SAMPLING DATE	12/1/08	6/30/09	4/23/10	NS	NS					
Bases/Neutrals											
Acenaphthene (mg/L)	0.42000	-	<0.010	<48	NS	NS					
Acenaphthylene (mg/L)	NNS	-	<0.010	<48	NS	NS					
Anthracene (mg/L)	2.10000	-	<0.010	<48	NS	NS					
Benzo(a)anthracene (mg/L)	0.00190	-	<0.010	<48	NS	NS					
Benzo(a)pyrene (mg/L)	0.00020	-	<0.010	<48	NS	NS					
Benzo(b)fluoranthene (mg/L)	NNS	-	<0.010	<96	NS	NS					
Benzo(g,h,i)perylene (mg/L)	NNS	-	<0.010	<48	NS	NS					
Benzo(k)fluoranthene (mg/L)	0.04800	-	<0.010	<96	NS	NS					
Chrysene (mg/L)	0.00479	-	<0.010	<48	NS	NS					
Dibenz(a,h)anthracene (mg/L)	0.00190	-	<0.010	<48	NS	NS					
Diethyl phthalate (mg/L)	5.60000	-	<0.010	<96	NS	NS					
Dimethyl phthalate (mg/L)	NNS	-	<0.010	<96	NS	NS					
Di-n-butyl phthalate (mg/L)	NNS	-	<0.010	<96	NS	NS					
Di-n-octyl phthalate (mg/L)	2.80000	-	<0.010	<96	NS	NS					
Fluoranthene (mg/L)	0.28000	-	<0.010	<48	NS	NS					
Fluorene (mg/L)	0.28000	-	<0.010	<48	NS	NS					
Indeno(1,2,3-cd)pyrene (mg/L)	0.00048	-	<0.010	<48	NS	NS					
Naphthalene (mg/L)	0.14000	-	<0.010	<48	NS	NS					
Phenanthrene (mg/L)	NNS	-	<0.010	<48	NS	NS					
Pyrene (mg/L)	0.21000	-	<0.010	<48	NS	NS					

OUTFALL ID: Tucson MS4 Grant Road		MONITORING SEASONS									
RECEIVING WATER: Santa Cruz				Summe	er: June 1	- October	31				
				Winter	: Novembe	er 1 - May :	31				
DESIGNATED USES: ADOT Facility		Winter 2008-09	Summer 2009	Winter 2009-10	Summer 2010	Winter 2010-11	Summer 2011	Winter 2011-12	Summer 2012		
	SAMPLING DATE	12/1/08	6/30/09	4/23/10	NS	NS					
Pesticides											
Aldrin (mg/L)	0.00200	-	<0.000050	<96	NS	NS					
Alpha BHC (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Beta BHC (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Delta BHC (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Gamma BHC (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Chlordane (mg/L)	0.00200	-	<0.00050	<96	NS	NS					
4,4-DDD (mg/L)	NNS	-	<0.000050	<96	NS	NS					
4,4-DDE (mg/L)	NNS	-	<0.000050	<96	NS	NS					
4,4-DDT (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Dieldrin (mg/L)	0.00200	-	<0.000050	<96	NS	NS					
Endosulfan I (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Endosulfan II (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Endosulfan sulfate (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Endrin (mg/L)	0.00200	-	<0.000050	<96	NS	NS					
Endrin aldehyde (mg/L)	NNS	-	<0.000050	<96	NS	NS					
Heptachlor (mg/L)	0.00040	-	<0.000050	<96	NS	NS					
Heptachlor epoxide (mg/L)	0.00020	-	<0.000050	<96	NS	NS					
Toxaphene (mg/L)	NNS	-	<0.00050	<0.00096	NS	NS					

NS - Not Sampled

## APPENDIX J Industrial Discharge Monitoring Reports



## AZS000018 DISCHARGE MONITORING REPORT (DMR)

(Complete a separate form for each monitoring point)

acility Name: Durango Sign Factory				Point (Outfal	l):				
			Storm dra	n located ap	proximately	south-ce	ntral in the parking lo	ot	
			Year:						
	ona 85009				ar – Summe	r/Winter S	Storm Event		
):				Collected:					
			NA						
Duration of R	ainfall Event:		•		Rainfall Am	ount (inch	es):		
NA					NA				
Time Elapsed	Since Last 0.1	inch Rainfall	Event:		Oualifying I	Rainfall Ev	ent:		
NA				YES NO					
scharge (Inclu	de units: gal. ft <sup>3</sup>	etc.):							
Estimated Total Volume of Discharge (include diffs, gai, it , etc.). <u>32,700 ft<sup>2</sup> XNA</u> of rain = <u>NA</u> X 75% runoff = <u>NA</u> (7.2827) = <u>NA</u>					NO DISCHA	ARGE 🖂			
Qua	antity or Loadi	ng	Qualit	y or Concentr	ation	No Ex	Frequency of	Sample Type	
Average	Maximum	Units	Minimum	Average	Units		Analysis	1 71	
					mg/L		Once each season	Grab	
A	dequate volun	ne of discha	rge was		8				
nc	ot received to	conduct ana	lyses		mg/L		Once each season	Grab	
					ma/I		Once each geogen	Creh	
Total Nitrogen					IIIg/L		Once each season	Grab	
TKN					mg/L		Once each season	Grab	
	): Duration of R NA Time Elapsed NA scharge (Inclue = <u>NA</u> X 75% r Que Average	Duration of Rainfall Event:         NA         Time Elapsed Since Last 0.1         NA         scharge (Include units; gal, ft <sup>2</sup> = <u>NA</u> X 75% runoff = <u>NA</u> (7.2         Quantity or Loadin         Average       Maximum         Adequate volum	): Duration of Rainfall Event: NA Time Elapsed Since Last 0.1 inch Rainfall NA scharge (Include units; gal, ft <sup>3</sup> , etc.): = <u>NA</u> X 75% runoff = <u>NA</u> (7.2827) = <u>NA</u> Quantity or Loading Average Maximum Units Adequate volume of discha	Storm drai         Year:         2010/11 R         2010/11 R         Date/Time (NA)         Duration of Rainfall Event:         NA         Time Elapsed Since Last 0.1 inch Rainfall Event:         NA         scharge (Include units; gal, ft <sup>3</sup> , etc.):         = NA X 75% runoff         Quantity or Loading       Quality	Storm drain located ap         Year:         2010/11 Reporting Year         2010/11 Reporting Year         Date/Time Collected:         NA         Duration of Rainfall Event:         NA         Time Elapsed Since Last 0.1 inch Rainfall Event:         NA         scharge (Include units; gal, ft³, etc.):         = <u>NA</u> X 75% runoff = <u>NA</u> (7.2827) = <u>NA</u> Quantity or Loading       Quality or Concentr         Average       Maximum         Units       Minimum         Adequate volume of discharge was       Image: Concentre	Year: 2010/11 Reporting Year – Summe Date/Time Collected: NA         Duration of Rainfall Event: NA       Rainfall Am NA         Time Elapsed Since Last 0.1 inch Rainfall Event: NA       Qualifying I         Scharge (Include units; gal, ft³, etc.): = NA X 75% runoff = NA (7.2827) = NA       NO DISCHA         Quantity or Loading       Quality or Concentration         Average       Maximum       Units       Minimum       Average       Units         Adequate volume of discharge was not received to conduct analyses       mg/L       mg/L	Storm drain located approximately south-ce         Year:       2010/11 Reporting Year – Summer/Winter S         2010/11 Reporting Year – Summer/Winter S       Date/Time Collected:         NA       NA         Duration of Rainfall Event:       Rainfall Amount (inch NA         Time Elapsed Since Last 0.1 inch Rainfall Event:       Qualifying Rainfall Event:         NA       Guainfall Event:       NO DISCHARGE         Scharge (Include units; gal, ft³, etc.):       NO DISCHARGE       No Ex         Quantity or Loading       Quality or Concentration       No Ex         Average       Maximum       Units       Minimum       Average       Units         Adequate volume of discharge was not received to conduct analyses       mg/L       mg/L       mg/L	Storm drain located approximately south-central in the parking lo	

## APPENDIX K Construction Discharge Monitoring Reports



NO DISCHARGE THIS MONTH


PI 	ROJECT NA [-10 Genega VA -01	MEANDAI Marsh i Cree 0E(21	odress: Station H ele Di)A \$ 010	D -E-NFA	COMPLETE AND SUBMIT ONE COPY PER MONITORING POINT Mail to: ADOT Office of Environmental Services Water Quality Group 1611 W Jackson Street, MD EM02 Phoenix, AZ 85007							
	AZSO	00018-2008 T NUMBER			#/ TORING POIN			118	11			
L				MONT	TOKINO TOIN		MONTH	YEA	R			
	RAMETER		TURBIDITY		Ī	T	1	Streamflow	T			
	NALYSIS TY ield, Lab, Cal		Field			1		Field	Calc.*			
	NTS	culation )	NTUs				-	ft <sup>3</sup> /sec	kg/day			
PR	RMIT	Min.						11 / Sec	TMDL			
	MITS	Mean							Info			
	T	Max.							Only			
		1										
		2										
	<u> </u>	4				<u> </u>						
1		5			+	<u> </u>						
		6			1				<u> </u>			
		7							<u>†</u>			
		8										
		9										
		10						· · · · · · · · · · · · · · · · · · ·				
Ħ	····· ·	12						<b></b>				
E		13										
HUNOW		14			1							
		15										
THE		16										
ΟF		17										
		18 19										
DAY		20					-					
		21					++	·····				
l		22						· · · · · · · · · · · · · · · · · · ·				
[		23					1					
		24										
ŀ		25										
ł		26					-					
ŀ	•	28										
F		29					++		<u> </u>			
t		30					++					
		31					1					
		hly Mean					1					
		est Value							1			
<u>\</u>		est Value										
N	umber of Exc		g Calculations in k	aldau	A							
	11	TOT LOROIN	5 Calculations in K	g/uay: mg/	L X SUCAMION	X 2.4405	g/L x Streamflow	x 0.0024465	]			

I certify under penalty of luw, that this document and all attuchments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Bused on my biguity of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am answer that there are significant penalties for submitting fube information, including the possibility of fine and imprisonment for knowing violations.

SCAN Scholala NAME OF PRINCIPAL EXECUTIVE OFFICER TITLE OF PRINCIPAGEXECUTIVE OFFICER For Sean Schiela SIGNATUR

Z! 18 602-920-9264 TELEPHONE






PI	PROJECT NAME AND ADDRESS: I-10 Marsh Station to Genega Creek HRA-010-E(201)A \$ 010-E-NA			~	COMPLETE AND SUBMIT ONE COPY PER MONITORING POIN							
-	1-10	Marsh	Stanon 1	0								
	Cienego	i Cree	elle-		Mail to	ADOT (	Office of Envir Juality Group	ohmental Servic	es			
AR	FA-01	0-E(2	01)A \$ 010	-E-NFA		1611 W	Jackson Street, AZ 85007	, MD EM02				
·			·····					1 1				
		00018-2008			#2		02	18				
L	PERM	IT NUMBER	<u> </u>	MONI	TORING POINT I	<u>D</u>	MONTH	YEA	R			
	RAMETER		TURBIDITY					Streamflow	<b>T</b>			
	NALYSIS TY ield, Lab, Ca		Field					Field	Calc.*			
	VITS		NTUs					ft <sup>3</sup> /sec	kg/day			
PH	RMIT	Min.						11/360	TMDL			
	MITS	Mean							Info			
	1	Max.		and the second state					Only			
		1										
		3							<b></b>			
		4							+{			
		5										
		6										
ľ	7											
					+				<b> </b>			
	10								<u> </u> ]			
		11			+				<u> </u>			
E		12										
HINOM		13										
		<u>14</u> 15										
HE		15			+							
		17										
QF OF		18			1							
DAY		19			1							
Ã		20										
		21			I							
		22				·		· · · · · · · · · · · · · · · · · · ·				
		24		·····								
		25			1			······				
		26										
		27										
		28		·•	<u>├</u> ──── <u></u>							
ł	10 10 10 10 10 10 10 10 10 10 10 10 10 1	<u>29</u> 30			╂							
		31			╂							
	Mon	thly Mean		····	<u>†</u> {							
	Higl	est Value										
	Lowest Value											
N	umber of Exceedances											
	* T	MDL Loadir	g Calculations in	kg/day: mg	/L x Streamflow x	2.4465 :g/l	. x Streamflow	x 0.0024465				

I certify under penalty of law, that this document and all attuchments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly guthered and evaluated the information submitted Bused on my inguity of the person or persons who manage the system, or these persons directly responsible forguthering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting fusise information, including the possibility of fine and hoprisonment for knowing violations.

Sebela Sean Sebela NAME OF PRINCIPAL EXECUTIVE OFFICER FLC PRINCIPAL EXECUTIVE OFFICER THE CIPALEXECUTIVE OFFICER h<del>le fyngling externi</del> or *Scan Sebe*la

602-820-9264 TELEPHONE






PF	PROJECT NAME AND ADDRESS: I-10 Marsh Station to Genega Creek MA-010-E(201)A \$ 010-E-NA			ha	COMPLET		UBMIT	NF COPY	PER MONITOR	NG BODIT
1	r=0	Marsh	Stanon 7	0						
	Cienega	cree	ville of an	6.15	Ma	v	Vater Qua	lity Group	ohmental Service	s
AR	FA - 0(			I-E-NIA			611 W Ja hoenix, A	ckson Street, Z 85007	MD EM02	
	AZSO	0018-2008		<b></b>	\$3		Г	012	<del>- / 18 -</del>	
		T NUMBER		MONI	TORING POIN	TID	Ľ	MONTH	YEA	R
PA	RAMETERS	}	TURBIDITY			1			Streamflow	TJ
	ALYSIS TY		Field			1			······	Cult
	eld, Lab, Cal IITS	culation*)							Field	Calc.*
		Min.	NTUs						ft <sup>3</sup> /sec	kg/day
	RMIT MITS	Mean								TMDL Info
	WI15	Max.								Only
		1					Ī			<u> </u>
		2								
		3								
		4								
		6			-	+				
		7				+				
		8			1	1				
		9				1				
		10								
<b>1</b> 71		11		-11-14-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-						
Ę		12								
MONTH		13				+				
		15				+				
田		16				1				
OF		17								
		18								
рау		19				ļ				
А	-	20				<u> </u>				
ł		22								
ł		23			+					
[		24				1				
		25								
		26			ļ					
ŀ		27				ļ				
⊦		28				<b> </b>				
ł		30		<u></u>	1			<u>·</u>		
F		31			1	t				
		hly Mean			1					
		est Value								
		est Value								
N	umber of Exc				L	L				
	• TN	MUL Loadin	g Calculations in	kg/day: mg	L x Streamflov	w x 2.4465	i :g/Lx	Streamflow	x 0.0024465	

I certify under penalty of luw, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Bused on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am anware the there are significant penulties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Sean Selvela NAME OF PRINCIPAL EXECUTIVE OFFICER ECC TITLE OF PRIN AL EXECUTIVE OFFICER signature offennopapezyduene officer for Sean Sebela

Z/1B 602-920-9264 TELEPHON





PI - AR	ROJECT NAM [-10] Genegg AA - 011	MEANDA Marsh Gree 0-E(2	DDRESS: Station ek UI)A \$ 01	to 0-E-NFA	COMPLETE AND SUBMIT ONE COPY PER MONITORING Mail to: ADOT Office of Envirohmental Services Water Quality Group 1611 W Jackson Street, MD EM02 Phoenix, AZ 85007						
	AZSOO	0018-2008	]		¥(	l					
L	PERMI	I NUMBEI	<u> </u>	MONI	TORING POIN	NT ID	Ľ	MONTH	YE	AR	
PA	RAMETERS		TURBIDITY	· ]					Streamflow		
	VALYSIS TY ield, Lab, Calc		Field			1			Field	Calc.*	
	NITS		NTUs						ft <sup>3</sup> /sec	kg/day	
PE	RMIT	Min.								TMDL	
LI	JMITS Mean JMITS Max.									Info	
	1				-	+				Only	
		2									
		3									
		4		+							
		6									
		7		1	1	-				+	
		8							1	<u> </u>	
		<u> </u>		4							
		10									
Ħ		12		+	+						
HLNOW		13				+				<u> </u>	
Ŭ		14							1	1	
THE		15 16									
		10		+						<u> </u>	
OF		18								II	
ДΑΥ		19				1				<u> </u>	
A		20									
	····	21 22	1411-141-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		ļ						
		23								<b> </b>	
		24		1	1	1		·····			
		25									
ł	····	26							· · ·		
ŀ		27		<u> </u>		<b> </b>					
ł		28		<del> </del>		<u> </u>					
t		30		1		<u>†</u>					
[		31									
		ily Mean									
		est Value									
N	umber of Exce										
		- Linite			L						


\* TMDL Loading Calculations in kg/day: mg/L x Streamflow x 2.4465 :g/L x Streamflow x 0.0024465

I certify under penalty of law, that this document and all attuchments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly guthered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the best of my knowledge and belief, brue, accurate, and complete. I am aware that fare are significant penalties for submitting failse information, including the possibility of fine and imprisonment for knowing violations.

NAME OF PRINCIPAL EXECUTIVE OFFICER ECC RINCIPAL EXECUTIVE OFFICER TITLE O NCIPAL EXECUTIVE OFFICER

-619-8454 ELEPHON





PF	PROJECT NAME AND ADDRESS: I-10 Marsh Station to Genega Creek ARFA-010-E(201)A \$ 010-E-No											
1	[-10 1	Marsh	Station +	0	COMPLET	E AND	SUBMIT	ONE COPY	PER MONITOR	ING POINT		
-	Genera	Cree	ele		Mail	to:	ADOT O	ffice of Envi	rohmental Service	25		
		-10	- A Min	6.13			Water Qu	ality Group		-		
AR	fA - 010	0-8(4	DUA Z 010	-E-NM			1611 W J	ackson Stree AZ 85007	t, MD EM02			
L							rnoemx,	AL 63007				
<b></b>	1780	0018-2008	······	r	#7							
		T NUMBER		MONI	TORING POINT	1 C J						
L		110000000	·	mon		ID I	l l	MONTH	YEA	<u>.</u> R]		
PA	RAMETERS	}	TURBIDITY	·····	T	r	I		Streamflow	TJ		
	IALYSIS TY		Field			[			Field	Colort		
	eld, Lab, Calo NTS	culation*)								Calc.*		
	115	Min.	NTUs						ft <sup>3</sup> /sec	kg/day		
	RMIT	Mean						<b></b>		TMDL		
	MITS	Max.								Info Only		
		1								- Only		
		2								<u>{</u>		
		3								<u>+</u>		
		4								1		
	ļ	5										
1		6										
	7				-							
	<u> </u>											
		10			+	·····						
		11										
E		12										
HLNOW		13										
		14				_						
HE		15										
		16										
Ь		18			-							
	******	19										
ДΑΥ		20			1							
[		21										
	·····	22										
		23										
		24 25			<u> </u>							
	****	25			<del> </del>							
		27		·····	<u> </u>							
		28			<u> </u>	•••••						
		29										
		30										
		31										
		hly Mean										
		est Value			<b> </b>  -							
N	umber of Exc	est Value			<u> </u>							
			g Calculations in	kp/dav: ma	/I. x Streamflow	x 2 AA	<u> </u>	v Streemflau	v x 0.0024465			
			o were and the Hi		- A DUCALINIOW	N 6.77	سلاط، ده	~ DUGGIIIIOV	v A U.VU2440J	1		


I certify under penalty of law, that this document and all attuchments were prepared ander my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Bused on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am answer that there are significant penalties for submitting fulse information, including the possibility of fine and imprisonment for knowing violations.

7/11/ir NAME OF PRI CIPAL EXECUTIVE OFFICE ECC TITLE OF PRINCIPAD EXECUTIVE OFFICER SIGNATUR ECUTOOFFICER

602-619-8454 TELEPHONE

-






PI	PROJECT NAME AND ADDRESS:								
11	E-10 1	Marsh	Station +	6	COMPLETE	AND	SUBMIT ONE COL	PY PER MONITO	RING POINT
-	Genega	Cree	ile i		Mail	to:	ADOT Office of En	vironmental Servic	es
AR	FA - 01	0-E(2	Station t ek 01)A \$ 010	-E-NFA	<u>s</u>		Water Quality Grou 1611 W Jackson Str Phoenix, AZ 85007	cet, MD EM02	
·					11.2		0		
		0018-2008 T NUMBER		MONT	TOPPIOPOT		03	22	
L	1 23(19)1	INOMBER	<u></u>		TORING POINT		MONTH	H YEA	AR
PA	RAMETERS		TURBIDITY		1			Streamflow	<u>т                                    </u>
	ALYSIS TY		Field						
	eld, Lab, Calo	culation*)	NTUs					Field	Calc.*
	1	Min.	NIUS					ft <sup>3</sup> /sec	kg/day
	RMIT MITS	Mean							_ TMDL Info
1.11	MIIS	Max.							Only
		1			T				
		2							
		3			4				
		4							
		6							
		7			++				
		8			++				
		9						-	
		10							+
¥									
Ę		12		······································					
HLNOW		13		·····	+				ł
		15		······	+				
HE		16			1				<u> </u> ]
Ч		17							
		18							
DAY		19			<u> </u>				
		20			ł				
		22			<u> </u>			+	
ľ		23			<u> </u>				
		24			tt-			+	
ļ		25							
ŀ		26							
┟		27			łł-				
ŀ		28		·	<u> </u>			·	l
ŀ		30			<u>├</u> ────┤-				
	· · · · · · · · · · · · · · · · · · ·	31			<u>├</u>				
		nly Mean						1	
		est Value						1	
		est Value							
N	umber of Exc		- 0-11-1					1	
	- IN	IUL LOadin	g calculations in	kg/day: mg/	L x Streamflow )	<u> 2.446</u>	5 :g/L x Streamfle	ow x 0.0024465	

I certify under penalty of luw, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Bused on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the bast of my knowledge and belief, true, accurate, and complete. I am unvare that there are significant penalties for submitting fulse information, including the possibility of fine and imprisonment for knowing violations.

NAME OF PRINCIPAL EXECUTIVE OFFICER IIINR TITLE OF PRINCIPAL EXECUTIVE OFFICER XECUTIVE OFFICER OPPRINCIP/

602-619-8454 TELEPHONE

ADOT




PROJECT NAME AND ADDRESS: I-10 Marsh Station to				COMPLETE AND SUBMIT ONE COPY PER MONITORING POINT						
I-10 Marsh Station to Genega Creek ARRA-010-E(201)A \$ 010-E-NFA				Mai	l to:	ADOT Office of Envirohmental Services Water Quality Group 1611 W Jackson Street, MD EM02				
ANA -010-ELEVIA & 010-E-NM										
	AZ\$000018-2008				+		٦	met	$\frac{12}{12}$	-+-+-
				TORING POIN	TID	MONTH YEAR				
	RAMETER		TURBIDITY			T			Streamflow	<b></b>
	NALYSIS TY ield, Lab, Cal		Field						Field	Calc.*
	NITS		NTUs	•					ft <sup>3</sup> /sec	kg/day
PE	RMIT	Min.								TMDL
	MITS	Mean								Info
<b></b>		Max.								Only
		1								
		2								
		4								
		5				+				
	6									
	7									
	8					ļ				
	9			·						
	10									
H	12					<u> </u>				
MONTH		13			1	1				
М		14								
THE		15								
		16		······		ļ				
Ы		17				ļ				
		19								
DAY		20								
		21		·····						
ļ		22								
		23		·						
ł	······	24								
ł		25								
ł		27								
		28								
		29								
Ĺ		30								
		31								
		hly Mean								
Highest Value Lowest Value										
Number of Exceedances										
``			g Calculations in I	kg/day: mg	L x Streamflow	x 2.44	165 :0/1	x Streamflow	x 0.0024465	

I certify under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Bused on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Tam Billings ECC-TITLE OF PARISIPAL EXECUTIVE OFFICER PAL EXECUTIVE OFFICER U OF SIGNAT

DATE 602-619-8454 TELEPHONE





$\begin{array}{c c c c c c c c c c c c c c c c c c c $	PF	PROJECT NAME AND ADDRESS:									
AZS000018-2008 $42$ $542$ MONITORING POINT ID $5142+1+1+1$ MONITORING POINT ID $5142$ PARAMETERS       TURBIDITY       MONITORING POINT ID       Streamflow         ANALYSIS TYPE:       Field       Streamflow       Info         UNITS       NTUS       R <sup>1</sup> /sec       Kg/day         DERMIT       Min.       Info       Only         2       Info       Only       Info         2       Info       Info       Info         3       Info       Info       Info         4       Info       Info       Info         9       Info       Info       Info         1       Info       Info       Info         1       Info       Info       Info         1       Info       Info       Info         1       Info       Info       Info <td>11</td> <td colspan="4">1-10 Marsh Station to</td> <td colspan="6">COMPLETE AND SUBMIT ONE COPY PER MONITORING POINT</td>	11	1-10 Marsh Station to				COMPLETE AND SUBMIT ONE COPY PER MONITORING POINT					
AZS000018-2008 $42$ $542$ MONITORING POINT ID $5142+1+1+1$ MONITORING POINT ID $5142$ PARAMETERS       TURBIDITY       MONITORING POINT ID       Streamflow         ANALYSIS TYPE:       Field       Streamflow       Info         UNITS       NTUS       R <sup>1</sup> /sec       Kg/day         DERMIT       Min.       Info       Only         2       Info       Only       Info         2       Info       Info       Info         3       Info       Info       Info         4       Info       Info       Info         9       Info       Info       Info         1       Info       Info       Info         1       Info       Info       Info         1       Info       Info       Info         1       Info       Info       Info <td>ľ</td> <td colspan="4">Cienega Creek</td> <td colspan="4">Mail to: ADOT Office of Environmental Service</td> <td>rvices</td>	ľ	Cienega Creek				Mail to: ADOT Office of Environmental Service				rvices	
AZS000018-2005 PERMIT NUMBER $1 \\ MONTTORING POINT ID$ $1 \\ MONTH$ $YEAR$ PARAMETERS       TURBIDITY       MONTTORING POINT ID       Streamflow       Attack         ANALYSIS       Field       Field       Field       Calc.*         UNITS       NTUS       R <sup>2</sup> /sec       kg/dsy         PERMIT       Maan       NTUS       R <sup>2</sup> /sec       kg/dsy         TMIT       Maan       0nfy       Ntot       Ntot         1       0       0nfy       Ntot       Ntot         2       0       0nfy       Ntot       Ntot         4       0       0nfy       Ntot       Ntot         10       0       0nfy       0nfy       Ntot       Ntot         11       0       0       0nfy       0nfy       0nfy         12       0       0       0       0nfy       0nfy         13       0       0	AR	FA -01	Water Quality Group 1611 W Jackson Street, MD EM02 Phoenix, AZ 85007								
PERMIT NUMBER         MONITORING POINT ID         MONTH         YEAR           PARAMETERS         TURBIDITY          Streamflow            ANALYSIS TYPE:         Field         Field         Field         Calc.*           UNITS         NTUS         NTUS         R <sup>1</sup> /sec         kg/day           PERMIT         Man         1         NTUS         Inth           Q         1          Only         NTUS           2           Only         NTUS           2           Only         NTUS           3            Only           3               4               4               5               10               11               10                10						40			,		
PARAMETERS         TURBIDITY         Streamflow           ANALYSIS TYPE:         Field         Streamflow           UNITS         NTUs         R²/sec         kg/day           DERMIT         Min.         R²/sec         kg/day           UNITS         NTUs         R²/sec         kg/day           DERMIT         Min.         NTUs         R²/sec         kg/day           1						#C					
ANALYSIS TYPE: (Field Lab, Calculation*)         Field         Generation*/ Field         Field         Calc.*           UNITS         NTUS         R <sup>1</sup> /sec         TMDL         TMDL           Max.          0         0nly         TMDL           1           0         0nly           2            0           3            0           4               5               6               9                10                11                10                11                10                11               12					FORING POINT ID			MONTH YEAR			
ANALYSIS TYPE: (Field Lab, Calculation*)         Field         Generation*/ Field         Field         Calc.*           UNITS         NTUS         R <sup>1</sup> /sec         TMDL         TMDL           Max.          0         0nly         TMDL           1           0         0nly           2            0           3            0           4               5               6               9                10                11                10                11                10                11               12	PA	RAMETER		TIRBIDITY						<u>.</u>	
Image: constraint of the second sec							······································			Streamflo	W
Min.         Min.         If rec.         Regard           IMITS         Mean         If rec.         If rec.         If model           1         Max.         Image: Solution of the solution of			culation*)							Field	Calc.*
PERMIT LIMITS         Min. Mean         TMDL Info           Max.         00hy           1         00hy           2         00hy           3         00hy           4         00hy           5         00hy           6         00hy           7         00hy           8         00hy           9         00hy           11         00hy           12         00hy           13         00hy           14         00hy           13         00hy           14         00hy           13         00hy           14         00hy           15         00hy           16         00hy           17         00hy           18         00hy           20         00hy           21         00hy           22         00hy           23         00hy           24         00hy           25         00hy           30         00hy           31         00hy           31         00hy           31         00hy     <				NTUs						ft <sup>3</sup> /sec	kg/day
Identity         Max         Only           1         Only         Only           2         Only         Only           3         Only         Only           3         Only         Only           6         Only         Only           6         Only         Only           7         Only         Only           8         Only         Only           9         Only         Only           10         Only         Only           11         Only         Only           12         Only         Only           14         Only         Only           14         Only         Only           15         Only         Only           16         Only         Only           17         Only         Only           20         Only	PE	RMIT	the second secon								TMDL
1         0         000           2         0         0         0           3         0         0         0         0           6         0         0         0         0         0           9         0         0         0         0         0         0           10         0	LI	MITS	and an and a second						·····		
2         3											Only
4						++					
5	1		3			1					
6			4								
7											
8											
9         10         10           10         11         11           11         11         11           12         11         11           13         11         11           13         11         11           14         11         11           15         11         11           16         11         11           17         11         11           19         11         11           19         11         11           11         11         11           19         11         11           11         11         11           10         11         11           11         11         11           10         11         11           11         11         11           11         11         11           121         11         11           122         11         11           123         11         11           124         11         11           130         11         11           131         11         11<						+					
10     11       11     12       13     13       14     14       15     14       16     17       18     17       20     14       21     17       22     17       23     14       24     14       25     14       26     14       27     14       28     14       29     14       30     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       11     14       121     14       131     14       141     14       152     14       153     14       154     14       155     14       155     14       166     14       17     14       18     14 <td< td=""><td></td><td colspan="2">and the second se</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>		and the second se									
11     <		the second se				++					
15     16       17     17       18     17       20     18       21     17       22     10       23     10       24     10       25     10       26     10       27     10       28     10       30     10       31     10       Monthly Mean     10       Highest Value     10       Lowest Value     10						+					
15     16       17     17       18     17       20     18       21     17       22     10       23     10       24     10       25     10       26     10       27     10       28     10       30     10       31     10       Monthly Mean     10       Highest Value     10       Lowest Value     10	E	the second se									
15     16       17     17       18     17       20     18       21     17       22     10       23     10       24     10       25     10       26     10       27     10       28     10       30     10       31     10       Monthly Mean     10       Highest Value     10       Lowest Value     10	Z									***************************************	
Image: second	Ž					<u> </u>					
17     17       18     19       20     19       21     10       22     10       23     10       24     10       25     10       26     10       27     10       28     10       30     10       31     10       Monthly Mean     10       Highest Value     10       Lowest Value     10	臣										
0       18						-}				·····	
19	ö	the second s				<u>+</u> +-					
21	2					++-					
22         23         24           24         25         26           27         28         29           30         31         21           Monthly Mean         21         21           Highest Value         21         21           Lowest Value         21         21	à										
23	ļ										
24	ŀ					<u> </u>					
25	ŀ					<b>↓</b> ↓_					
26	ł	*****				<u> </u>	· · · · · · · · · · · · · · · · · · ·				
27     28       29     30       31     31       Monthly Mean     31       Highest Value     31       Lowest Value     31	F					<u> </u>					
29     30       31     31       Monthly Mean     31       Highest Value     31       Lowest Value     31       Number of Exceedances     31	Ī		the second s			1					
30     31       Monthly Mean     31       Highest Value     31       Lowest Value     31       Number of Exceedances     31	E					1					
31       Monthly Mean       Highest Value       Lowest Value       Number of Exceedances	ļ										
Monthly Mean	┝										
Highest Value					L	Children and a state					
Lowest Value         Image: Constraint of the second s									l_		
Number of Exceedances											
					┠────┤─						
				g Calculations in	kg/day: mg	/L x Streamflow x	2.4465	:e/L	x Streamflow	x 0.0024465	


I certify under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Bused on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, ihe information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting fulse information, including the possibility of fine and imprisonment for knowing violations.

Billings Iom NAME OF PRINCIPAL EXECUTIVE OFFICER ECC. TITLE OF PRAN GIPAL EXECUTIVE OFFICER SIGNAT PAL EXECUTIVE OFFICER

602-619-TELEPHONE



### ARIZONA DEPARTMENT OF TRANSPORTATION Monthly Discharge Monitoring Report (DMR) Form for the ADOT Statewide Permit #AZS000018-2008



PI	PROJECT NAME AND ADDRESS: I-10 Marsh Station to			to	COMPLETE AND SUBMIT ONE COPY PER MONITORING POINT					RING POINT
AR	I-10 Marsh Station to Genega Creek ARRA-010-E(201)A \$ 010-E-NFA			D-E-NFA	Mail	to:	Water Qu 1611 W J	ffice of Envir ality Group ackson Street AZ 85007	rohmental Servie t, MD EM02	ces
		00018-2008 T NUMBER	<u></u>	MONI	#3 TORING POINT	ID	] [	DT4 MONTH	2   YE	AR
PA	RAMETERS	5	TURBIDITY	T	11				Streamflow	
	ALYSIS TY		Field							
	eld, Lab, Cal	culation*)		ļ					Field	Calc.*
	ITS	Min.	NTUs	<u> </u>					ft <sup>3</sup> /sec	kg/day
1	RMIT	Mean		<u> </u>					· · · · · · · · · · · · · · · · · · ·	TMDL
	VIITS	Max.						·		Info Only
		1			╺┥╼╼╼╼		<del></del>			Only
1		2								
		3			1					
		4								+
		5								
Ι.		6								
		7								
		°								l
		10			++					- <u> </u> ]
		11			++					-{}
E		12			†					+
MONTH		13								+
		14								1
HE		15								
		16			<u> </u>					
Ъ		17								<u> </u> ]
	·····	19								I
DAY		20		······	++			+		<b></b>
[		21			1				······	<u>+</u>
		22								<u> </u>
ļ	····	23								
H		24			-					
ŀ		25			<b>}</b>					
ŀ		20			╂━━━━╋━					
F		28			<u>├</u>					<b> </b>
Ē		29			<u> </u>					
		30								{
		31								
		hly Mean					1			WC.C.C.C.C.C.C.C.C.C.C.C.C.C.C.C.C.C.C.
	High	est Value								
<b>N</b> L	Low umber of Exc	est Value								
N			Calculation - in	1-11-11	L x Streamflow )					
	- 11	INT FORMU	E Calculations in	kg/uay: mg/	L X Streamflow)	× 2.44	05 :g/L :	x Streamflow	x 0.0024465	

I certify under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to ussure that qualified personnel properly gathered and evuluated the information submitted. Bused on my inquiry of the person or persons who manage the system, or those persons directly responsible forgathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am unvite that there are significant penulties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Billings Iam NAME OF PRINCIPAL EXECUTIVE OFFICER ECC-TITLE OF PRI IPAL EXECUTIVE OFFICER SIGNATU PAL EXECUTIVE OFFICER **O** *[*]\*\*

602-619. TELEPHONE

TC: Atizona Department of Transportation 200 Nerth Colords, Suite C Payson, AZ 85541 PROJECT NO, 280 01 288/AC-NH-058-3(043) TRACS NO, H459901C ATTN: Tom Goodman RE: DMR submittal RE: DMR submittal WE ARE SENDING YOU: Submittal Box Data Seport Color Section Description Manufacturer Action Sec. Copies Section Description Manufacturer Action THESE ARE TRANSMITTED: Sec. For Approval Grad proved as Submitted For Approval Sec Comments OUTHER: YOU ARE REQUESTED TO: Resubmitt_Copies for Approval Submit_Copies for Final Distribution YOU ARE REQUESTED TO: Return_Copies Sec Comments DISTRIBUTION: Trans. Copy As Transmitted/Submitted by: Curris Bilow, Project Manager		AMES CON 8333 Eas Scotts TELEPHO	F TRANSMITTAL STRUCTION, INC st Hartford Drive dale, AZ 85255 NE (602) 431-2111 602) 431-5952	
PROJECT NO       280 G1 28/40/C-NH-053-20(43)         ATTN:       Tom Goodman         RE       DIR submittal         TRACS NO       100303-AC-ADDT-T114         WE ARE SENDING YOU:	200 North Colcord, Suite C	portation	DATE:	6/2/2011
ATN: Tom Goodman RE: DMR submittal TRANSMITTAL NO. 100303-AC-ADOT-T114 WE ARE SENDING YOU: X Submittal  Reports Shop Drawings  Samples  OTHER Specifications/Plans  Description  Manufacturer  Action Specifications/Plans Specifications/Plans Copies Section  Description  Manufacturer  Action	1 49001, 1 2 000 11		PROJECT NO TRACS NO.	260 GI 269/AC-NH-053-2(043)N H469801C
Submittal       Reports         Shop Drawings       Samples         OrHER       Data         Copy of Letter       Change Order/Request         Spac.       Space         Scolor       Description         Manufacturer       Action         Space       Section         Description       Manufacturer         Action       Space         Scolor       Description         Manufacturer       Action         Manufacturer       <				
Shop Drawings       Samples       OTHER         Specifications/Plans       Data         Copy of Letter       Change Order/Request         Spec.       Spec.         Copies       Section         Description       Manufacturer         Action         Spec.       Spec.         Copies       Section         Description       Manufacturer         Action         Spec.       Section         Description       Manufacturer         Action         Spec.       Section         Description       Manufacturer         Action         Spec.       Section         Description       Manufacturer         Action       Manufacturer         As Requested       Section         Submit       Copies for Approval         Submit       Copies for Final Distribution         YOUR RESPONSE IS REQUESTED BY: <td></td> <td></td> <td></td> <td></td>				
Specifications/Plans       Data         Copies       Section         Description       Manufacturer         Action         Manufacturer       Action </td <td></td> <td></td> <td></td> <td></td>				
Copy of Letter       Change Order/Request         Spec.       Section         Description       Manufacturer         Action         Manufacturer <td< td=""><td></td><td></td><td></td><td></td></td<>				
Spec. Section       Description       Manufacturer       Action				
Copies       Section       Description       Manufacturer       Action				
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:		Description	Manufacturer	Action
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:			<u> </u>	-
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:			. <u> </u>	nymmit p
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:				
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:	· · · · · · · · · · · · · · · · · · ·			
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:			······································	
For Approval       (A) Approved as Submitted       (E) Not Approved         Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:	<u> </u>		· · · · · · · · · · · · · · · · · · ·	
Resubmittal       (B) Approved as Noted       x For Your Use/Files/Information         For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:	) THESE ARE TRANSMITTED:			
For Color Selection       (C) For Revision & Resubmittal       Final Distribution         As Requested       See Comments       OTHER:	For Approval	(A) Approved as Submitted	(E) Not Approved	
As Requested       See Comments       OTHER:         YOU ARE REQUESTED TO:	Resubmittal	(B) Approved as Noted	x For Your Use/Files/Inforr	nation
As Requested       See Comments       OTHER:         YOU ARE REQUESTED TO:	For Color Selection	(C) For Revision & Resubmittal	Final Distribution	
YOU ARE REQUESTED TO:         ReturnCopies       ResubmitCopies for Approval         SubmitCopies for Final Distribution         YOUR RESPONSE IS REQUESTED BY:         COMMENTS:         DISTRIBUTION:         Trans.       Copy         As Transmitted/Submitted by:         Comment         Comment         Comment         Your RESPONSE IS REQUESTED BY:         Comment         Comment         Your RESPONSE IS REQUESTED BY:         Comment         Your RESPONSE IS REQUESTED BY:         Your RESPONSE IS REQUES			OTHER:	
ReturnCopies       ResubmitCopies for Approval         SubmitCopies for Final Distribution         YOUR RESPONSE IS REQUESTED BY:				
SubmitCopies for Final Distribution         YOUR RESPONSE IS REQUESTED BY:         COMMENTS:         DISTRIBUTION:         Trans.       Copy         As Transmitted/Submitted by:         CMBHG		Resubmit Conjes for Approval		
YOUR RESPONSE IS REQUESTED BY:				
COMMENTS:		Distribution	,	
COMMENTS:		eten rv.		
DISTRIBUTION: Trans. Copy As Transmitted/Submitted by:				
As Transmitted/Submitted by:				
As Transmitted/Submitted by:	No. and the second s			
As Transmitted/Submitted by:				
$C_{15}B_{7}6$ = = =	As Transmitted/Submitted by:	Trans.		
		•		
	1.550			
	Curtis Bilow. Project Manager		<u></u>	



Ames Construction, Inc. 8333 East Hartford Drive Scottsdale, AZ 85255 (602) 431-2111 Fax: (602) 431-5952 AZ ROC Lic# 074995-002 CLASS A



#### June 2, 2011

#### Serial # 100303-AC-AD-L029

Arizona Department of Transportation 200 North Colcord, Suite C Payson, AZ 85541

Attention: Tom Goodman

SUBJECT: Discharge Monitoring Report submittal

*REFERENCE:* SR-260 Doubtful Canyon

Mr. Goodman,

Ames Construction, Inc. (Ames) respectfully transmits a copy of the Discharge Monitoring Report for the period November 1 through May 31<sup>st</sup> pursuant to Part V.F.1.of the Construction General Permit AZG2008-001. Ames faxed a copy to the Arizona Department of Environmental Quality on June 2, 2011. Please note that no discharge occurred during this monitoring period.

If there are any questions or comments, please do not hesitate to contact me at 602.540.7981 (cell) or at the number listed above.

Sincerely, Ames Construction, Inc.

Curtis Bilow Project Manager

Cc: File

		ADR
Construction General Permit AZG2008-001 Discharge Monitoring Report Form	it AZG2008-001 teport Form	Arizona Department of Environmental Quality
۱. Authorization # AZCON- 57967 Project/Site	Name: <u>Payson to Show Low Hury -</u>	Submit to: Arizona Department of Environmental Quality Surface Water Section, Stormwater & General Permits Unit
Monitoring Period (yr/mo/day):	tful Canyon 260 MP 269	1110 West Washington Street, 5415A-1 Phoenix, Arizona 85007
Use this form for reporting analytical and visual	$\frac{7\delta}{10}$ M $\frac{\delta}{2}$ $\frac{\delta}{3}$ $\frac{\delta}{3}$	from the construction site (Permit Part V.F.).
II. Contact Information	V. Pollutants Monitored	
Name: Curtis Bilow	A. Visual Monitoring:	B. Analytical Monitoring:
Address: 8333 E Hert ford Drive	Sheen Color Foam Solids Odor Other Other TSS (Units)	Turbidity pH Other Other
Phone Number. <i>60スーS40 - 79</i> 8 /	. (specify) (specify)	(specify) (specify)
<u> </u>		
III. UISCRAIGE DATE		
	10 1) ISCHORD	
VI. ATTACHMENTS Y IN WIF "YES,"LIST. VII. CERTIFICATION:		
"I certify under penalty of law that this document and all attachme. Personnel properly gather and evaluate the information submitted gathering the information, I believe the information submitted is including the possibility of fine and imprisonment for knowing viola	" certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage this system, or those persons directly responsible for gathering the information. I believe the information submitted is true, accurate, and complete. I am aware that there are significant penalities for submitting false information, including the possibility of fine and imprisonment for knowing violations."	rdance with a system designed to assure that qualified e this system, or those persons directly responsible for significant penalties for submitting false information,
Printed Name: Curtics Billow	Title: Project Manager P	Phone: 603-540-7981
Signature: Ch JC June 2008	Date: 6/2/2011	
		Page 1 of

# **Ames Construction**

	V
A	

To: ADEQ -	Attention Stor General Pern	m Water je nits Units	From:	Ames Cons	truction, Inc.
Fax: 602	-771-4528	)	Pages	1 Z	
Phone:			Date:	6-2-11	
Re: DMR	submittel	for Nov-ma	27 per	ind	
🗆 Urgent	🗆 For Review	🗆 Please Com	· 1	Please Reply	🗆 Please Recycle

• Comments:

# APPENDIX L Maintenance Facility Discharge Monitoring Reports



# AZS000018 DISCHARGE MONITORING REPORT (DMR)

(Complete a separate form for each monitoring point)

Facility Name:	Monitoring I	Monitoring Point (Outfall):									
Nogales Maintenance Yar	d			Outfall from	Outfall from yard (drains approximately 2.75 acres or 119,790 ft <sup>2</sup> )						
Facility Address:				Year:							
1340 North Hohokam Driv		2010/11 Reporting Year –Summer Storm Event									
Monitoring Personnel Name(s		Date/Time Collected:									
Thomas Ross, EEC				7/20/2010 0	7/20/2010 @ 12:45pm						
Time Rainfall Began:	Duration of R	ainfall Event:		·		Rainfall Am		es):			
Approx 10:30am	Approx. 3 Hrs					0.24 (0.02 fee	et)				
Runoff Source:	Time Elapsed	Since Last 0.1	inch Rainfall	Event:		Qualifying R					
Rainfall Snowmelt	Approximatel	y 32 days						YES 🗌 NO			
Estimated Total Volume of Discharge (Include units; gal, ft <sup>3</sup> , etc.): <u>119,790 ft<sup>2</sup> X 0.02 ft<sup>2</sup> of rain = 2,395.8 ft<sup>3</sup> X 75% runoff = 1,796.85 ft<sup>3</sup> ( 7.28)</u>				2827) = 13 <u>,093.6</u>	5 gallons	NO DISCHA	ARGE	]			
Parameter	Quantity or Loading		Quality	Quality or Concentration		No Ex	Frequency of	Sample Type			
	Average	Maximum	Units	Minimum	Average	Units		Analysis	Jan Part Jra		
Ammonia Nitrogen		0.11	Lbs	0.50		mg/L		Once each season	Grab		
Total Dissolved Solids		64.55	Lbs	290		mg/L		Once each season	Grab		
Total Suspended Solids		144.69	Lbs	650		mg/L		Once each season	Grab		
Copper, total		0.11	Lbs	0.51		mg/L		Once each season	Grab		
TPH - DRO		1.18	Lbs	5.3		mg/L		Once each season	Grab		
Residual Chlorine		0.12	Lbs	0.55		mg/L		Once each season	Grab		
Kesiduai Ciliorine		0.12	LUS	0.55		IIIg/L		Once each season	Glav		
Total Coliform		534.24	Lbs	2400		MPN		Once each season	Grab		
E. Coli		534.24	Lbs	2400		MPN		Once each season	Grab		
Total Hardness		NR	Lbs	NR		mg/L		Once each season	Grab		

NR - Not Reported



# AZS000018 DISCHARGE MONITORING REPORT (DMR)

(Complete a separate form for each monitoring point)

Facility Name:				Monitoring Point (Outfall):						
ADOT – Superior Fuel Ya	rd L-413522-	-01		Along the v	Along the west corner of the exterior of the fuel yard					
Facility Address:				Year:						
952 W Main St., Superior, AZ 85273				2010/11 Re	porting Ye	ar – Summer	Storm E	vent		
Monitoring Personnel Name(s):				Date/Time C	ollected:					
Gary Hoffmann, EEC				7/22/10 at 1	11:39am					
Time Rainfall Began:	Duration of R	ainfall Event:				Rainfall Am	ount (inch	es):		
Approximately 9:30 am	Approximately	2 hours				0.21 inches (	or 0.0175 ft	.)		
Runoff Source:		Since Last 0.1 i	nch Rainfall	Event:		Qualifying R				
Rainfall Snowmelt	Approximately	v 15 days						YES 🗌 NO		
Estimated Total Volume of Discharge (Include units; gal, ft <sup>3</sup> , etc.):					NO DISCHARGE					
<u>9,150</u> ft <sup>2</sup> X <u>0.022</u> ft <sup>2</sup> of rain = <u>198.25</u> ft <sup>3</sup> X 75% runoff = <u>148.69 ft<sup>3</sup></u> (7.2827)				<b>7) 100304 1</b>	1		mor _			
$\frac{3,130}{2,130}$ It A $\frac{0.022}{2.022}$ It of fam = 1	<u>196.25</u> It A 757	$\sqrt[6]{runon} = 148.$	<u>69 ft°</u> (7.282)	() = 1.082.84  gal	lons					
Parameter		antity or Loadir		-	or Concentr	ration	No Ex	Frequency of	Sample Type	
				-		ation Units	No Ex	Frequency of Analysis	Sample Type	
Parameter	Qua	antity or Loadir Maximum	ng Units	Quality	or Concentr	Units	No Ex	Analysis		
	Qua	antity or Loadir	ng	Quality	or Concentr		No Ex		Sample Type Grab	
Parameter	Qua	antity or Loadir Maximum	ng Units	Quality	or Concentr	Units	No Ex	Analysis		
Parameter Total Dissolved Solids Total Suspended Solids	Qua	antity or Loadir Maximum 79.52 30.04	ng Units Lbs Lbs	Quality Minimum 450 170	or Concentr	Units mg/L mg/L	No Ex	Analysis Once Per Season Once Per Season	Grab	
Parameter Total Dissolved Solids	Qua	antity or Loadir Maximum 79.52	ng Units Lbs	Quality Minimum 450	or Concentr	Units mg/L	No Ex	Analysis Once Per Season	Grab	
Parameter Total Dissolved Solids Total Suspended Solids	Qua	antity or Loadir Maximum 79.52 30.04	ng Units Lbs Lbs	Quality Minimum 450 170	or Concentr	Units mg/L mg/L	No Ex	Analysis Once Per Season Once Per Season	Grab	




# AZS000018 DISCHARGE MONITORING REPORT (DMR) (Complete a separate form for each monitoring point)

Facility Name:		Monitoring	Monitoring Point (Outfall):									
ADOT – Superior Mainter	nance Yard			Along the s	Along the southeast corner of the maintenance yard							
Facility Address:				Year:								
	951 W Main St., Superior, AZ 85273					2010/2011 Reporting Year – Summer Storm Event						
Monitoring Personnel Name(s		Date/Time Collected:										
Gary Hoffmann, EEC				7/22/10 at	7/22/10 at 11:39am							
Time Rainfall Began:	Duration of R				Rainfall Amount (inches):							
Approximately 9:30 am	Approximately	2 hours				0.21 inches (	or 0.0175 f	t)				
Runoff Source:		Since Last 0.1	inch Rainfal	l Event:		Qualifying F						
Rainfall Snowmelt	Approximately	-					$\boxtimes$	YES 🗌 NO				
Estimated Total Volume of Di <u>16,500</u> ft <sup>2</sup> X <u>0.0175</u> ft <sup>2</sup> of rain =	scharge (Includ = 288 <u>.75</u> ft <sup>3</sup> X 7	de units; gal, ft 5% runoff  = <u>2</u>	<sup>3</sup> , etc.): 2 <u>16.56 ft<sup>3</sup></u> ( 7.2	2827) = <u>1,577.16</u> §	gallons	NO DISCHA	ARGE	]				
Parameter	Qua	antity or Loadi	ng	Quality	or Concentr	ation	No Ex	Frequency of	Sample Type			
	Average	Maximum	Units	Minimum	Average	Units		Analysis				
Oil & Grease (Hexane Extr)		0.94	Lbs	5.3		mg/L		Once per season	Grab			
Total Dissolved Solids		79.52	Lbs	450		mg/L		Once per season	Grab			
Total Suspended Solids		25.52	Lbs	170		mg/L		Once per season	Grab			
Copper		0.04	Lbs	0.28		mg/L		Once per season	Grab			
Copper, Dissolved		0.01	Lbs	0.056		mg/L		Once per season	Grab			

APPENDIX M Maintenance Facility Laboratory Report **Superior Maintenance Yard** 



# Quality Control Summary SDG: L470257





12065 Lebanon Rd Mt. Juliet, TN 37122 (615) 758-5858 (800) 767-5859 Fax (615) 758-5859 Tax I.D 62-0814289 Est. 1970

# Quality Control Summary

SDG: L470257

For: Engineering & Env. Consultants, INC. -AZ Project: Superior Storage and Fueling Yard July 30, 2010

### Sample Receiving and Handling

All sample aliquots were received at the correct temperature, in the proper containers, and with the appropriate preservatives. All method specified holding times were met.

### **Dissolved Solids by Method 2540C**

### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490104. The laboratory control sample associated with this sample was within the laboratory control limits.

### Sample Duplicate Analysis

For analytical batch WG490104 sample duplicate analysis was performed on sample L470043-03. The relative percent differences were within the method limits.

For analytical batch WG490104 sample duplicate analysis was performed on sample L470290-02. The relative percent differences were within the method limits.

### Matrix Spike/Matrix Spike Duplicate

Precision for batch WG490104 was evaluated using the LCS / LCSD. The RPDs were within method limits.

### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

### Oil & Grease (Hexane Extr) by Method 1664A

### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490396. The laboratory control sample associated with this sample was within the laboratory control limits.

### Matrix Spike/Matrix Spike Duplicate

Precision for batch WG490396 was evaluated using the LCS / LCSD. The RPDs were within method limits.

### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

### Suspended Solids by Method 2540D

### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490813. The laboratory control sample associated with this sample was within the laboratory control limits.

### **Sample Duplicate Analysis**

For analytical batch WG490813 sample duplicate analysis was performed on sample L470257-01. The relative percent differences were within the method limits.



# **Quality Control Summary**

12065 Lebanon Rd Mt. Juliet, TN 37122 (615) 758-5858 (800) 767-5859 Fax (615) 758-5859 Tax I.D 62-0814289 Est. 1970

SDG: L470257

For: Engineering & Env. Consultants, INC. -AZ Project: Superior Storage and Fueling Yard July 30, 2010

### Matrix Spike/Matrix Spike Duplicate

Precision for batch WG490813 was evaluated using the LCS / LCSD. The RPDs were within method limits.

#### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

#### **Trace Metals by Method 6010B**

#### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490219. The laboratory control sample associated with this sample was within the laboratory control limits for all compounds.

Sample L470257-01 was analyzed in analytical batch WG490656. The laboratory control sample associated with this sample was within the laboratory control limits for all compounds.

#### **Sample Duplicate Analysis**

For analytical batch WG490219 sample duplicate analysis was performed on sample L470412-01. The relative percent differences were within the method limits.

For analytical batch WG490656 sample duplicate analysis was performed on sample L470580-13. The relative percent differences were within the method limits.

#### Matrix Spike/Matrix Spike Duplicate

For analytical batch WG490219 matrix spike/matrix spike duplicate analysis was performed on sample L470412-01. The matrix spike recoveries and relative percent differences were within laboratory control limits for all target analytes.

For analytical batch WG490656 matrix spike/matrix spike duplicate analysis was performed on sample L470580-13. The matrix spike recoveries and relative percent differences were within laboratory control limits for all target analytes.

#### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

Nancy F. Winters ESC Representative ESC Lab Sciences



12065 Lebanon Rd. Mt. Juliet, TN 37122 (615) 758-5858 1-800-767-5859 Fax (615) 758-5859

Tax I.D. 62-0814289

Est. 1970

Gary Hoffmann Engineering & Env. Consultants, INC. -AZ 7878 N. 16th Street, Suite 140 Phoenix, AZ 85020

### Report Summary

Friday July 30, 2010

Report Number: L470257 Samples Received: 07/23/10 Client Project: 308032.07

Description: Superior Fueling Yard

The analytical results in this report are based upon information supplied by you, the client, and are for your exclusive use. If you have any questions regarding this data package, please do not hesitate to call.

Entire Report Reviewed By:

Daphne Richards , ESC Representative

#### Laboratory Certification Numbers

A2LA - 1461-01, AIHA - 100789, AL - 40660, CA - I-2327, CT - PH-0197, FL - E87487 GA - 923, IN - C-TN-01, KY - 90010, KYUST - 0016, NC - ENV375/DW21704, ND - R-140 NJ - TN002,NJ NELAP - TN002, SC - 84004, TN - 2006, VA - 00109, WV - 233 AZ - 0612, MN - 047-999-395, NY - 11742, WI - 998093910, NV - TN000032008A


Accreditation is only applicable to the test methods specified on each scope of accreditation held by ESC Lab Sciences.

Note: The use of the preparatory EPA Method 3511 is not approved or endorsed by the CA ELAP.

This report may not be reproduced, except in full, without written approval from ESC Lab Sciences. Where applicable, sampling conducted by ESC is performed per guidance provided in laboratory standard operating procedures: 060302, 060303, and 060304.



# Quality Control Summary SDG: L470257





### SAMPLE NUMBER SUPERIOR STORAGE

SSOLIDS	Suspended Solids		1.0	17	<b>'</b> 0		
CAS NO	Analyte		RL mg/l	m	ESULTS g/l	FLAG	
Method: 2540D		Dilution: 1					
Instrument: BAL		Analyst: 183		Preparat	ion Date: 7/2	8/2010 6:38	
Analytic Batch: WC	G490813	Analysis Date: 7/28/2	2010	•	5 Time: 6:38		
2540D							
DSOLIDS	Dissolved Solids		10	45	50		
CAS NO	Analyte		RL mg/l		ESULTS g/l	FLAG	
Method: 2540C		Dilution: 1					
Instrument: BAL		Analyst: 183		Preparat	ion Date: 7/2	7/2010 7:52	
Analytic Batch: WC	5490104	Analysis Date: 7/28/2	2010	•	Time: 10:04		
2540C							
	Oil & Grease (Hexane	Extr)	5.3	<	5.3		
			mg/l		g/l		
CAS NO	Analyte		RL	R	ESULTS	FLAG	
Wieulou, 1004A							
Instrument: BAL Method: 1664A		Analyst: 078 Dilution: 1		Preparat	ion Date: 7/2	1/2010 12:24	
Analytic Batch: WG490396		Analysis Date: 7/28/2	2010		5 Time: 12:32		
1664A					TT: 10.00		
Lab Sample ID :	L470257-01		Date R	eceived :	7/23/2010	)	
Location :	Superior Storage a	nd Fueling Yard	Sample	•	Phillip M		
Source :	SUPERIOR STOR		Date Sampled :		<u>7/22/2010 11:39 AM</u>		
Customer :		v. Consultants, INC	5			<u>308032.07</u> 7/22/2010 11 20 AM	
Customan	Engineening 0- En	Concultanta INC	Duciast		2000220	7	

Comments:

1) Sample results are reported as rounded values.

2) These results are applicable only to the items tested.



### SAMPLE NUMBER SUPERIOR STORAGE

				50	LIGICIÓ	IORIGE
					YARI	D
Customer :	Engineering & Env	v. Consultants, INC	Project :	:	<u>308032.0</u>	<u>7</u>
Source :	SUPERIOR STOR	SUPERIOR STORAGE YARD		mpled :	7/22/2010 11:39 AM	
Location :	Superior Storage and	nd Fueling Yard			Phillip M	cNamara
Lab Sample ID :	1 0		-	ceived :	7/23/2010	
6010B						
Analytic Batch: WG	490219	Analysis Date: 7/28/2	2010	Analysis	s Time: 10:29	)
Instrument: ICP6		Analyst: 338		•	ion Date: 7/2	
Method: 6010B		Dilution: 1		1		
CAS NO	Analyte		RL	R	ESULTS	FLAG
	1 inuty te		mg/l		g/l	12:10
7440-50-8	Copper		0.020		28	
6010B						
Analytic Batch: WG	490656	Analysis Date: 7/28/2	2010	Analysis	s Time: 11:58	
Instrument: ICP6		Analyst: 338		Preparat	ion Date:	
Method: 6010B		Dilution: 1				
CAS NO	Analyte		RL	R	ESULTS	FLAG
			mg/l		g/l	
7440-50-8	Copper, Dissolved		0.020	0.	056	
LEGEND						
RL -	Reporting Limit					

Comments:

1) Sample results are reported as rounded values.

2) These results are applicable only to the items tested.



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Dissolved Solids by Method 2540C		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490104
Analysis Date:	7/28/2010 10:04:00 PM	Analyst:	183
Instrument ID:	BAL	Extraction Date:	7/24/2010
Sample Numbers	: L470257-01		

### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Dissolved Solids		<10.0	

### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Dissolved Solids	8800	8660	98.4	85 - 115	

### Laboratory Control Sample Duplicate (LCSD)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Dissolved Solids	8800	8720	99.0	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Dissolved Solids by Method 2540C	,	
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490104
Analysis Date:	7/28/2010 10:04:00 PM	Analyst:	183
Instrument ID:	BAL	Extraction Date:	7/24/2010
Sample Numbers	: L470257-01		

### Laboratory Control Sample/ Laboratory Control Sample Duplicate

Analyte	Spike	LCS	% Rec	LCSD	% Rec	Control Limits	Qualifier	% RPD	Control Limits	Qualifier
Dissolved Solids	8800	8660	98.4	8720	99.0	85-115		0.6	20	

### Sample Duplicate L470043-03

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Dissolved Solids	2300	2240	2.4	5	

### Sample Duplicate L470290-02

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Dissolved Solids	1700	1650	3.2	5	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Oil & Grease (Hexane Extr) by Method 1664A	,	
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490396
Analysis Date:	7/28/2010 12:32:00 PM	Analyst:	078
Instrument ID:	BAL	Extraction Date:	7/27/2010
Sample Numbers:	L470257-01		

### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Oil & Grease (Hexane Extr)		<5.00	

### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Oil & Grease (Hexane Extr)	40.0	40.0	100	78 - 114	

### Laboratory Control Sample Duplicate (LCSD)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Oil & Grease (Hexane Extr)	40.0	40.0	100	78 - 114	



Test:

12065 Lebanon Rd Mt. Juliet, TN 37122 (615) 758-5858 (800) 767-5859 Fax (615) 758-5859 Tax I.D 62-0814289 Est. 1970

# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Oil & Grease (Hexane Extr) by Method 1664A

Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	<b>Analytic Batch:</b>	WG490396
Analysis Date:	7/28/2010 12:32:00 PM	Analyst:	078
Instrument ID:	BAL	Extraction Date:	7/27/2010
Sample Numbers	: L470257-01		

Laboratory Control Sample/ Laboratory Control Sample Duplicate										
	-	-	%	•	%	Control	-	%	Control	
Analyte	Spike	LCS	Rec	LCSD	Rec	Limits	Qualifier	RPD	Limits	Qualifier
Oil & Grease (Hexane Extr)	40.0	40.0	100	40.0	100	78-114		0.0	20	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Suspended Solids by Method 2540D	,	
308032.07	Matrix:	Water - mg/L
Superior Storage and Fueling Yard	EPA ID:	TN00003
7/22/2010	<b>Analytic Batch:</b>	WG490813
7/28/2010 6:38:00 PM	Analyst:	183
BAL	Extraction Date:	7/28/2010
: L470257-01		
	308032.07 Superior Storage and Fueling Yard 7/22/2010 7/28/2010 6:38:00 PM	308032.07Matrix:Superior Storage and Fueling YardEPA ID:7/22/2010Analytic Batch:7/28/2010 6:38:00 PMAnalyst:BALExtraction Date:

### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Suspended Solids		<1.00	

### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Suspended Solids	773	800	103	85 - 115	

### Laboratory Control Sample Duplicate (LCSD)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Suspended Solids	773	772	99.9	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Suspended Solids by Method 2540D		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490813
Analysis Date:	7/28/2010 6:38:00 PM	Analyst:	183
Instrument ID:	BAL	Extraction Date:	7/28/2010
Sample Numbers	: L470257-01		

### Laboratory Control Sample/ Laboratory Control Sample Duplicate

Analyte	Spike	LCS	% Rec	LCSD	% Rec	Control Limits	Qualifier I	% RPD	Control Limits	Qualifier
Suspended Solids	773	800	103	772	99.9	85-115		3.6	20	

# Sample Duplicate L470257-01

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Suspended Solids	170	176	3.5	5	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490219
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/25/2010
Sample Numbers	: L470257-01		

### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Copper	7440-50-8	< 0.0200	

### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Copper	1.13	1.13	100	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490656
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/28/2010
Sample Numbers	: L470257-01		

### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Copper,Dissolved	7440-50-8	< 0.0200	

### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Copper, Dissolved	1.13	1.09	96.5	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	<b>Analytic Batch:</b>	WG490219
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/25/2010
Sample Numbers	: L470257-01		

### **Sample Duplicate**

L470412-01

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Copper	0.00000	0.0000			

### Matrix Spike/Matrix Spike Duplicate

			Ι	.47041	12-01						
	Spike			%		%	Control	% Rec	%	Control	RPD
Analyte	Value	Sample	MS	Rec	MSD	Rec	Limits	Qualifier	RPD	Limits	Qual
Copper	1.13	0.00000	1.16	103	1.15	102	75-125		0.9	20	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490656
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/28/2010
Sample Numbers	: L470257-01		

### **Sample Duplicate**

L470580-13

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Copper, Dissolved	0.00000	0.0000			

### Matrix Spike/Matrix Spike Duplicate

	Spike		Ι	_47058 %	30-13	%	Control	% Rec	%	Control	RPD
Analyte	1	Sample	MS	Rec	MSD	Rec	Limits	Qualifier			Qual
Copper, Dissolved	1.13	0.00000	1.07	94.7	1.07	94.7	75-125		0.0	20	


Company Name/Address			Alternate B	illing				Anal	ysis/C	ontain	er/Pre	servati	ve		Chain of Custody
EEC														£033	Page_1_of1_
7878 N. 16th St., Suite 140 Phoenix, AZ 85020												17 17 17 17 17 17 17 17 17 17 17 17 17 1		Prepared by:	
		ĸ	Report to:	ARY HOF	EMANN						Pres			ENVIRON Science cor 12065 Leba	<b>p</b> non Road
Project Description: Superior Storage	e and Fueling	y Yard	GHOFFI	City/	CPKX-CO	m				n n	No Pr	-		Mt. Juliet TN	
PHONE:602-248-7702	Client Project I			Superent Lab Project#			Pres	6	4	イ	Щ			Phone (615) Phone (800 FAX (61	
FAX: 602-248-7851 Collected by:	3080	<del>, , , , , , , , , , , , , , , , , , , </del>		P.O.#			Ž	Pres	ΗC	HNO3	500ml HD			n an	
PHILLE MCNAMALA Colleged by(gignature):	Superior Rush? (L		<b>s<u>é 9</u>4~0</b> be Notified)	Date Result	s Needed	No	HDPE	E No	Clear						(lab use only)
Packed on Ice N_Y	l1	WO Day	100% 50% y25%		loXYes lo_Yes	of	250ml HDPE	1L HDPE		500ml HDPE	(Dissolved)			Template/Prelogin Shipped Via:	
Sample ID	Comp/Grab	Matrix	Depth	Date	Time	Cntrs	TDS	TSS	OGHEX	Cu	Cu (I			Remarks/contaminant	Sample # (lab only)
SUPERIOR STORAGE YARD	GRAB	or		7/2/10	11:39Am	5	X	X	X	X	X				L470257-1
·				+											
											a	-			
												<u>ः</u> य			
													*.		
					ļ,										
Matrix: SS-Soil/Solid GW-Groundwa	iter WW-Wa	stewater I	OW-Drinking V	Vater OT-O	ther STORM	NATE	ik.						рН	Temp	

Relinquisher by:(Signature       Date:       Time:       Received by:(Signature)       Samples returned via: FedEx UPS_Other_       Condition       (lab use only)         Relinquisher by:(Signature       Date:       Time:       Received by:(Signature)       Samples returned via: FedEx UPS_Other_       Condition       (lab use only)         Relinquisher by:(Signature       Date:       Time:       Received by:(Signature)       Temp:       Bottles Received:       COCS F         Relinquisher by:(Signature       Date:       Time:       Received for lab by:(Signature)       Date:       Time:       pH Checked:       NCF:			Other	Flow						
Relinquisher by:(Signature     Date:     Time:     Received by: (Signature)     Temp: 2,3°     Bottles Received: 5       Relinquisher by:(Signature)     Date:     Time:     pH Checked:     NCF:		(lab use only	Condition			Received by (Signature)	Time:		•	· · · · · · · · · · · · · · · ·
Relinquisher by:(Signature     Date:     Time:     Received for lab by: (Signature)     Date:     Time:     pH Checked:     NCF:	~11	SF				Received by: (signature)	Time:		•	
	DIC			5	2.300	1 200				
1801 1801 1800 123/10 0900 27 1801	18	NCF: 18 of					Time:	Date:		Relinquisher by:(Signature

**Superior Fuel Yard** 



# Quality Control Summary SDG: L470257





12065 Lebanon Rd Mt. Juliet, TN 37122 (615) 758-5858 (800) 767-5859 Fax (615) 758-5859 Tax I.D 62-0814289 Est. 1970

# Quality Control Summary

SDG: L470257

For: Engineering & Env. Consultants, INC. -AZ Project: Superior Storage and Fueling Yard July 30, 2010

### Sample Receiving and Handling

All sample aliquots were received at the correct temperature, in the proper containers, and with the appropriate preservatives. All method specified holding times were met.

### **Dissolved Solids by Method 2540C**

### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490104. The laboratory control sample associated with this sample was within the laboratory control limits.

### Sample Duplicate Analysis

For analytical batch WG490104 sample duplicate analysis was performed on sample L470043-03. The relative percent differences were within the method limits.

For analytical batch WG490104 sample duplicate analysis was performed on sample L470290-02. The relative percent differences were within the method limits.

### Matrix Spike/Matrix Spike Duplicate

Precision for batch WG490104 was evaluated using the LCS / LCSD. The RPDs were within method limits.

### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

### Oil & Grease (Hexane Extr) by Method 1664A

### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490396. The laboratory control sample associated with this sample was within the laboratory control limits.

### Matrix Spike/Matrix Spike Duplicate

Precision for batch WG490396 was evaluated using the LCS / LCSD. The RPDs were within method limits.

### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

### Suspended Solids by Method 2540D

### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490813. The laboratory control sample associated with this sample was within the laboratory control limits.

### **Sample Duplicate Analysis**

For analytical batch WG490813 sample duplicate analysis was performed on sample L470257-01. The relative percent differences were within the method limits.



# **Quality Control Summary**

12065 Lebanon Rd Mt. Juliet, TN 37122 (615) 758-5858 (800) 767-5859 Fax (615) 758-5859 Tax I.D 62-0814289 Est. 1970

SDG: L470257

For: Engineering & Env. Consultants, INC. -AZ Project: Superior Storage and Fueling Yard July 30, 2010

### Matrix Spike/Matrix Spike Duplicate

Precision for batch WG490813 was evaluated using the LCS / LCSD. The RPDs were within method limits.

#### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

#### **Trace Metals by Method 6010B**

#### Laboratory Control Sample

Sample L470257-01 was analyzed in analytical batch WG490219. The laboratory control sample associated with this sample was within the laboratory control limits for all compounds.

Sample L470257-01 was analyzed in analytical batch WG490656. The laboratory control sample associated with this sample was within the laboratory control limits for all compounds.

#### **Sample Duplicate Analysis**

For analytical batch WG490219 sample duplicate analysis was performed on sample L470412-01. The relative percent differences were within the method limits.

For analytical batch WG490656 sample duplicate analysis was performed on sample L470580-13. The relative percent differences were within the method limits.

#### Matrix Spike/Matrix Spike Duplicate

For analytical batch WG490219 matrix spike/matrix spike duplicate analysis was performed on sample L470412-01. The matrix spike recoveries and relative percent differences were within laboratory control limits for all target analytes.

For analytical batch WG490656 matrix spike/matrix spike duplicate analysis was performed on sample L470580-13. The matrix spike recoveries and relative percent differences were within laboratory control limits for all target analytes.

#### **Blank Analysis**

The method blank, the initial, and all continuing calibration blanks contained no analytes at concentrations above the method reporting limit.

Nancy F. Winters ESC Representative ESC Lab Sciences



12065 Lebanon Rd. Mt. Juliet, TN 37122 (615) 758-5858 1-800-767-5859 Fax (615) 758-5859

Tax I.D. 62-0814289

Est. 1970

Gary Hoffmann Engineering & Env. Consultants, INC. -AZ 7878 N. 16th Street, Suite 140 Phoenix, AZ 85020

### Report Summary

Friday July 30, 2010

Report Number: L470257 Samples Received: 07/23/10 Client Project: 308032.07

Description: Superior Fueling Yard

The analytical results in this report are based upon information supplied by you, the client, and are for your exclusive use. If you have any questions regarding this data package, please do not hesitate to call.

Entire Report Reviewed By:

Daphne Richards , ESC Representative

### Laboratory Certification Numbers

A2LA - 1461-01, AIHA - 100789, AL - 40660, CA - I-2327, CT - PH-0197, FL - E87487 GA - 923, IN - C-TN-01, KY - 90010, KYUST - 0016, NC - ENV375/DW21704, ND - R-140 NJ - TN002,NJ NELAP - TN002, SC - 84004, TN - 2006, VA - 00109, WV - 233 AZ - 0612, MN - 047-999-395, NY - 11742, WI - 998093910, NV - TN000032008A


Accreditation is only applicable to the test methods specified on each scope of accreditation held by ESC Lab Sciences.

Note: The use of the preparatory EPA Method 3511 is not approved or endorsed by the CA ELAP.

This report may not be reproduced, except in full, without written approval from ESC Lab Sciences. Where applicable, sampling conducted by ESC is performed per guidance provided in laboratory standard operating procedures: 060302, 060303, and 060304.



# Quality Control Summary SDG: L470257





### SAMPLE NUMBER SUPERIOR STORAGE

SSOLIDS	Suspended Solids		1.0	17	<b>'0</b>	
CAS NO	Analyte		RL mg/l	m	ESULTS g/l	FLAG
Method: 2540D		Dilution: 1				
Instrument: BAL		Analyst: 183		Preparat	ion Date: 7/2	8/2010 6:38
Analytic Batch: WO	G490813	Analysis Date: 7/28/2	2010	•	Time: 6:38	
2540D						
DSOLIDS	Dissolved Solids		10	45	50	
CAS NO	Analyte		RL mg/l		ESULTS g/l	FLAG
Method: 2540C		Dilution: 1				
Instrument: BAL		Analyst: 183		Preparat	ion Date: 7/2	7/2010 7:52
Analytic Batch: WO	5490104	Analysis Date: 7/28/2	2010	•	Time: 10:04	
2540C						
	Oil & Grease (Hexane	Extr)	5.3	<	5.3	
			mg/l		g/l	
CAS NO	Analyte		RL	R	ESULTS	FLAG
Meulou: 1004A						
Instrument: BAL Method: 1664A		Analyst: 078 Dilution: 1		Preparat	ion Date: 7/2	7/2010 12:24
Analytic Batch: WC	3490396	Analysis Date: 7/28/2	2010		Time: 12:32	
1664A						
Lab Sample ID :	L470257-01		Date R	eceived :	7/23/2010	)
Location :	Superior Storage a	nd Fueling Yard	Sample	•	<u>Phillip M</u>	
Source :	SUPERIOR STOR			ampled :		<u>) 11:39 AN</u>
Customer :		v. Consultants, INC	•		<u>308032.0</u>	
C		Committee DIC	D		200022.0	7

Comments:

1) Sample results are reported as rounded values.

2) These results are applicable only to the items tested.



#### SAMPLE NUMBER SUPERIOR STORAGE

				50	LIGICIÓ	IORIGE
					YARI	D
Customer :	Engineering & Env	v. Consultants, INC	Project :	:	<u>308032.0</u>	<u>7</u>
Source :	SUPERIOR STOR	AGE YARD	Date Sa	mpled :	7/22/2010	) 11:39 AN
Location :	Superior Storage and	nd Fueling Yard	Sampleo	d By :	Phillip M	cNamara
Lab Sample ID :	1 0		-	ceived :	7/23/2010	
6010B						
Analytic Batch: WG	490219	Analysis Date: 7/28/2	2010	Analysis	s Time: 10:29	)
Instrument: ICP6		Analyst: 338		•	ion Date: 7/2	
Method: 6010B		Dilution: 1		1		
CAS NO	Analyte		RL	R	ESULTS	FLAG
	1 inuty te		mg/l		g/l	12:10
7440-50-8	Copper		0.020		28	
6010B						
Analytic Batch: WG	490656	Analysis Date: 7/28/2	2010	Analysis	s Time: 11:58	
Instrument: ICP6		Analyst: 338		Preparat	ion Date:	
Method: 6010B		Dilution: 1				
CAS NO	Analyte		RL	R	ESULTS	FLAG
			mg/l		g/l	
7440-50-8	Copper, Dissolved		0.020	0.	056	
LEGEND						
RL -	Reporting Limit					

Comments:

1) Sample results are reported as rounded values.

2) These results are applicable only to the items tested.



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Dissolved Solids by Method 2540C		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490104
Analysis Date:	7/28/2010 10:04:00 PM	Analyst:	183
Instrument ID:	BAL	Extraction Date:	7/24/2010
Sample Numbers	: L470257-01		

#### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Dissolved Solids		<10.0	

#### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Dissolved Solids	8800	8660	98.4	85 - 115	

#### Laboratory Control Sample Duplicate (LCSD)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Dissolved Solids	8800	8720	99.0	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Dissolved Solids by Method 2540C	,	
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490104
Analysis Date:	7/28/2010 10:04:00 PM	Analyst:	183
Instrument ID:	BAL	Extraction Date:	7/24/2010
Sample Numbers	: L470257-01		

### Laboratory Control Sample/ Laboratory Control Sample Duplicate

Analyte	Spike	LCS	% Rec	LCSD	% Rec	Control Limits	Qualifier	% RPD	Control Limits	Qualifier
Dissolved Solids	8800	8660	98.4	8720	99.0	85-115		0.6	20	

#### Sample Duplicate L470043-03

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Dissolved Solids	2300	2240	2.4	5	

#### Sample Duplicate L470290-02

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Dissolved Solids	1700	1650	3.2	5	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Oil & Grease (Hexane Extr) by Method 1664A	,	
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490396
Analysis Date:	7/28/2010 12:32:00 PM	Analyst:	078
Instrument ID:	BAL	Extraction Date:	7/27/2010
Sample Numbers:	L470257-01		

#### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Oil & Grease (Hexane Extr)		<5.00	

#### Laboratory Control Sample (LCS)

Analyte	True Value Found		Recovery %	Control Limits	Qualifiers
Oil & Grease (Hexane Extr)	40.0	40.0	100	78 - 114	

#### Laboratory Control Sample Duplicate (LCSD)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Oil & Grease (Hexane Extr)	40.0	40.0	100	78 - 114	



Test:

12065 Lebanon Rd Mt. Juliet, TN 37122 (615) 758-5858 (800) 767-5859 Fax (615) 758-5859 Tax I.D 62-0814289 Est. 1970

# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Oil & Grease (Hexane Extr) by Method 1664A

Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	<b>Analytic Batch:</b>	WG490396
Analysis Date:	7/28/2010 12:32:00 PM	Analyst:	078
Instrument ID:	BAL	Extraction Date:	7/27/2010
Sample Numbers	: L470257-01		

Laboratory Control Sample/ Laboratory Control Sample Duplicate										
	-	-	%	•	%	Control	-	%	Control	
Analyte	Spike	LCS	Rec	LCSD	Rec	Limits	Qualifier	RPD	Limits	Qualifier
Oil & Grease (Hexane Extr)	40.0	40.0	100	40.0	100	78-114		0.0	20	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Suspended Solids by Method 2540D	,	
308032.07	Matrix:	Water - mg/L
Superior Storage and Fueling Yard	EPA ID:	TN00003
7/22/2010	<b>Analytic Batch:</b>	WG490813
7/28/2010 6:38:00 PM	Analyst:	183
BAL	Extraction Date:	7/28/2010
: L470257-01		
	308032.07 Superior Storage and Fueling Yard 7/22/2010 7/28/2010 6:38:00 PM	308032.07Matrix:Superior Storage and Fueling YardEPA ID:7/22/2010Analytic Batch:7/28/2010 6:38:00 PMAnalyst:BALExtraction Date:

#### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Suspended Solids		<1.00	

#### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Suspended Solids	773	800	103	85 - 115	

#### Laboratory Control Sample Duplicate (LCSD)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Suspended Solids	773	772	99.9	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Suspended Solids by Method 2540D		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490813
Analysis Date:	7/28/2010 6:38:00 PM	Analyst:	183
Instrument ID:	BAL	Extraction Date:	7/28/2010
Sample Numbers	: L470257-01		

#### Laboratory Control Sample/ Laboratory Control Sample Duplicate

Analyte	Spike	LCS	% Rec	LCSD	% Rec	Control Limits	Qualifier I	% RPD	Control Limits	Qualifier
Suspended Solids	773	800	103	772	99.9	85-115		3.6	20	

# Sample Duplicate L470257-01

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Suspended Solids	170	176	3.5	5	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490219
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/25/2010
Sample Numbers	: L470257-01		

#### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Copper	7440-50-8	< 0.0200	

#### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Copper	1.13	1.13	100	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	Analytic Batch:	WG490656
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/28/2010
Sample Numbers	: L470257-01		

#### **Method Blank**

Analyte	CAS	PQL	Qualifiers
Copper,Dissolved	7440-50-8	< 0.0200	

#### Laboratory Control Sample (LCS)

Analyte	True Value	Found	Recovery %	Control Limits	Qualifiers
Copper, Dissolved	1.13	1.09	96.5	85 - 115	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	<b>Analytic Batch:</b>	WG490219
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/25/2010
Sample Numbers	: L470257-01		

#### **Sample Duplicate**

L470412-01

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Copper	0.00000	0.0000			

#### Matrix Spike/Matrix Spike Duplicate

L470412-01											
	Spike			%		%	Control	% Rec	%	Control	RPD
Analyte	Value	Sample	MS	Rec	MSD	Rec	Limits	Qualifier	RPD	Limits	Qual
Copper	1.13	0.00000	1.16	103	1.15	102	75-125		0.9	20	



# Quality Control Summary SDG: L470257 Engineering & Env. Consultants, INC. -AZ

Test:	Trace Metals by Method 6010B		
Project No:	308032.07	Matrix:	Water - mg/L
Project:	Superior Storage and Fueling Yard	EPA ID:	TN00003
Collection Date:	7/22/2010	<b>Analytic Batch:</b>	WG490656
Analysis Date:	7/28/2010	Analyst:	338
Instrument ID:	ICP6	Extraction Date:	7/28/2010
Sample Numbers	L470257-01		

#### **Sample Duplicate**

L470580-13

Name	Sample Results	Duplic Results	%RPD	Limit	Qualifiers
Copper, Dissolved	0.00000	0.0000			

#### Matrix Spike/Matrix Spike Duplicate

	Spike		Ι	_47058 %	30-13	%	Control	% Rec	%	Control	RPD
Analyte	1	Sample	MS	Rec	MSD	Rec	Limits	Qualifier			Qual
Copper, Dissolved	1.13	0.00000	1.07	94.7	1.07	94.7	75-125		0.0	20	

Company Name/Address			Alternate B	illing				Anal	ysis/C	ontair	er/Pre	eservat	ive		Chain of Custody
EEC														A033	Page_1_of1_
7878 N. 16th St., Suite 140 Phoenix, AZ 85020												1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	24. 24.	Prepared by:	
		ĸ	Report to:	ARY HOF	FMANN						Pres			ENVIRON Science cor 12065 Leba	<b>p</b> non Road
Project Description: Superior Storage	e and Fueling	Yard	GHOFFI	City/	CPHX-CM State Collected:	m				a	No Pr			Mt. Juliet TN	
PHONE:602-248-7702	Client Project I			Sup <u>equal</u> Lab Project#			Pres	6	4	イ	ЪЕ				)/58-5858 )) 767-5859  5)758-5859
FAX: 602-248-7851 Collected by:	3080	<del>, , , , , , , , , , , , , , , , , , , </del>		P.O.#			Ž	Pres	ΗC	HNO3	500ml HD			1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	
PHILLE MCNAMALA Colleged by(gignature):	Superior Rush? (L		<b>s<u>é</u> 9440</b> pe Notified)	Date Result	ts Needed	No	HDPE	DE No	Clear					CoCode ENGENVPAZ	(lab use only)
Packed on Ice N_Y	<b></b> 1	WO Day	100% 50% y25%		loXYes	of	250ml HDPE	1L HDPE	1	500ml HDPE	(Dissolved)			Template/Prelogin Shipped Via:	
Sample ID	Comp/Grab	Matrix	Depth	Date	Time	Cntrs	TDS	TSS	OGHEX	Cu	Cu (I	1		Remarks/contaminant	Sample # (lab only)
SUPERIOR STORAGE YARD	GRAB	or		7/2/10	11:39Am	5	X	X	X	X	X				L470257-1
·				<u> </u>											
					<u>.                                    </u>			-							
													a'		
Matrix: SS-Soil/Solid GW-Groundwa	iter WW-Wa	stewater I	DW-Drinking V	Vater OT- O	ther STORM	NATE	ik.						рН	Temp	

2,3° 5		Other	Flow						Remarks.
Relinquisher by:(Signature Date: Time: Received by Gignature Temp: 2,3° Souther Southe	(lab use only)	Condition (la			Received by (Signature)	Time: RZI			1 <i>1</i> )
2,3° 5	F OI	(OCSF			Received by Usignature	Time:			
Relinguisher by: (Signature Date: Time: Received for lab by: (Signature) Date: Time: Det Checked:	O/(	Ŭ,	5	2.300	220				
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	NCF: 18 of 18		Time:	Date:	Received for lab by: (Signature)	Time:	Date:	ire in the second s	Relinquisher by:(Signature

**Nogales Maintenance Yard** 



August 17, 2010

John Burton Engineering and Environmental Consultants, Inc. 7878 N. 16th Street Suite 140 Phoenix, AZ 85020

TEL (602) 248-7702 FAX 6022487851

RE: ADOT SW (Nogales)

Work Order No.: 10G0599 Order Name: 308032.07

Dear John Burton,

Turner Laboratories, Inc. received 1 sample(s) on 07/20/2010 for the analyses presented in the following report.

All results are intended to be considered in their entirety, and Turner Laboratories, Inc. is not responsible for use of less than the complete report. Results apply only to the samples analyzed. Samples will be disposed of 30 days after issue of our report unless special arrangements are made.

The pages that follow may contain sensitive, privileged or confidential information intended solely for the addressee named above. If you receive this message and are not the agent or employee of the addressee, this communication has been sent in error. Please do not disseminate or copy any of the attached and notify the sender immediately by telephone. Please also return the attached sheet(s) to the sender by mail.

Please call if you have any questions.

Respectfully submitted,

Turner Laboratories, Inc. ADHS License AZ0066

eni L. Harcia

Terri Garcia Technical Director

# Turner Laboratories, Inc.

Client: Project:	Engineering and Environmental Consultants, Inc ADOT SW (Nogales) Order: 308032.07				
Work Order: Date Received:	10G0599 07/20/2010	Work Order Sample Summary			
Lab Sample ID	Client Sample ID	Matrix	Collection Date/Time		

10G0599-01

Nogales ADOT SW

Storm Water

07/20/2010 1245

# Turner Laboratories, Inc.

Client:	Engineering and Environmental Consultants, Inc.	
Project:	ADOT SW (Nogales)	
Work Order:	10G0599	
Date Received:	07/20/2010	Case Narrative

E Value is above quantitation range.

- M7 The matrix spike recovery was below acceptance limits. Re-extraction and/or re-analysis confirms the low recovery.
- ND Not Detected at or above the PQL
- PQL Practical Quantitation Limit
- DF Dilution Factor

# Turner Laboratories, Inc.

Project: Work Order:	Engineering ar ADOT SW (N 10G0599 10G0599-01	nd Environmer ogales)	ntal Con	sultants	nts Client Sample ID: Nogales ADOT SW Collection Date/Time: 07/20/2010 1245 Matrix: Storm Water Order Name: 308032.07				
Analyses	R	Result	PQL	Qual	Units	DF	Prep Date	Analysis Date	Analyst
ICP Dissolved Metals-E	200.7								
Copper	N	D	0.020		mg/L	1	07/24/2010 1015	07/26/2010 134	l RAD
N-Hexane Extractable N	laterial (HEM)-I	E1664A							
Oil & Grease	5.	.30	5.00		mg/L	1	07/23/2010 0800	07/23/2010 1622	2 EW
ICP Total Metals-E200.7									
Copper	0.	.051	0.020		mg/L	1	07/26/2010 0815	07/29/2010 1137	7 RAD
Total Residual Chlorine-H8167									
Total Residual Chlorine	e 0.	.55	0.50	M7	mg/L	5	07/20/2010 1515	07/20/2010 1640	) GW
Total Dissolved Solids (F	Residue, Filterabl	le)-SM2540 C							
Total Dissolved Solids Filterable)	(Residue, 2	90	20		mg/L	1	07/22/2010 0840	07/27/2010 1125	5 GW
Total Suspended Solids (	Desidue Non Fil	Itanahla) SM254(	) D						
Total Suspended Solids		50	10		mg/L	1	07/22/2010 1125	07/23/2010 0920	) GW
A	<b>B</b> <i>C</i>								
Ammonia as N-SM4500 Nitrogen, Ammonia (A	·	ID	0.50		mg/L	1	07/21/2010 0730	07/22/2010 1130	) JM
Total Coliform & E. Col	i, MPN-SM92231	В							
E.Coli		400	1	Е	org/100 mL	. 1	07/20/2010 1450	07/21/2010 1550	) EW
Total Coliform	24	400	1	Е	org/100 mL			07/21/2010 1550	

Turner Laboratories W.O. #: <u>106-0 S99</u> Delivered by: <u>CIIENT</u>



1.	Shipping container/cooler in good condition?	Hes	🗆 No	🗌 Not Present
2.	Custody seals intact on sample bottles?	□ Yes	🗆 No	ENOT Present
3.	Chain of custody present?	Li Tes	∃No	
4.	COC agrees with sample labels?	Tes	🗆 No	
5.	Samples in proper container/bottle?	[] Yes	ETN0	
6.	Sample container intact?	Fres	🗆 No	
7.	Sufficient sample volume for requested tests?	1) Yes	🗆 No	
8.	Samples received within holding times?	Yes	⊡No	
9.	VOA vials received with no headspace?	🛾 Yes	🛛 No	-E No Vials
10.	Bacti bottles received with appropriate headspace?	Tes 🗆 Not Applic		∃ Above 100ml ∃ Below 100ml

Additional Comments: MPN COllecter By CLIENT THE REET OF SAMPLES POURED OVER BY LAB PERSONEL

2443 NORTH COYOTE DRIVE 📓 SUITE #104 🗎 TUCSON, ARIZONA 85745 🗉 520 882-5880 🖬 FAX # 520 882-9788

÷

# APPENDIX N Summary of EPA Audit Results



U.S. Environmental Protection Agency, Region 9 75 Hawthorne Street San Francisco, CA 94105-3901

## MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) COMPLIANCE AUDIT

# STATE OF ARIZONA DEPARTMENT OF TRANSPORTATION

# ADOT MS4 AUDIT REPORT

Audit Date: October 25–29, 2010

> Report Date: May 10, 2011

United States Environmental Protection Agency Region 9 75 Hawthorne Street San Francisco, CA 94105

#### CONTENTS

### Page

EXECUTIVE SU	UMMARY	iii
SECTION 1.0	BACKGROUND INFORMATION	1
SECTION 2.0	INFORMATION OBTAINED REGARDING COMPLIANCE WITH THE PERMIT	
SECTION 2.1	MEASURES TO CONTROL DISCHARGES THROUGH EDUCATION	
SECTION 2.2	ILLICIT DISCHARGE / ILLEGAL DUMPING DETECTION AND ELIMINATION	4
SECTION 2.3	POST-CONSTRUCTION STORM WATER MANAGEMENT	9
SECTION 2.4	STORM SEWER SYSTEM AND HIGHWAY MAINTENANCE	13
SECTION 2.5	MAINTENANCE FACILITIES MANAGEMENT: GOOD HOUSEKEEPING AND POLLUT	
	Prevention	
SECTION 2.6	CONSTRUCTION SITE STORMWATER MANAGEMENT	
SECTION 2.7	INDUSTRIAL FACILITIES MANAGEMENT	
SECTION 2.8	MONITORING PROGRAM	
APPENDIX A:	AUDIT SCHEDULE AND PARTICIPANTS	
APPENDIX B:	EXHIBIT LOG	
APPENDIX C:	CONSTRUCTION AND POST-CONSTRUCTION PROGRAM SITE VISIT	REPORTS

- APPENDIX D: MAINTENANCE AND INDUSTRIAL PROGRAM SITE VISIT REPORTS
- APPENDIX E: ADOT MS4 PERMIT (AZS000018-2008)
- APPENDIX F: ADOT STATEWIDE STORMWATER MANAGEMENT PLAN (SSWMP)

# **Executive Summary**

Between October 25 and 29, 2010, EPA contractor PG Environmental and representatives from the U.S. Environmental Protection Agency, Region 9 ("EPA") conducted an audit of the State of Arizona, Department of Transportation ("ADOT"), Municipal Separate Storm Sewer System (MS4) Program. The purpose of the audit was to assess compliance with the *Arizona Pollutant Discharge Elimination System* ("*AZPDES*") *Arizona Department of Transportation Statewide Permit for Discharges to Waters of the United States*, No. AZS000018-2008 ("Permit") and to evaluate ADOT's current implementation of its Statewide Stormwater Management Program ("SSWMP").

The EPA Audit Team evaluated four ADOT Districts: Phoenix, Flagstaff, Tucson and Prescott. The audit included document review, interviews, and field verification inspections at 57 ADOT construction sites and maintenance facilities. ADOT staff, including Headquarters and District program managers and construction and maintenance personnel participated extensively throughout the entire audit process. An ADOT headquarters session was held to obtain information regarding overall program management, program evaluation and oversight, and the MS4-related monitoring program. In addition, the EPA Audit Team held a closing conference at ADOT Headquarters on October 29, 2010, with representatives from headquarters and several Districts.

The audit team observed several positive elements of the ADOT MS4 Program, including:

- ADOT Environmental Management personnel demonstrated a thorough knowledge of Permit requirements and ADOT's SSWMP;
- ADOT had implemented sound monitoring and sampling practices at construction projects within <sup>1</sup>/<sub>4</sub>-mile of unique and sensitive waters; and
- The District Environmental Coordinators were knowledgeable of local stormwater features and maintenance issues and effectively communicated stormwater maintenance needs to ADOT staff.

This Program audit report also identifies program deficiencies and potential Permit violations; however, it is not a formal finding of violation. The following summarizes the most significant potential permit violations:

- ADOT had not fully implemented its Employee Stormwater Training Program;
- ADOT had not conducted dry-weather outfall screening of its 71 major MS4 outfalls;
- ADOT had not implemented an adequate illicit connection and illicit discharge detection and elimination program;
- ADOT had not conducted inspections of post-construction BMPs and had not implemented a system to inspect and track conditions of its MS4 system; and
- Inspections of ADOT facilities and construction sites revealed common housekeeping deficiencies, including improperly installed BMPs, inadequate containment of pollutant sources and uncertified or outdated Storm Water Pollution Prevention Plans.