

# Arizona Department of Transportation I-17, Drainage Improvements Peoria Avenue to Greenway Road

City of Phoenix Council Policy Session January 14, 2020



End Project Greenway Rd

Thunderbird Rd

Cactus Rd

Peoria Ave


Begin Project ACDC

## **Project Overview**

- Install a gravity drainage system from Greenway Road to Arizona Canal Diversion Channel (ACDC)
- Approximately 4 miles of large diameter pipe
- Remove 4 existing pumps stations



#### How a gravity drainage system works





# Need for the Project





# Need for the Project





### Main Project Features

- 23,800 LF of Pipe
- 2 Detention Basins (171,000 CY)
- ACDC Outlet Structure
- 4 Pump Stations Removed



### Storm Drain Installation



#### Storm Drain Pipe

- Reinforced Concrete Pipe (RCP)
- Trench Construction on Frontage Roads
- Depth of Pipe Varies from 10 ft to 30 ft
- Pipe Size Varies from 15-inch to 90-inch
- Slurry & Earth Backfill

#### 30" Jack and Bore Under I-17

Thunderbird Road

Retention Basins at Thunderbird Road



### ACDC – Outlet System



#### Junction Structure Outfall Tie In

- Required US Army Corps of Engineers (USACE) Section 408
   Permit
- Required Flood Control District of Maricopa County (FCDMC)
  Right-of-Way Use Permit



### **Project Cost**

- Design and Construction -\$38.2M
- Temporary Construction
   Easements \$124K





### Construction

- Contract awarded to Fischer Contracting, Inc. on 9/23/2019
- Preconstruction/Partnering Meeting held on 11/7/2019
- Construction Start 01/21/2020
- Construction Duration 20 months
- ADOT Resident Engineer Jimmy Naujokaitis



### **Construction Sequencing**

- Phase 1 ACDC to Peoria Ave (4 months)
- Phase 2 Peoria Ave to Cactus Rd (3 months)
- Phase 3 Cactus Rd to Thunderbird Rd (6 months)
- Phase 4 Thunderbird Rd to Greenway Rd (7 months)



### **Road Closures**

### I-17 Frontage Roads

Close one Segment

### Crossroads

- One crossroad per weekend
- 9:00pm Fridays 5:00am Mondays
- Coordination Required with City of Phoenix
- Liquidated Damages





# Public Outreach So Far (Design)

- News media
- Developed and maintained project web page
- Distributed informational fliers
- Presented at HOA meeting
- Participated in a community event at Metro Center Mall
- Met with Councilwoman Stark



### Public Outreach Moving Forward (Construction)


- Gunn Communications, Inc. hired to assist with public outreach
- News and social media announcements
- Distribute informational fliers
- Maintain project web page with critical construction info
- Send email alerts
- Presentation to the Village Planning Committee and/or HOA if requested
- Business outreach business walk and initial outreach and regular interaction/check-ins



### Staying Informed

Web Site: <a href="https://azdot.gov">https://azdot.gov</a>

Subscribe to receive project updates and traffic alerts during construction



**Bilingual Project Information Line: 855.712.8530**